



County of Los Angeles Department of Public Works

**Stormwater Best Management Practice
Design and Maintenance Manual**

**For Publicly Maintained
Storm Drain Systems**

May 2009

THIS PAGE INTENTIONALLY LEFT BLANK

Table of Contents

1. INTRODUCTION.....	1-1
PURPOSE.....	1-1
OTHER STORMWATER BMP SELECTION AND DESIGN MANUALS.....	1-1
CONTENT AND ORGANIZATION OF THIS MANUAL.....	1-2
GENERAL CONSIDERATIONS.....	1-2
<i>Maintenance Responsibility</i>	<i>1-2</i>
<i>Pretreatment</i>	<i>1-3</i>
<i>Infiltration</i>	<i>1-3</i>
<i>Biofiltration.....</i>	<i>1-4</i>
<i>Bioretention.....</i>	<i>1-4</i>
<i>Filtration.....</i>	<i>1-4</i>
<i>Wetpools.....</i>	<i>1-4</i>
<i>Oil/Water Separation</i>	<i>1-5</i>
<i>"On-line" and "Off-line" Facilities</i>	<i>1-5</i>
<i>Hydromodification Control.....</i>	<i>1-6</i>
<i>Unit Process-Based BMP Selection and Design</i>	<i>1-7</i>
2. DRY EXTENDED DETENTION BASINS.....	2-1
DEFINITION	2-1
GENERAL CONSTRAINTS AND SITING CONSIDERATIONS	2-1
MULTI-USE OPPORTUNITIES.....	2-1
DRY EXTENDED DETENTION BASIN DESIGN SPECIFICATIONS	2-2
<i>Basin Sizing and Geometry.....</i>	<i>2-2</i>
<i>Soils Considerations</i>	<i>2-2</i>
<i>Energy Dissipation.....</i>	<i>2-3</i>
<i>Forebay.....</i>	<i>2-3</i>
<i>Vegetation.....</i>	<i>2-3</i>
<i>Outlet Structure and Drawdown Time</i>	<i>2-4</i>
<i>Emergency Spillway.....</i>	<i>2-6</i>
<i>Side Slopes.....</i>	<i>2-7</i>
<i>Embankments.....</i>	<i>2-7</i>
<i>Fencing</i>	<i>2-8</i>
<i>Right-of-Way</i>	<i>2-8</i>
<i>Maintenance Access</i>	<i>2-8</i>
<i>Landscaping</i>	<i>2-9</i>
<i>Restricted Construction Materials.....</i>	<i>2-9</i>
DRY EXTENDED DETENTION BASINS MAINTENANCE STANDARDS	2-14
<i>General Requirements.....</i>	<i>2-14</i>
<i>Maintenance Standards.....</i>	<i>2-15</i>
3. VEGETATED SWALES	3-1
DEFINITION	3-1
GENERAL CONSTRAINTS AND SITING CONSIDERATIONS	3-1
MULTI-USE OPPORTUNITIES.....	3-1
VEGETATED SWALE DESIGN SPECIFICATIONS.....	3-2
<i>Geotechnical Considerations.....</i>	<i>3-2</i>
<i>Sizing.....</i>	<i>3-2</i>
<i>Swale Geometry.....</i>	<i>3-5</i>
<i>Bottom Slope.....</i>	<i>3-6</i>
<i>Water Depth and Dry Weather Flow Drain.....</i>	<i>3-6</i>
<i>Energy Dissipation.....</i>	<i>3-6</i>

<i>Flow Spreaders</i>	3-7
<i>Check Dams</i>	3-8
<i>Underdrains</i>	3-8
<i>Swale Divider</i>	3-9
<i>Soils</i>	3-9
<i>Vegetation</i>	3-9
<i>Restricted Construction Materials</i>	3-11
VEGETATED SWALE MAINTENANCE STANDARDS	3-14
<i>General Requirements</i>	3-14
<i>Maintenance Standards</i>	3-15
4. FILTER STRIPS	4-1
DEFINITION	4-1
GENERAL CONSTRAINTS AND SITING CONSIDERATIONS	4-1
MULTI-USE OPPORTUNITIES	4-1
FILTER STRIP DESIGN SPECIFICATIONS	4-1
<i>Location</i>	4-1
<i>Tributary Area Length</i>	4-2
<i>Sizing</i>	4-2
<i>Geometry</i>	4-3
<i>Energy Dissipation / Level Spreading</i>	4-3
<i>Access</i>	4-4
<i>Water depth and Velocity</i>	4-4
<i>Soils</i>	4-4
<i>Vegetation</i>	4-5
<i>Restricted Construction Materials</i>	4-5
FILTER STRIP OPERATIONS AND MAINTENANCE	4-7
<i>General Requirements</i>	4-7
<i>Maintenance Standards</i>	4-7
5. BIORETENTION	5-1
DEFINITION	5-1
GENERAL CONSTRAINTS AND SITING CONSIDERATIONS	5-1
MULTI-USE OPPORTUNITIES	5-1
BIORETENTION DESIGN SPECIFICATIONS	5-1
<i>Geotechnical and Landscape Considerations</i>	5-1
<i>Pretreatment</i>	5-2
<i>Sizing Criteria</i>	5-2
<i>Geometry</i>	5-5
<i>Flow Entrance and Energy Dissipation</i>	5-5
<i>Underdrains</i>	5-5
<i>Overflow</i>	5-7
<i>Hydraulic Restriction Layers</i>	5-7
<i>Planting/Storage Media</i>	5-7
<i>Plants</i>	5-9
<i>Restricted Construction Materials</i>	5-10
BIORETENTION OPERATIONS AND MAINTENANCE	5-12
<i>General Requirements</i>	5-12
<i>Maintenance Standards</i>	5-13
6. INFILTRATION FACILITIES	6-1
DEFINITION	6-1
GENERAL CONSTRAINTS AND SITING CONSIDERATIONS	6-1

MULTI-USE OPPORTUNITIES	6-2
INFILTRATION FACILITY DESIGN SPECIFICATIONS	6-2
<i>Geotechnical Considerations</i>	6-2
<i>Site Geotechnical Investigation</i>	6-3
<i>Setbacks</i>	6-3
<i>Pretreatment</i>	6-3
<i>Sizing Criteria</i>	6-4
<i>Facility Geometry</i>	6-6
<i>Embankments</i>	6-7
<i>Additional Control Functions</i>	6-7
<i>Drainage</i>	6-8
<i>Emergency Overflow</i>	6-8
<i>Vegetation</i>	6-8
<i>Maintenance Access</i>	6-9
<i>Construction</i>	6-10
<i>Landscaping</i>	6-10
<i>Restricted Construction Materials</i>	6-11
INFILTRATION FACILITY OPERATIONS AND MAINTENANCE	6-14
<i>General Requirements</i>	6-14
<i>Maintenance Standards</i>	6-16
7. STORMWATER WETLAND BASINS.....	7-1
DEFINITION	7-1
GENERAL CONSTRAINTS AND SITING CONSIDERATIONS	7-1
MULTI-USE OPPORTUNITIES	7-2
STORMWATER WETLAND BASIN DESIGN SPECIFICATIONS.....	7-2
<i>Basin Sizing and Geometry</i>	7-2
<i>Water Supply</i>	7-3
<i>Soils Considerations</i>	7-3
<i>Buffer Zone</i>	7-4
<i>Energy Dissipation</i>	7-4
<i>Vegetation</i>	7-4
<i>Outlet Structure and Spillway</i>	7-4
<i>Side Slopes</i>	7-5
<i>Embankments</i>	7-5
<i>Fencing</i>	7-6
<i>Right-of-Way</i>	7-6
<i>Maintenance Access</i>	7-6
<i>Landscaping Outside of the Facility</i>	7-7
<i>Restricted Construction Materials</i>	7-7
STORMWATER WETLAND BASIN MAINTENANCE STANDARDS.....	7-11
<i>General Requirements</i>	7-11
<i>Maintenance Standards</i>	7-12
8. SAND FILTERS	8-1
DEFINITION	8-1
GENERAL CONSTRAINTS AND SITING CONSIDERATIONS	8-1
SAND FILTER DESIGN SPECIFICATIONS	8-1
<i>Basin Sizing and Geometry</i>	8-1
<i>Sizing Methodology</i>	8-2
<i>Sand Specification</i>	8-4
<i>Underdrains</i>	8-5
<i>Pretreatment</i>	8-6

<i>Flow Spreading</i>	8-6
<i>Vegetation</i>	8-7
<i>Emergency Overflow Structure</i>	8-7
<i>Side Slopes</i>	8-7
<i>Embankments</i>	8-7
<i>Fencing</i>	8-8
<i>Right-of-Way</i>	8-8
<i>Maintenance Access</i>	8-8
<i>Landscaping Outside of the Facility</i>	8-9
<i>Restricted Construction Materials</i>	8-9
SAND FILTER MAINTENANCE STANDARDS	8-11
<i>General Requirements</i>	8-11
<i>Maintenance Standards</i>	8-11
9. PROPRIETARY DEVICES	9-1
DEFINITION	9-1
GENERAL DESIGN SPECIFICATIONS	9-2
EXPECTED PERFORMANCE	9-2
SIZING	9-3
OPERATION AND MAINTENANCE	9-3
<i>Hydrodynamic Separation Devices</i>	9-3
<i>Catch Basin Inserts</i>	9-4
<i>Cartridge filters</i>	9-4
<i>Biotreatment Devices</i>	9-4
ONLINE RESOURCES	9-4
10. REFERENCES	10-1
11. ACKNOWLEDGMENTS	11-1
DOCUMENT PREPARATION TEAM	11-1
SPECIAL ACKNOWLEDGEMENT	11-1

Appendix A	Glossary
Appendix B	BMP Sizing Worksheets
Appendix C	Pond Outlet Sizing Examples
Appendix D	Flow Splitter Design Specification
Appendix E	Facility Inspection
Appendix F	Facility Inspection and Maintenance Checklists
Appendix G	Policy for New Percolation Basin Testing, Design, and Maintenance

List of Tables

Table 1-1: Unit Operations and Processes Provided by Common BMPs and BMP Components.	1-9
Table 1-2: BMP Practicability Screening Matrix	1-10
Table 2-1: Dry Extended Detention Pond Routine and Major Maintenance Quick Guide.....	2-15
Table 2-2: Routine Maintenance Standards - Extended Detention Basins	2-16
Table 2-3: Major Maintenance Standards - Extended Detention Basins	2-17
Table 3-1: Vegetated Swale Routine and Major Maintenance Quick Guide.....	3-15
Table 3-2: Routine Maintenance Standards - Vegetated Swales.....	3-16
Table 3-3: Major Maintenance Standards - Vegetated Swales.....	3-17
Table 4-1: Filter Strip Routine and Major Maintenance Quick Guide	4-8
Table 4-2: Routine Maintenance – Filter Strips	4-8
Table 4-3: Major Maintenance – Filter Strips	4-9
Table 5-1: Bioretention Routine and Major Maintenance Quick Guide	5-13
Table 5-2: Routine Maintenance – Bioretention	5-14
Table 5-3: Major Maintenance – Bioretention	5-15
Table 6-1: Infiltration Facility Routine and Major Maintenance Quick Guide.....	6-16
Table 6-2: Routine Maintenance – Infiltration Facilities	6-17
Table 6-3: Major Maintenance – Infiltration Facilities	6-18
Table 7-1: Recommended Distribution of Depths in Wetland Basin	7-3
Table 7-2: Wetland Basin Routine and Major Maintenance Quick Guide	7-12
Table 7-3: Routine Maintenance Standards – Stormwater Wetland Basins	7-13
Table 7-4: Major Maintenance Standards – Stormwater Wetland Basins	7-14
Table 8-1: Sand filter Routine and Major Maintenance Quick Guide	8-11
Table 8-2: Routine Maintenance – Sand Filters.....	8-12
Table 8-3: Major Maintenance – Sand Filters.....	8-13
Table 9-1: Proprietary Device Manufacturer Websites	9-5

List of Figures

Figure 1-1: Difference Between On-line, Off-line, and In-stream Controls.	1-6
Figure 2-1: Detention Pond.....	2-10
Figure 2-2: Perforated Riser Outlet.....	2-11
Figure 2-3: Multiple Orifice Outlet	2-12
Figure 2-4: Spillway.....	2-13
Figure 3-1: Vegetated Swale.....	3-12
Figure 3-2: Flow Spreader and Check Dam	3-13
Figure 4-1: Filter Strip	4-6
Figure 5-1: Bioretention Area	5-11
Figure 6-1: Infiltration Basin	6-12
Figure 6-2: Infiltration Trench.....	6-13
Figure 7-1: Stormwater Wetland Basin	7-8
Figure 7-2: Riser Outlet	7-9
Figure 7-3: Inverted Pipe Outlet.....	7-10
Figure 8-1: Sand Filter.....	8-10

1. INTRODUCTION

Purpose

Stormwater treatment best management practices (BMPs) are an integral part of stormwater management plans for new development and significant redevelopment projects. Certain new development and redevelopment projects are required to submit drainage concept and stormwater quality plans that show details of treatment facilities designed to mitigate potential impacts to surface water and groundwater quality. These treatment facilities can be either privately or publicly maintained. The purpose of this BMP design and maintenance manual is to provide design criteria and guidelines for developers, to assist the County in the review and approval of stormwater treatment BMP designs, and to provide guidance on BMP maintenance requirements for those devices that will be publicly maintained.

Other Stormwater BMP Selection and Design Manuals

Three previous stormwater BMP manuals have been published by the County of Los Angeles Department of Public Works:

1. Development Planning for Stormwater Management – A Manual for the Standard Urban Stormwater Mitigation Plan (SUSMP), dated September 2002, prepared by the LACDPW; and
2. Technical Manual for Stormwater Best Management Practices in the County of Los Angeles, draft dated February 2004, prepared by the LACDPW.
3. Los Angeles County-Wide Structural BMP Prioritization Methodology, dated April 2006, prepared by Geosyntec Consultants and Heal the Bay.

These three manuals were designed to assist the development community in Los Angeles County in selecting and designing site-specific post-construction BMPs to minimize pollutant impacts from urban stormwater runoff. These manuals also describe the legal framework for the development planning program within the County of Los Angeles. In contrast, this manual does not provide information on plan submittal requirements, but instead provides detailed guidance on BMP sizing, design specifications, and maintenance requirements. The design specifications contained in this manual were based on and are consistent with the general design principles contained in the three previous LACDPW manuals.

California Stormwater Quality Association (CASQA) released four Stormwater Best Management Practice Handbooks in January 2003. The design guidance contained in the New Development and Redevelopment Best Management Practice Handbook was also used in the preparation of this manual.

Design specifications were also drawn from a number of other sources:

- King County Surface Water Design Manual, King County Department of Natural Resources, Seattle, Washington. August 2005.

- Technical Guidance Manual for Stormwater Quality Control Measures, Ventura Countywide Stormwater Quality Management Program. July 2002.
- Hydrology Manual, Los Angeles County Department of Public Works. January 2006.
- Design Manual - Debris Dams and Basins, Los Angeles County Flood Control District. October, 1979.
- Design Manual - Hydraulic, Los Angeles County Flood Control District. March 1982.

Content and Organization of this Manual

Chapter 1 serves as an introduction and summarizes available options for treatment of stormwater. Chapters 2 - 10 provide design specifications and maintenance guidance for specific types of treatment. The appendices include a glossary (Appendix A); sample worksheets for BMP sizing (Appendix B); design specifications for flow diversion structures (Appendix C); facility inspection procedures (Appendix D); facility inspection and maintenance checklists (Appendix E); and the Policy for New Percolation Basin Testing, Design, and Maintenance dated October 10, 2007 (Appendix F).

General Considerations

Runoff treatment facilities are designed to remove pollutants contained in stormwater runoff. The pollutants of concern, depending on the watershed, may include trash, debris, and sediment; metals such as copper, lead, and zinc; nutrients (e.g., nitrogen and phosphorous); certain bacteria and viruses; mineral salts such as chloride; and organic chemicals such as petroleum hydrocarbons and pesticides. Methods of pollutant removal include sedimentation/settling, filtration, plant uptake, ion exchange, adsorption, and microbially-mediated decomposition. Floatable pollutants such as oil, debris, and scum can be removed with separator structures. Runoff treatment facilities can also be designed to reduce runoff volume, thereby reducing pollutant loading to receiving waters. Runoff treatment facility types and common terms used in runoff treatment are discussed below.

Maintenance Responsibility

Maintenance is required for all types of runoff treatment facilities. Upon acceptance into the Flood Control District, LACDPW will assume operation and maintenance responsibilities for the BMPs contained in this manual. The devices shall be placed within public right-of-ways or Flood Control District easements.

The primary purpose of BMPs is water quality treatment. However, an ancillary benefit of certain BMPs is the provision of habitat for aquatic and terrestrial wildlife. The quality and extent of such habitat may be affected by maintenance activities required to ensure the continued water quality performance of the BMP. In situations where there is potential for habitat to attract threatened or endangered species, the project proponent must coordinate with and develop written agreements with the California Department of Fish and Game or the US Fish and Wildlife service. These agreements must ensure that the BMPs are considered treatment facilities and not waters of the United States, and that long term operation and maintenance requirements are acceptable to these agencies.

Pretreatment

Pretreatment must be provided for filtration and infiltration facilities, and other facilities whose function could be adversely affected by sediment or other pollutants. Pretreatment may also be provided for water quality detention basins and other BMPs to facilitate the routine removal of sediment, trash, and debris, and to increase the longevity of the downstream BMPs. Runoff from undeveloped hillsides and canyons should be routed to debris basins in compliance with County requirements and, where feasible, routed around downstream treatment BMPs.

Pretreatment may be provided by presettling basins or forebays (small detention basins), vegetated swales, filter strips, hydrodynamic separators, and catch basin inserts. Debris controls as described in the Los Angeles County Sedimentation Manual may also be appropriate for pretreatment. Source control activities, implemented per the SUSMP requirements, minimize the introduction of pollutants into stormwater runoff and also help to protect filtration and infiltration facilities. Effort should be made early in the site planning stages to minimize runoff from impervious areas by grading toward landscaped areas, disconnecting downspouts, and using pervious conveyances prior to discharging to the storm drain system. These low impact development (LID) practices can reduce the size and maintenance burden of downstream, end-of-pipe BMPs.

Infiltration

Infiltration refers to the use of the filtration, adsorption, and biological decomposition properties of soils to remove pollutants prior to the intentional routing of runoff to the subsurface for groundwater recharge. Infiltration BMPs include infiltration basins and trenches. Infiltration can provide multiple benefits, including pollutant removal, peak flow control, groundwater recharge, and flood control. However, conditions that can limit the use of infiltration include soil properties and potential adverse impacts on groundwater quality. To adequately address the protection of groundwater when evaluating infiltration, site soils must be determined to be suitable by conducting a geotechnical investigation that includes an in-situ percolation test, per the Policy for New Percolation Basin Testing, Design, and Maintenance (October 10, 2007, or as amended (provided in Appendix G)) and determination of minimum depth to groundwater. Soils must have sufficient organic content and sorption capacity to remove certain pollutants, but must be coarse enough to infiltrate runoff in a reasonable amount of time (e.g., < 72 hours). Examples of suitable soils are silty and sandy loams. Coarser soils, such as gravelly sands, have limited organic content and high permeability and therefore present a potential risk to groundwater from certain pollutants, especially in areas of shallow groundwater. NPDES permits often specify a water table distance separation of ten feet depth or more to protect groundwater quality. These permits also specify that infiltration BMPs are not allowed for areas of industrial activity or areas subject to high vehicular traffic (25,000 or greater average daily traffic (ADT) on the main roadway or 15,000 or more ADT on any intersecting roadway), nor are they allowed within 100 feet from any drinking water well unless appropriate pretreatment for the pollutants of concern is provided.

Incidental infiltration that occurs in other types of BMPs, such as dry extended detention basins, vegetation swales, filter strips, and bioretention areas, generally pose a lesser risk to groundwater quality as treatment is provided in the BMP prior to infiltration.

Biofiltration

Biofiltration utilizes vegetation in conjunction with slow and shallow-depth flow for runoff treatment. As runoff passes through the vegetation, the combined effects of filtration, infiltration, adsorption, and biological uptake remove pollutants. Vegetation also decreases the velocity of flow and allows for particulates to settle. Biofiltration facilities include both vegetated swales, which are designed to convey and treat concentrated runoff flowing at shallow depths and slow velocities, and filter strips, which are broad areas of turf grasses or other vegetation designed for treating sheet flow runoff from adjacent impervious surfaces.

Bioretention

Bioretention areas are vegetated (i.e., landscaped) shallow depressions that provide storage, infiltration, and evapotranspiration, and also provide for pollutant removal (e.g. filtration, adsorption, nutrient uptake) by filtering stormwater through the vegetation and soils. In bioretention areas, as in biofiltration BMPs, pore spaces and organic material in the soils help to retain water in the form of soil moisture and to promote the adsorption of pollutants (e.g., dissolved metals and petroleum hydrocarbons) into the soil matrix. Plants utilize soil moisture, promote the drying of the soil through transpiration, and uptake pollutants in their roots and leaves. Plants with extensive root systems also help to maintain filtration rates. Where bioretention facilities are underlain by highly infiltrative soils, an underdrain is not necessary. Underdrains may be used where space is limited (underdrains allow for a smaller bioretention area footprint), where low infiltrative soils are present, or to minimize ponding.

Filtration

Various media, such as sand, perlite, zeolite, compost, and activated carbon, can be used to effectively remove total suspended solids (TSS) and associated pollutants such as organics (hydrocarbons and pesticides) and particulate metals in filtration BMPs. Filtration systems can be configured in the form of horizontal beds, trenches, or lastly, cartridge systems in underground vaults or catch basins.

Wetpools

A wetpool is a permanent pool of water incorporated into a wetpond, stormwater lake, or stormwater wetland BMP.¹ Wetpools provide runoff treatment by allowing settling of particulates (sedimentation), by biological uptake, and by vegetative filtration (if vegetation is present). Wetpool BMPs may be single-purpose facilities, providing only runoff treatment, or they may also provide flow control by providing additional detention storage with the use of a multi-stage outlet structure. If combined with detention, the wetpool volume can often be stacked under the detention volume with little further loss of development area.

¹ Wetponds are constructed, naturalistic ponds with a permanent or seasonal pool of water. Stormwater lakes are a special form of wetpond designed to provide stormwater quality management. Stormwater wetland basins are a treatment system consisting of a sediment forebay and a permanent micro-pool with aquatic vegetation covering a significant portion of the basin. Wetponds and lakes will not be publicly maintained; stormwater wetland basins will be publicly maintained (see Section 7).

Oil/Water Separation

Oil/water separators (also called "water quality inlets") remove floating oil from the surface of the water. There are two general types of separators - American Petroleum Institute (API) separators and coalescing plate (CP) separators. Both types use physical mechanisms to remove high concentrations of floating and dispersed oil. Oil/water separators are not suitable for the relatively low concentrations of petroleum hydrocarbons present in typical urban runoff, and should only be used in locations where higher concentrations of oil are expected to occur, such as retail fuel facilities, high volume roads, and petroleum-related industrial facilities. Oil/water separators must be located off-line from the primary conveyance system, as they function at low flow conditions and will wash out in high flow conditions. Other oil control devices/facilities that may be used for removal of slightly elevated concentrations of oil (i.e., typical of high use commercial parking lots) include catch basin inserts, hydrodynamic devices, and linear sand filters. Oil control devices/facilities should always be placed upstream of other treatment facilities and as close to the source of oil generation as possible.

"On-line" and "Off-line" Facilities

The location and configuration of control facilities can vary depending on the desired function. For example, debris basins are often located in a drainage channel so as to collect solids and wood debris from the upstream portion of the watershed prior to entering a storm drain system. Such facilities may be referred to as "in-stream" controls.

On the other hand, runoff treatment facilities cannot be located in Waters of the US, but rather are located upland to treat runoff prior to discharge into Waters of the US. Such facilities are generally located within the development as part of the storm drain system. If the facility is located in the storm drain system such that all the runoff passes through the facility, the facility is called an "on-line" system. If, on the other hand, the facility only receives lower flows (defined as those less than or equal to the water quality design flow) that are diverted from the main storm drain line, the facility is called an "off-line" system. Off-line systems therefore require a flow splitter or equivalent device to be installed in the main storm drain line. Generally treatment performance is better for off-line facilities because a larger percentage of the runoff is treated. Figure 1-1 illustrates the difference between on-line, off-line, and in-stream controls.




Figure 1-1: Difference Between On-line, Off-line, and In-stream Controls.

Hydromodification Control

As defined by the State Water Resources Control Board (2006), "hydromodification is the alteration of stream and river channels, installation of dams and water impoundments, and streambank and shoreline erosion." Urban development results in hydromodification by increasing runoff volume and the frequency and duration of flows. This alteration in the flow regime increases sediment transport capacity and, depending on sediment supply and channel conditions, can cause stream bank and stream bed erosion. Hydromodification control can be achieved through one or a combination of the following three approaches:

- Avoid, to the extent possible, the need to mitigate for hydromodification impacts by preserving natural hydrologic conditions and protecting sensitive hydrologic features, sediment sources, and sensitive habitats.

- Minimize the effects of development through site design practices (e.g., reducing connected impervious surfaces), implementation of stormwater volume-reducing BMPs (project-based hydrologic source control), and incorporation of flow duration control into water quality treatment BMPs such as extended detention basins and infiltration basins, as needed.
- Mitigate hydromodification impacts in-stream using geomorphically-based channel design.

Unit Process-Based BMP Selection and Design

As opposed to other design approaches that recommend the selection of typical BMPs based solely on documented performance factors, such as percent removal, effluent quality and/or percent capture, the design approach contained herein recommends the selection of the unit operations and processes (UOPs) that address the pollutants of concern and then selection of BMPs and/or BMP design components that incorporate those UOPs.

UOPs can be divided into four fundamental process categories: 1) hydrologic operations, 2) physical operations, 3) biological processes, and 4) chemical processes (Strecker et al., 2005). Hydrologic operations are essentially a subset of physical operations and include the principles of flow attenuation (e.g., peak shaving and detention) and volume reduction (e.g., infiltration and evapotranspiration). Physical operations, as referred to herein, include the principles of size separation and exclusion (e.g., screening and filtration), density separation (e.g., sedimentation and flotation), aeration and volatilization, and physical agent disinfection (e.g., ultra-violet light and heat). Biological processes include the principles of microbially-mediated transformations (e.g., redox reactions resulting from microbial respiration) and uptake and storage (e.g., bioassimilation). Chemical processes include the principles of sorption (e.g., ion exchange and surface complexation), coagulation and flocculation (e.g., particle agglomeration and precipitation), and chemical agent disinfection (e.g., chlorination and ozonation). The selection of any one of these UOPs should be based on the type and form (speciation) of the target pollutants in relation to specific stormwater management goals.

Most treatment facilities include more than one UOP. For example, dry extended detention basins may reduce the total runoff volume due to infiltration and evapotranspiration (ET), as well as attenuate peak flows, which causes particulates to settle out. Furthermore, some BMPs can be modified to include unit processes that are typically not incorporated in their design, such as including amended soils to promote infiltration in a vegetated swale. Consequently, several BMPs may include multiple unit processes, and in order to exploit the synergy amongst BMPs, the placement or order of BMPs and BMP components within a treatment system should be carefully considered. The recommended approach is to use the concept of the treatment train based on the following general progression:

1. Minimize flow rates and/or volume of runoff (site design practices and hydrological source control).
2. Remove bulk solids ($> 5\text{mm}$) (primary treatment)
3. Remove settleable solids ($>75\ \mu\text{m}$) and liquid floatables (primary treatment)
4. Remove suspended ($25\text{-}75\ \mu\text{m}$) and colloidal solids ($> 0.1\text{-}25\ \mu\text{m}$) (secondary treatment)
5. Remove colloidal, dissolved, volatile, and pathogenic constituents (tertiary treatment)

It is important to note that some stormwater BMPs, such as vegetated swales, may be used as either primary and/or secondary components of a treatment train. Furthermore, tertiary treatment may be provided in BMPs that provide secondary treatment, such as constructed wetlands. Therefore, it may be more useful to categorize BMPs (and their components) according to the unit treatment processes that they provide. Table 1-1 provides a guide for linking unit treatment processes and target pollutants to stormwater BMPs. The choice of BMP should be driven by the target pollutants and the UOPs needed to address those pollutants.

Table 1-2 is a BMP practicability screening matrix that can be used to assist in the selection of BMPs for a particular site. The table briefly summarizes the critical design parameters, typical pollutants removed, major constraints, and maintenance requirements for the BMPs included in this manual. For detailed guidance on BMP selection and siting that considers pollutants of concerns, site conditions, and constraints refer to the following recent documents:

- Los Angeles County-Wide Structural BMP Prioritization Methodology (Geosyntec, 2006); <http://labmpmethod.org/>
- Critical Assessment of Stormwater Treatment and Control Selection Issues (Strecker et al., 2005); <https://www.werf.us/products/products.cfm>.

Table 1-1: Unit Operations and Processes Provided by Common BMPs and BMP Components.

Fundamental Process Category (FPC)	Unit Operation or Process (UOP) <i>Target Pollutants</i>	Common BMPs/BMP Components
Hydrologic Operations	Flow and Volume Attenuation	Dry extended detention basins Wet ponds Stormwater wetland basins
	Volume Reduction <i>All pollutant loads</i>	Infiltration facilities Dry extended detention basins Bioretention Vegetated swales Filter strips
Physical Treatment Operations	Physical Sorption <i>Nutrients, metals, petroleum compounds</i>	Bioretention Infiltration facilities Sand filters Engineered media / granular activated carbon
	Size Separation and Exclusion (screening and filtration) <i>Coarse sediment, trash, debris</i>	Screens/bars/trash racks Bioretention Vegetated swales Filter strips Sand filters Infiltration facilities Proprietary filters Hydrodynamic separators Catch basin inserts (i.e., surficial filters)
	Density, Gravity, Inertial Separation (grit separation, sedimentation, flotation and skimming, and clarification) <i>Sediment, trash, debris, oil and grease</i>	Dry extended detention basins Wet ponds Wetland basins Settling basins Swales with check dams Oil-water separators Hydrodynamic separators
	Aeration and Volatilization <i>Oxygen demand, PAHs, VOCs</i>	Sprinklers Aerators
	Natural Disinfection <i>Pathogens</i>	Shallow detention ponds Ultra-violet systems
	Microbially Mediated Transformation (can include oxidation, reduction, or facultative processes) <i>Metals, nutrients, organic pollutants</i>	Wetland basins Bioretention Wet ponds Proprietary filters (e.g. compost)
Chemical Processes	Uptake and Storage <i>Metals, nutrients, organic pollutants</i>	Wetlands basins Bioretention Wet ponds
	Chemical Sorption Processes <i>Metals, nutrients, organic pollutants</i>	Infiltration facilities Sand filters Subsurface wetlands Proprietary filters (e.g. compost)
	Coagulation/Flocculation <i>Fine sediment, nutrients</i>	Dry extended detention basins Wet ponds Wetland basins Coagulant/flocculent injection systems
	Ion Exchange <i>Metals, nutrients, mineral salts</i>	Engineered media, zeolites, peats, surface complexation media
	Chemical Disinfection <i>Pathogens</i>	Custom devices for mixing chlorine or aerating with ozone Advanced treatment systems

Table 1-2: BMP Practicability Screening Matrix

BMP Type	Critical Design Parameters	Typical Pollutants Removed	Major Constraints	Maintenance Requirements
Extended Detention Basin	Stage-discharge relationship (outlet design); Storage capacity; Length to width ratio; Flow rate diversion for off-line facilities	High removal efficiency of coarse solids, trash and debris. Moderate removal of suspended sediment. Little to no predicted removal of dissolved metals and nutrients.	Surface space availability; Depth of excavation; Slope stability; Compatibility with flood control	Dredging of forebay required approximately every 5 years with reestablishment of pond bottom; Frequent mowing; Side slope upkeep; Trash and debris removal; Periodic inspections
Swale	Retention time; Minimum length; Maximum width; Flow rate, velocity, & depth; No. of check dams; Grass selection	High removal efficiency of coarse solids, trash, and debris. Moderate removal of suspended sediment. Variable removal of nutrients and metals.	Steep terrain; Availability of pervious area; Size of tributary area; High flows	Seasonal mowing and vegetation upkeep required; Sediment removal when exceeds 4 inches in any location; Periodic inspections
Filter Strip	Retention time; Minimum length; Longitudinal slope; Flow rate, velocity, & depth; Grass selection	High removal efficiency of coarse solids, trash, and debris. Moderate removal of suspended sediment. Limited removal of nutrients and metals.	Steep terrain; Availability of pervious area; Ability to maintain sheet flow; Size of tributary area; High flows	Seasonal mowing and vegetation upkeep required; Sediment removal when exceeds 4 inches in any location; Periodic regrading and reseeding; Periodic inspections
Bioretention	Soil characteristics and amendments; Depth to groundwater; Storage capacity; Plant selection	High removal efficiency of coarse solids, trash, and debris. Moderate removal of suspended sediment and metals. Variable removal of nutrients.	Field infiltration rate; Depth to groundwater; Contaminated soils; Proximity to storm drain; Vertical relief and proximity to storm drain; Surface space availability;	Semiannual, annual, and post-storm inspections; Vegetation upkeep; Periodic surface scarification and sediment removal
Infiltration Facilities	Min/Max infiltration rate; Depth to groundwater; Storage capacity	High removal efficiency of coarse solids, particulate and suspended sediment. Moderate removal of phosphorus/nitrogen. Dissolved metals and pathogen removal dependent on soil types.	Field infiltration rate; Depth to groundwater; Contaminated soils; Proximity to structures; Large drainage area	Semiannual/ annual and post-storm inspections; Vegetation upkeep; Periodic surface scarification and sediment removal;
Wetponds	Length to width ratio; Stage-discharge relationship; Permanent pool and surcharge capacity; Maximum depth; Base flow; Plant selection; Flow rate diversion for off-line facilities	High removal efficiency of coarse solids, suspended solids, trash, and debris. Some removal of dissolved solids, total phosphorus, soluble nutrients, trace metals, coliform and organics.	Surface space availability; Depth of excavation; Compatibility with flood control; Vector control	Dredging required approximately every 5 years with reestablishment of pond bottom; Side slope upkeep; Trash and debris removal; Periodic inspections; Removal of algal mats and control of fringe vegetation;
Stormwater Wetland	Volume of design storm; Length to width ratio; Depth distribution; Base flow; Plant selection; Flow rate diversion for off-line facilities	High removal efficiency of coarse solids, suspended sediment, trash and debris. Moderate removal of metals. Variable removal of phosphorus/nitrogen.	Surface space availability; soil type; System hydraulics; Vector control; Lack of base flow	Monthly inspections required until vegetation is established; Periodic removal of nuisance species and litter as required
Sand Filter	Maximum emptying time; Media depth; Particle size gradation; Depth to groundwater	High removal efficiency of coarse solids, suspended sediment, and metals. Some removal of nutrients and BOD.	Vertical relief and proximity to storm drain; Large drainage area; High sediment loadings; Aesthetics;	Seasonal surface scarification; Periodic removal of trash and debris and accumulated silt on bed surface (when >0.5" thick); Frequent inspection; Potential media replacement

2. DRY EXTENDED DETENTION BASINS

Definition

Dry extended detention (ED) basins (a.k.a. dry ponds, extended detention basins, detention ponds, extended detention ponds) are basins whose outlets have been designed to detain the SUSMP runoff volume (see *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended)) for 36 to 48 hours to allow sediment particles and associated pollutants to settle and be removed. Dry ED basins do not have a permanent pool; they are designed to drain completely between storm events. They can also be used to provide hydromodification and/or flood control by modifying the outlet control structure design and including additional detention storage. The slopes, bottom, and forebay of ED basins are typically vegetated.

Dry ED basins can be located either on-line or off-line. For off-line basins, a flow diversion structure is used to divert the SUSMP volume to the basin from the storm drain. For on-line basins, all storm drain flows are routed through the basin; storm events exceeding the water quality design capacity will pass through the basin and will discharge over a primary overflow outlet untreated, or during extreme events, over an emergency spillway. In both types of basins, influent flows enter a sediment forebay where coarse solids are first removed prior to flowing into the main cell of the basin where finer sediment and associated pollutants settle as stormwater is detained and slowly released through a controlled outlet structure.

General Constraints and Siting Considerations

- Surface space availability - typically 0.5 to 2.0 percent of the total tributary development area required.
- Depth to groundwater - bottom of basin should be 2 feet higher than the seasonal high water table elevation.
- Steep slopes - basins placed above slopes greater than 15 percent or within 200 feet from the top of a hazardous slope or landslide area require a geotechnical investigation.
- Compatibility with flood control - basins must not interfere with flood control functions of existing conveyance and detention structures.

Multi-Use Opportunities

A dry ED basin can sometimes be retrofitted into an existing flood control basin or integrated into the design of a park or playfield. Perforated risers, multiple orifice plate outlets, or similar multi-stage outlets are required for flood control retrofit applications to ensure adequate detention time for small storms while still providing peak flow attenuation for the flood design storm. Recreational multi-use facilities must be inspected after every storm and may require a greater maintenance frequency than dedicated water quality basins to ensure aesthetics and public safety are not compromised. Any planned multi-use facility must obtain special approval by the LACDPW and any other jurisdictional agencies.

Dry Extended Detention Basin Design Specifications

Basin Sizing and Geometry

Dry extended detention basin geometry is illustrated in Figure 2-1.

1. Dry extended detention basins shall be sized to capture and treat the entire SUSMP volume with a 36 to 48 hour draw-down time.
2. The total basin volume shall be the SUSMP volume plus an additional 5% for total suspended solids (TSS) accumulation (105% of the SUSMP volume). Freeboard is in addition to the total basin volume.
3. The minimum freeboard shall be 2 feet above the maximum water surface elevation over the emergency spillway for online basins and 1 foot above the maximum water surface elevation over the emergency spillway for offline basins.
4. The length-to-width ratio at half basin depth shall be a minimum of 1.5:1. *Intent: a long flow length will improve TSS removal.*
5. The cross-sectional geometry across the width of the basin should be approximately trapezoidal with a maximum side slope of 3:1 unless otherwise permitted by the County (see Side Slopes below). Shallower side slopes are necessary if the basin is designed to have recreational uses during dry weather conditions.
6. A low flow channel shall be provided. A low flow channel is a narrow, shallow trench filled with pea gravel (or equivalent) that runs the length of the basin to drain dry weather flows. The low flow channel shall have a depth of 6 inches and a width of 1 foot, and shall tie into the outlet structure.
7. The basin bottom shall have a 1% longitudinal slope (direction of flow) in the forebay, and may range from 0 to 1% longitudinal slope in the main basin. The bottom of the basin shall slope 2% toward the center low flow channel.
8. A basin should be large enough to allow for equipment access. If the water quality design volume is such that the basin bottom would be less than 5 feet wide, an alternative BMP should be considered. See Maintenance Access below.

Soils Considerations

1. Extended detention basins can be used with almost all soils and geology, with minor design adjustments for rapidly percolating soils (sandy or gravelly soils with infiltration rate > 2.4 in/hr). If rapidly percolating soils are present, extended detention basins should be designed by a licensed soil engineer to include lower permeability soils in the subgrade to prevent rapid, untreated infiltration.
2. The slopes of the detention basin shall be analyzed for slope stability using rapid drawdown conditions and shall meet Los Angeles County minimum standards. A 1.5 static factor of

safety shall be used. Seismic analysis is not required due to the temporary inundation condition.

Energy Dissipation

1. Energy dissipation controls, constructed of sound materials such as stones, concrete, or proprietary devices that are rated to withstand the energy of the influent flow, shall be installed at the inlet to the forebay. Flow velocity into the basin forebay shall be controlled to 4 feet per second (fps) or less.
2. Energy dissipation controls must also be used at the outlet from the extended detention basin unless the basin discharges to a storm drain or hardened channel.
3. Consult the Los Angeles County Department of Public Works Design Division or Land Development Division for type and design of energy dissipation structure.

Forebay

As untreated stormwater enters the extended detention basin, it passes through a forebay for coarse solids removal. The forebay may be constructed using an internal berm constructed out of earthen embankment material, grouted riprap, or other structurally sound material.

1. The basin shall be sized so that 25% of the total basin volume is in the forebay and 75% of the total basin volume is in the main portion of the basin.
2. A gravity drain outlet from the forebay (4" minimum diameter) must extend the entire width of the internal berm.
3. The forebay outlet shall be offset from the inflow flowline to prevent short-circuiting.
4. Permanent steel post depth markers shall be placed in the forebay to define settled sediment removal limits at 50% and 100% of the forebay sediment storage depth.

Vegetation

Vegetation provides erosion protection from both wind and water and biofiltration of stormwater.

1. The bottom and slopes of the extended detention basin shall be vegetated. A mix of erosion-resistant plant species that effectively bind the soil should be used on the slopes and a diverse selection of plants that thrive under the specific site, climatic, and irrigation conditions should be specified for the basin bottom. The basin bottom should not be planted with trees, shrubs, or other large woody plants that may interfere with maintenance activities. Only native perennial grasses, forbs, or similar vegetation that can be replaced via seeding should be used on the basin bottom.
2. Only native or non-invasive plants should be used as approved by a licensed landscape architect. Suitable plant types for the specific BMP areas can be found by consulting an arborist, licensed landscape architect or referring to various online sources such as:

- CalFlora - a database of wild California plants that include plant characteristics and photos
<http://www.calflora.org>
- The California Invasive Plant Council - a listing of invasive, non-native plants of California
<http://www.cal-ipc.org/>
- Jepson Online Interchange For California Floristics - a database that provides information on identification, taxonomy, distribution, ecology, relationships, and diversity of California vascular plants.
<http://ucjeps.berkeley.edu/interchange.html>
- L.A. River Master Plan Landscaping and Plant Palettes - a guidance document providing a listing of native plant communities in the Los Angeles area
http://ladpw.org/wmd/watershed/LA/LAR_planting_guidelines_webversion.pdf
- VegSpec - a web-based decision support system that assists land managers in the planning and design of vegetative establishment practices
<http://ironwood.itc.nrcs.usda.gov/Netdynamics/Vegspec/pages/HomeVegspec.htm>
- USDA Plants Database - an extensive database of native and non-native plants of the United States with over 100 plant characteristics
<http://plants.usda.gov/index.html>

Outlet Structure and Drawdown Time

A total drawdown time of 36 to 48 hours shall be provided. The outlet structure shall be designed to release the bottom 50% of the detention volume (half-full to empty) over 24 to 32 hours, and the top half (full to half-full) in 12 to 16 hours. *Intent: Draw down schemes that detain low flows for longer periods than high flows have the following advantages over outlets that drain the pond evenly:*

- *Greater flood control capabilities*
- *Enhanced treatment of low flows which make up the bulk of incoming flows.*

There are two options that can be used for the outlet structure:

1. Uniformly perforated riser structures.
2. Multiple orifice structures (orifice plate).

The outlet structure can be placed in the pond with a debris screen (Figure 2-2) or housed in a standard manhole (Figure 2-3).

Note that a primary overflow (typically a riser pipe connected to the outlet works) should be sized to pass the peak flow rate from the developed capital design storm. The primary overflow is intended to protect against overtopping or breaching of the basin embankment.

Uniformly Perforated Riser Outlet Sizing Methodology (Figure 2-2)

The following attributes influence the perforated riser outlet sizing calculations:


- Shape of the pond (e.g. trapezoidal)
- Depth and volume of the pond
- Elevation / depth of first row of holes
- Elevation / depth of last row of holes
- Size of holes
- Number of rows and number of holes per row
- Desired draw down time (e.g. 16 hour and 32 hour draw down for top half and bottom half respectively, 48 hour total draw down time)

The governing rate of discharge from a perforated riser structure having uniform holes at equal spacing can be calculated using Equation 2-1 below:

$$Q = C_p \frac{2A_p}{3H_s} \sqrt{2g} H^{3/2} \quad (\text{Equation 2-1})$$

Where:

- Q = riser flow discharge (cfs)
 C_p = discharge coefficient for perforations (use 0.61)
 A_p = cross-sectional area of all the holes (ft²)
 s = center to center vertical spacing between perforations (ft)
 H_s = distance from $s/2$ below the lowest row of holes to $s/2$ above the top row of holes (McEnroe 1988).
 H = distance from $s/2$ below the lowest row of holes to the water surface elevation under consideration.



For the iterative computations needed to size the holes in the riser and determine the riser height a simplified version of Equation 2-1 may be used, as shown below in Equation 2-2:

$$Q = kH^{3/2} \quad (\text{Equation 2-2})$$

Where:

$$k = C_p \frac{2A_p}{3H_s} \sqrt{2g} \quad (\text{Equation 2-3})$$

Uniformly perforated riser designs are defined by the depth or elevation of the first row of perforations, the length of the perforated section of pipe, and the size or diameter of each perforation. The steps needed to size a perforated riser outlet are illustrated in Appendix C.

Multiple Orifice (Non-Uniform) Outlet Sizing Methodology

The following attributes influence multiple orifice outlet sizing calculations:

- Shape of the pond (e.g. trapezoidal)
- Depth and volume of the pond
- Elevation of each orifice
- Desired draw-down time (e.g., 16 hour and 32 hour draw down times for top half and bottom half respectively, 48 hour draw down time for whole pond)

The rate of discharge from a single orifice can be calculated using Equation 2-4 below:

$$Q = CA(2gH)^{0.5} \quad (\text{Equation 2-4})$$

Where:

- Q = orifice flow discharge
- C = discharge coefficient
- A = cross-sectional area of orifice or pipe (ft²)
- g = acceleration due to gravity (32.2 ft/s²)
- H = effective head on the orifice (measured from center of orifice to water surface)

Multiple orifice designs are defined by the depth (or elevation) and the size (or diameter) of each orifice (Figure 2-1). The steps needed to size a dual orifice outlet are outlined in Appendix C; multiple orifices may be provided and sized using a similar approach.

Emergency Spillway

A primary overflow outlet above the water quality outlet should be provided, as described above, to pass the developed capital design storm. An emergency overflow spillway in addition to the primary overflow outlet is required. Spillways shall meet the California Department of Water Resources, Division of Safety of Dams Guidelines for the Design and Construction of Small Embankment Dams (<http://damsafety.water.ca.gov/docs/GuidelinesSmallDams.pdf>).

Intent: Emergency overflow spillways are intended to control the location of pond overtopping and direct overflows back into the downstream conveyance system or other acceptable discharge point.

Online Basins

1. If indicated by a downstream risk assessment, online basins must have an emergency overflow spillway to prevent overtopping of walls or berms should blockage of the primary outlet occur.
2. The overflow spillway must be sized to pass the capital developed peak flow.
3. The minimum freeboard shall be 2 feet above the maximum water surface elevation corresponding to flow over the emergency spillway.

Offline Basins

1. Offline basins must have either an emergency overflow spillway or an emergency overflow riser. The emergency overflow must be designed to pass the SUSMP storm peak flow directly to the downstream conveyance system or another acceptable discharge point.
2. The emergency overflow spillway shall be armored to withstand the energy of the spillway flows (Figure 2-4). The spillway shall be constructed of grouted rip-rap.
3. The minimum freeboard shall be 1 foot above the maximum water surface elevation corresponding to flow over the emergency spillway.

Side Slopes

1. Interior side slopes above the water quality design depth and up to the emergency overflow water surface shall be no steeper than 3H:1V, unless stabilization has been approved by a licensed geotechnical engineer.
2. Exterior side slopes shall be no steeper than 2H:1V, unless stabilization has been approved by a licensed geotechnical engineer.
3. For any slope (interior or exterior) greater than 2H:1V a geotechnical report must be submitted and approved by the County's Geotechnical and Materials Engineering Division.
4. Pond walls may be vertical retaining walls, provided: (a) they are constructed of reinforced concrete, (b) a fence is provided along the top of the wall (see fencing below) or further back, and (d) the design is stamped by a licensed civil engineer and approved by the County.

Embankments

1. Embankments are earthen slopes or berms used for detaining or redirecting the flow of water.
2. The minimum top width of all berm embankments shall be 20 feet, or as approved by the Geotechnical and Materials Division.
3. Basin berm embankments must be constructed on native consolidated soil (or adequately compacted and stable fill soils analyzed by a licensed geotechnical engineer) free of loose surface soil materials, roots, and other organic debris.
4. Earthworks shall be in accordance with Section 300-6 of the Standard Specifications for Public Works Construction, most recent edition.
5. Basin berm embankments greater than 4 feet in height must be constructed by excavating a key equal to 50% of the berm embankment cross-sectional height and width. This requirement may be waived if specifically approved by a licensed geotechnical engineer.

6. The berm embankment shall be constructed of compacted soil (95% minimum dry density, modified proctor method per ASTM D1557), placed in 6-inch lifts.
7. Low growing native or non-invasive perennial grasses shall be planted on downstream embankment slopes. See the Vegetation Management on Embankment Dams of Public Works' Debris Control Facilities, Attachment B, for a recommended plant list.

Fencing

Safety is provided by fencing of the facility.

1. Fences shall be designed and constructed in accordance with Title 11, Section 11.48 of the Los Angeles County Code and must be located at or above the overflow water surface elevation. Shrubs (County approved, California-adapted species) can be used to hide the fencing.

Right-of-Way

1. Detention basins and associated access roads to be maintained by the County shall be dedicated in fee or in an easement to Los Angeles County with appropriate access.

Maintenance Access

Maintenance access road(s) shall be provided to the control structure and other drainage structures associated with the basin (e.g., inlet, emergency overflow or bypass structures). Manhole and catch basin lids must be in or at the edge of the access road.

An access ramp is required for removal of accumulated sediment with a backhoe or loader and truck. The ramp must extend to the basin bottom to avoid damage to vegetation planted on the basin slope.

Access roads shall meet the following design criteria:

1. All access ramps and roads shall be paved with a minimum of 6 inches of concrete over 3 inches of crushed aggregate base material. This requirement may be modified depending on the soil conditions and intended use of the road at the discretion of the Department.
2. Maximum grade shall be 12% unless otherwise approved by the Department.
3. Centerline turning radius shall be 40 feet, minimum.
4. Access roads less than 500 feet long shall have 12-foot wide pavement within a minimum 15-foot wide bench. Access roads greater than 500 feet long shall have 16-foot wide pavement within a minimum 20-foot wide bench.
5. All access roads shall terminate with turnaround areas of 40 feet by 40 feet. A hammer type turn around area or a circle drive around the top of the pond is also acceptable.

6. Adequate double-drive gates and commercial driveways are required at street crossings. Gates should be located a minimum of 25 feet from the street curb except in residential areas where the gates may be located along the property line provided there is adequate site distance to see oncoming vehicles at the posted speed limit.


Landscaping

Landscaping outside of the basin is required for all dry extended detention basins and must adhere to the following criteria so as not to hinder maintenance operations:


1. No trees or shrubs may be planted within 10 feet of inlet or outlet pipes or manmade drainage structures such as spillways, flow spreaders, or earthen embankments. Species with roots that seek water, such as willow or poplar, shall not be used within 50 feet of pipes or manmade structures. Weeping willow (*Salix babylonica*) should not be planted in or near detention basins.
2. The use of prohibited non-native plant species is not permitted. For more information on prohibited non-native plant species and invasive weeds, including biology and control of listed weeds, look at the "encycloweedia" located at the California Department of Food and Agriculture website at <http://www.cdffa.ca.gov/wma> or the California Invasive Plant Council website at <http://portal.cal-ipc.org/weedlist>.
3. Other resources for identifying suitable plant types for specific BMP areas can be found by consulting a nurseryman, arborist, landscape architect or referring to various online sources such as:
 - CalFlora - a database of wild California plants that include plant characteristics and photos
<http://www.calflora.org>
 - L.A. River Master Plan Landscaping and Plant Palettes - a guidance document providing a listing of native plant communities in the Los Angeles area
http://ladpw.org/wmd/watershed/LA/LAR_planting_guidelines_webversion.pdf
 - Jepson Online Interchange For California Floristics - a database that provides information on identification, taxonomy, distribution, ecology, relationships, and diversity of California vascular plants.
<http://ucjeps.berkeley.edu/interchange.html>
 - VegSpec - a web-based decision support system that assists land managers in the planning and design of vegetative establishment practices
<http://ironwood.itc.nrcs.usda.gov/Netdynamics/Vegspec/pages/HomeVegspec.htm>
 - USDA Plants Database - an extensive database of native and non-native plants of the United States with over 100 plant characteristics
<http://plants.usda.gov/index.html>

Restricted Construction Materials

The use of treated wood or galvanized metal anywhere inside the facility is prohibited. The use of galvanized fencing is permitted if in accordance with the fencing requirement above.



Plan View
(Not to Scale)





Section A - A'
(Not to Scale)

NOTES:

- ① INLET PIPE SHALL BE DESIGNED AND LOCATED SO THAT NON-EROSIVE VELOCITIES OCCUR IN THE FOREBAY
- ② MAINTENANCE RAMP SHOULD BE PAVED. SLOPE SHOULD NOT EXCEED 12%. MAINTENANCE RAMP SHOULD PROVIDE ACCESS TO BOTH THE FOREBAY AND MAIN BASIN.
- ③ RIP RAP APRON OR OTHER INLET ENERGY DISSIPATION SHALL BE PROVIDED SUCH THAT VELOCITIES IN THE FOREBAY ARE < 4 FT/S.
- ④ SEDIMENT FOREBAY SHOULD BE SIZED TO PROVIDE 25% OF THE TOTAL BASIN VOLUME.
- ⑤ SIDE SLOPES SHOULD NOT EXCEED 3:1 UNLESS APPROVED BY AN ENGINEER. SIDE SLOPES SHALL NOT EXCEED 2:1 WITHOUT A SUPPORTING GEOTECHNICAL REPORT.
- ⑥ EMERGENCY SPILLWAY MUST BE SIZED TO PASS CAPITAL DEVELOPMENT PEAK FLOW FOR ON-LINE BASINS, AND WATER QUALITY DESIGN FLOW FOR OFF-LINE BASINS.
- ⑦ OUTLET PIPE. ENERGY DISSIPATION SHALL BE PROVIDED UNLESS DISCHARGE IS TO PIPE OR HARDENED CHANNEL.
- ⑧ OUTLET STRUCTURE SHOULD BE SIZED TO DRAIN WATER QUALITY VOLUME IN 36 - 48 HOURS (SEE FIGURE 2-2 FOR PERFORATED RISER DETAILS). ALTERNATIVELY PLACE RISER STRUCTURE IN A MANHOLE (SEE FIGURE 2-3).
- ⑨ INSTALL EARTHEN BERM OR EQUIVALENT. TOP OF BERM SHALL BE 2' MINIMUM BELOW DESIGN WATER QUALITY STAGE. BERM SHALL BE KEYED INTO EMBANKMENT A MINIMUM OF 1' ON BOTH SIDES.


Figure 2-1
DETENTION POND




NOTES:

- ① RISER PIPE SHALL BE SIZED TO PROVIDE 36 TO 48-HOUR FULL BRIM DRAW DOWN TIME.
- ② TOTAL OUTLET CAPACITY: CAPITAL DEVELOPED PEAK FLOW FOR ON-LINE BASINS AND WATER QUALITY DESIGN FLOW FOR OFF-LINE BASINS.
- ③ SCREEN OPENINGS SHALL BE AT LEAST $\frac{1}{4}$ " AND SHALL NOT EXCEED THE DIAMETER OF THE PERFORATIONS ON THE RISER.
- ④ RISER PIPE PERFORATION DIAMETER SHALL BE NO LESS THAN $\frac{1}{2}$ " AND NO MORE THAN 2"
- ⑤ MINIMUM PIPE DIAMETER (D) IS 2'
- ⑥ RISER PIPE MATERIAL IS CMP

Figure 2-2
PERFORATED RISER STRUCTURE



Plan View
(Not to Scale)



NOTES:

- ① USE A MINIMUM OF A 54" DIA TYPE 2 CATCH BASIN
- ② OUTLET CAPACITY: CAPITAL DEVELOPED PEAK FLOW FOR ON-LINE BASINS.
- ③ METAL PARTS: CORROSION RESISTANT. NON-GALVANIZED PARTS PREFERRED. GALVANIZED PIPE PARTS TO HAVE ASPHALT TREATMENT.
- ④ FRAME AND LADDER OR STEPS OFFSET SO:
 - A. CLEANOUT GATE IS VISIBLE FROM TOP.
 - B. CLIMB-DOWN SPACE IS CLEAR OF RISER AND
 - C. FRAME IS CLEAR OF CURB.
- ⑤ IF METAL OUTLET PIPE CONNECTS TO CEMENT CONCRETE PIPE: OUTLET PIPE TO HAVE SMOOTH O.D. EQUAL TO CONCRETE PIPE I.D. LESS $\frac{1}{4}"$
- ⑥ PROVIDE AT LEAST ONE 3 X .090 GAGE SUPPORT BRACKET ANCHORED TO CONCRETE WALL. (MAXIMUM 3' VERTICAL SPACING)
- ⑦ LOCATE ADDITIONAL LADDER RUNGS IN STRUCTURES USED AS ACCESS TO TANKS OR VAULTS TO ALLOW ACCESS WHEN CATCH BASIN IS FILLED WITH WATER






Figure 2-3
MULTIPLE ORIFICE OUTLET



Plan View
(Not to Scale)



Section A – A' Option 1
(Not to Scale)



Section A – A' Option 2
(Not to Scale)



NOTES:

1. ALTERNATIVE SPILLWAY DESIGNS BASED ON THE CALIFORNIA DEPARTMENT OF WATER RESOURCES' GUIDELINES FOR THE DESIGN AND CONSTRUCTION OF SMALL EMBANKMENT DAMS OR AT THE DISCRETION OF THE DEPARTMENT

Figure 2-4
SPILLWAY

Dry Extended Detention Basins Maintenance Standards

General Requirements

Maintenance is critical for extended detention basins to continue to function as originally designed. A specific maintenance plan shall be formulated for each facility outlining the schedule and scope of maintenance operations, as well as documentation and reporting requirements. The following are general maintenance requirements:

1. The basin should be inspected annually and inspections after major storm events are encouraged (see Appendix E for guidance on BMP inspection). Trash and debris should be removed as needed, but at least annually prior to the beginning of the wet season (see Appendix F for dry extended detention basin inspection and maintenance checklist).
2. Site vegetation should be maintained as follows:
 - Vegetation, large shrubs, or trees that limit access or interfere with basin operation should be pruned or removed.
 - Slope areas that have become bare should be revegetated and eroded areas should be regraded prior to being revegetated.
 - Grass should be mowed to 4"-9" high and grass clippings should be removed.
 - Fallen leaves and debris from deciduous plant foliage should be raked and removed.
 - Invasive vegetation, such as Alligatorweed (*Alternanthera philoxeroides*), Halogeton (*Halogeton glomeratus*), Spotted Knapweed (*Centaurea maculosa*), Giant Reed (*Arundo donax*), Castor Bean (*Ricinus communis*), Perennial Pepperweed (*Lepidium latifolium*), and Yellow Starthistle (*Centaurea solstitialis*) must be removed and replaced with non-invasive species. Invasive species should never contribute more than 25% of the vegetated area. For more information on invasive weeds, including biology and control of listed weeds, look at the "encycloweed" located at the California Department of Food and Agriculture website at <http://www.cdffa.ca.gov/wma> or the California Invasive Plant Council website at <http://portal.cal-ipc.org/weedlist>.
 - Dead vegetation should be removed if it exceeds 10% of area coverage. Vegetation should be replaced immediately to maintain cover density and control erosion where soils are exposed.
 - No herbicides or other chemicals shall be used to control vegetation.
3. Accumulation of sediment exceeding 50% of the sediment storage capacity in the forebay, as indicated on the permanent steel post depth markers, should be removed. Sediment from the remainder of the basin should be removed when 6 inches of sediment accumulates. Sediment should be tested for toxic substance accumulation in compliance with current disposal requirements if visual or olfactory indications of pollution are noticed. If toxic substances are encountered at concentrations exceeding thresholds of Title 22, Section 66261 of the California Code of Regulations, the removed sediment must be disposed of in a hazardous waste landfill.
4. Following sediment removal activities, replanting and/or reseeding of vegetation may be required for reestablishment.

Maintenance Standards

A summary of the routine and major maintenance activities recommended for dry extended detention ponds is shown in Table 2-1. The routine and major maintenance standards listed in Tables 2-2 and 2-3 are intended to be measures to determine if maintenance actions are required as identified through inspection. They are not intended to be measures of the facility's required condition at all times between inspections.

Table 2-1: Dry Extended Detention Pond Routine and Major Maintenance Quick Guide

Inspection and Maintenance Activities Summary	
Routine Maintenance	• Removal trash and debris • Remove any evidence of visual contamination from floatables such as oil and grease • Remove minor sediment accumulation near inlet and outlet structures • Stabilize/repair eroded banks and fill in animal burrows if present • Make minor structural repairs to inlet/outlet structures, valves, sluice gates, pumps, fences, locks, access hatches should be inspected and kept functional • Eliminate pests and conditions that promote breeding of pests • Periodically observe function under wet weather conditions • Take photographs before and after maintenance (encouraged)
Major Maintenance	• Remove dead, diseased, or dying trees and woody vegetation that interfere with facility maintenance • Clean-out underdrains • Correct problems associated with berm settlement • Repair berm/dike breaches and stabilize eroded parts of the berm • Repair and rebuild spillway as needed to reverse the effects of severe erosion • Remove sediment build up in forebay and main pond area to restore original sediment holding capacity • Regrade main pond bottom to restore bottom slope and eliminate the incidence of standing pools • Aerate compacted areas to promote infiltration if volume reductions are desired • Repair or replace gates, fences, flow control structures, and inlet/outlet structures as needed to maintain full functionality

Table 2-2: Routine Maintenance Standards - Extended Detention Basins

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Trash & Debris	Any trash and debris which exceed 5 cubic feet per 1,000 sf of basin area (one standard garbage can). In general, there should be no visual evidence of dumping. If less than threshold all trash and debris will be removed as part of next scheduled maintenance.	Trash and debris cleared from site.	Annually prior to wet season After major storm events (>0.75 in/24 hrs) if spot checks of some basins indicate widespread damage/maintenance needs
Inlet / outlet sediment accumulation	Minor sediment accumulation that affects flow through the facility.	Sediment cleaned out.	
Erosion of banks and channels	Rilling over 2 inches deep where cause of damage is still present or where there is potential for continued erosion. Any erosion observed on a compacted berm embankment.	Slopes should be stabilized using appropriate erosion control measure(s); e.g., rock reinforcement, planting of grass, compaction.	
Visual contaminants and pollution	Any evidence of oil, gasoline, contaminants or other pollutants.	No visual evidence of contaminants or pollutants present.	
Noxious pests	Visual observations or receipt of complaints of numbers of pests that would not be naturally occurring and could pose a threat to human or aquatic health.	Vectors controlled per LACDPW standards.	
Aesthetics	Minor vegetation removal and thinning. Mowing berms and surroundings	Facility is visually pleasing.	Monthly (or as dictated by agreement between County and landscape contractor)
Noxious Weeds	Any evidence of noxious weeds.	Eradicate all noxious weeds; control and prevent the spread of all noxious weeds. Use Integrated Pest Management techniques, if applicable. See http://www.ipm.ucdavis.edu/ for more information.	

Table 2-3: Major Maintenance Standards - Extended Detention Basins

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Tree Growth	Tree growth does not allow maintenance access or interferes with maintenance activity (i.e., slope mowing, silt removal, vactoring, or equipment movements). If trees are not interfering, do not remove. Dead, diseased, or dying trees should be removed.	Trees do not hinder maintenance activities. Remove dead, diseased, or dying trees. (Use a certified Arborist to determine health of tree or removal requirements)	Annual or as needed (infrequent) After major storm events (>0.75 in/24 hrs) if spot checks of some basins indicate widespread damage/maintenance needs.
Settling of berm	If settlement is apparent. Settling can be an indication of more severe problems with the berm or outlet works. A geotechnical engineer should be consulted to determine the source of the settlement if the dike/berm is serving as a dam.	Berm is built back to the design elevation.	
Piping through berm	Discernable water flow through basin berm. Ongoing erosion with potential for erosion to continue. A licensed geotechnical engineer should be called in to inspect and evaluate condition and recommend repair of condition.	Piping eliminated. Erosion potential resolved and berm stability achieved. Report of annual burrows.	
Tree and large shrub growth on downstream slope of embankments	Tree and large shrub growth on downstream slopes of embankments may prevent inspection and provide habitat for burrowing rodents.	Trees and large shrubs should be removed. All dead roots should be removed if practical. Otherwise, dead roots should be removed to a minimum of 36 inches below grade and replaced with cement grout to 12 inches below grade. The top 12 inches of the root holes should be filled with compacted, in-situ soils. The area facility engineer may require additional root removal if necessary for dam safety or maintenance purposes.	

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Erosion on Spillway	Rock is missing and soil is exposed at top of spillway or outside slope.	Rocks and pad depth are restored to design standards.	
Sediment accumulation	Sediment buildup exceeding 50% of the forebay sediment storage capacity. Six inches or more of accumulated sediment across basin bottom.	Basin capacity restored.	
Standing water	Low flow channel is not draining, standing pools of water are observed.	No standing pools of water in low flow channel.	
Gate/Fence Damage	Damage to gate/fence, including missing locks and hinges	Gate/Fence repaired.	

3. VEGETATED SWALES

Definition

Vegetated swales are open, shallow channels with low-lying vegetation covering the side slopes and bottom that collect and slowly convey runoff flow to downstream discharge points. Vegetated swales provide pollutant removal through settling and filtration in the vegetation (usually grasses) lining the channels, provide the opportunity for stormwater volume reduction through infiltration and evapotranspiration, and reduce the flow velocity in addition to conveying stormwater runoff. An effective vegetated swale achieves uniform sheet flow over and through a densely vegetated area for a period of several minutes. The vegetation in the swale can vary depending on its location within a development project and is the choice of the designer, depending on the design criteria outlined below.

Vegetated swales can be designed to be either on-line or off-line. On-line vegetated swales are used for conveying high flows as well as providing treatment of the water quality design flow, and can replace curbs, gutters, and storm drain systems. On-line swales are sized so that the low flow portion of the swale meets the treatment BMP design criteria, and the upper portion of the swale conveys high flows up to the capital storm (e.g. flood conveyance), with a set freeboard (per the LACFCD "Design Manual Hydraulics"). Flow velocities are limited to prevent reentrainment of sediment and associated pollutants. Off-line swales have flows up to the water quality design flow diverted to them from the conveyance system. Freeboard for off-line swales is 8 inches.

The effectiveness of vegetated swales can be enhanced by adding check dams at approximately 50 foot increments along their length. These dams maximize the retention time within the swale, decrease flow velocities, and promote particulate settling. The incorporation of vegetated filter strips parallel to the top of the channel banks can help to treat sheet flows entering the swale.

General Constraints and Siting Considerations

- High flow velocity - steep terrain and/or large tributary area may cause erosive flows
- Shallow grades - limited site slope may cause ponding
- Compatibility with flood control - swales must not interfere with flood control functions of existing conveyance and detention structures
- Appropriate selection of vegetation based on irrigation requirements and exposure (shady versus sunny areas).

Multi-Use Opportunities

Swales can be easily integrated into roadside vegetated buffers or parking lot landscaping.

Vegetated Swale Design Specifications

Geotechnical Considerations

Vegetated swales can be used wherever the local climate and soils permit the establishment and maintenance of an appropriate vegetative cover, and slopes are low or can be engineered to swale specifications. They are impractical in areas with steep topography (slopes in excess of approximately 10%).

Sizing

The flow capacity of a vegetated swale is a function of the longitudinal slope (parallel to flow), the resistance to flow (i.e. Manning's roughness), and the cross sectional area. The cross section is normally approximately trapezoidal and the area is a function of the bottom width and side slopes. The flow capacity of vegetated swales should be such that the design water quality flow rate will not exceed a flow depth of 2/3 the height of the vegetation within the swale or 4 inches at the SUSMP design intensity. Once design criteria have been selected, the resulting flow depth for the design water quality flow rate is checked. If the depth restriction is exceeded, swale parameters (e.g. longitudinal slope, width) are adjusted to reduce the flow depth.

Procedures for sizing swales are summarized below and illustrated in Figure 3-1.

Step 1: Select design flows

The swale sizing is based on the SUSMP design flow Q_{wq} (see *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended)).

Step 2: Calculate swale bottom width.

The swale bottom width is calculated based on Manning's equation for open-channel flow. This equation can be used to calculate discharges as follows:

$$Q = 1.49 / n QAR^{1.67} S^{0.5} \quad (\text{Equation 3-1})$$

where:

- Q = flow rate (cfs)
- n = Manning's roughness coefficient (unitless)
- A = cross-sectional area of flow (ft²)
- R = hydraulic radius (ft) = area divided by wetted perimeter
- S = longitudinal slope (ft/ft)

For shallow flow depths in swales, channel side slopes are ignored in the calculation of bottom width. Use the following equation (a simplified form of Manning's formula) to estimate the swale bottom width:

$$b = Q_{wq} n_{wq} / 1.49 y^{1.67} s^{0.5} \quad (\text{Equation 3-2})$$

Where:

- b = bottom width of swale (ft)
- Q_{wq} = water quality design flow (cfs)
- n_{wq} = Manning's roughness coefficient for shallow flow conditions = 0.2 (unitless)
- y = design flow depth (ft)
- s = longitudinal slope (along direction of flow) (ft/ft)

Proceed to Step 3 if the bottom width is calculated to be between 2 and 10 feet. A minimum 2-foot bottom width is required. Therefore, if the calculated bottom width is less than 2 feet, increase the width to 2 feet and recalculate the design flow depth y using the Equation 3-2 where Q_{wq} , n_{wq} , and s are the same values as used above, but $b = 2$ feet.

The maximum allowable bottom width is 10 feet; therefore if the calculated bottom width exceeds 10 feet, then one of the following steps is necessary to reduce the design bottom width:

- Increase the longitudinal slope (s) to a maximum of 6 feet in 100 feet (0.06 feet per foot).
- Increase the design flow depth (y) to a maximum of 4 inches.
- Place a divider lengthwise along the swale bottom (Figure 3-1) at least three-quarters of the swale length (beginning at the inlet), without compromising the design flow depth and swale lateral slope requirements. Swale width can be increased to an absolute maximum of 16 feet if a divider is provided.

Step 3: Determine design flow velocity

To calculate the design flow velocity through the swale, use the flow continuity equation:

$$V_{wq} = Q_{wq} / A_{wq} \quad (\text{Equation 3-3})$$

where:

- V_{wq} = design flow velocity (fps)
- $A_{wq} = by + Zy^2$ = cross-sectional area (ft²) of flow at design depth, where Z = side slope length per unit height (e.g., $Z = 3$ if side slopes are 3H:1V)

If the design flow velocity exceeds 1 foot per second, go back to Step 2 and modify one or more of the design parameters (longitudinal slope, bottom width, or flow depth) to reduce the design flow velocity to 1 foot per second or less. If the design flow velocity is calculated to be less than 1 foot per second, proceed to Step 4. *Note: It is desirable to have the design velocity as low as possible, both to improve treatment effectiveness and to reduce swale length requirements.*

Step 4: Calculate swale length

Use the following equation to determine the necessary swale length to achieve a hydraulic residence time of at least 10 minutes (600 seconds):

$$L = 60t_{hr}V_{wq} \quad (\text{Equation 3-4})$$

Where:

- L = minimum allowable swale length (ft)
- t_{hr} = hydraulic residence time (s)
- V_{wq} = design flow velocity (fps)

The minimum swale length is 100 feet; therefore, if the swale length is calculated to be less than 100 feet, increase the length to a minimum of 100 feet, leaving the bottom width unchanged. If a larger swale can be fitted on the site, consider using a greater length to increase the hydraulic residence time and improve the swale's pollutant removal capability. If the calculated length is too long for the site, or if it would cause layout problems, such as encroachment into shaded areas, proceed to Step 5 to further modify the layout. If the swale length can be accommodated on the site, proceed to Step 6.

Step 5: Adjust swale layout to fit on site

If the swale length calculated in Step 4 is too long for the site, the length can be reduced (to a minimum of 100 feet) by increasing the bottom width up to a maximum of 16 feet, as long as the 10 minute retention time is retained. However, the length cannot be increased in order to reduce the bottom width because Manning's depth-velocity-flow rate relationships would not be preserved. If the bottom width is increased to greater than 10 feet, a low flow dividing berm is needed to split the swale cross section in half to prevent channelization.

Length can be adjusted by calculating the top area of the swale and providing an equivalent top area with the adjusted dimensions.

- a) Calculate the swale treatment top area based on the swale length calculated in Step 4:

$$A_{top} = (b_i + b_{slope})L_i \quad (\text{Equation 3-5})$$

Where:

- A_{top} = top area (ft²) at the design treatment depth
- b_i = bottom width (ft) calculated in Step 2
- b_{slope} = the additional top width (ft) above the side slope for the design water depth (for 3:1 side slopes and a 4-inch water depth, $b_{slope} = 2$ feet)
- L_i = initial length (ft) calculated in Step 4.

- b) Use the swale top area and a reduced swale length L_f to increase the bottom width, using the following equation:

$$L_f = A_{top} / (b_f + b_{slope}) \quad (\text{Equation 3-6})$$

where:

L_f = reduced swale length (ft)
 b_f = increased bottom width (ft).

- c) Recalculate V_{wq} according to Step 3 using the revised cross-sectional area A_{wq} based on the increased bottom width b_f . Revise the design as necessary if the design flow velocity exceeds 1 foot per second.
- d) Recalculate to assure that the 10 minute retention time is retained.

Step 6: Provide conveyance capacity for flows higher than Q_{wq}

Vegetated swales may be designed as flow-through channels that convey flows higher than the water quality design flow rate, or they may be designed to incorporate a high-flow bypass upstream of the swale inlet. A high-flow bypass usually results in a smaller swale size. If a high-flow bypass is provided, this step is not needed. If no high-flow bypass is provided, proceed with the procedure below. Flow diversion structure design is described in Appendix D.

- a) Check the swale size to determine whether the swale can convey the capital storm peak flows (Refer to Design Manual - Hydraulic, Section C, "Criteria for Hydraulic Design Open Channels" and "Hydrology Manual" LACDPW).
- b) The capital storm peak flow velocity must be less than 3.0 feet per second. If this velocity exceeds 3.0 feet per second, return to Step 2 and increase the bottom width or flatten the longitudinal slope as necessary to reduce the capital storm peak flow velocity to 3.0 feet per second or less. If the longitudinal slope is flattened, the swale bottom width must be recalculated (Step 2) and must meet all design criteria.

Swale Geometry

1. In general, trapezoidal channel shape should be assumed for sizing calculations above, but a more naturalistic channel cross-section is preferred.
2. Swales designed for water quality treatment purposes only are anticipated to be fairly shallow, generally less than 1-foot. Therefore, a side slope of 2:1 (H:V) can be used and is acceptable. Milder slopes are necessary for mowed turf swales (3H:1V max).
3. Overall depth from the top of the side walls to the swale bottom shall be at least 12 inches.
4. Swale length shall be greater than 100 linear feet. Regardless of the recommended detention time, the swale should be not less than 100 feet in length. Length can be increased by meandering the swale.
5. The minimum swale bottom width shall be 2 feet to allow for ease of mowing.
6. The maximum swale bottom width shall be limited to 10 feet, unless a dividing berm is provided, then maximum bottom width can be 16 feet. Swale width is calculated without the dividing berm. *Intent: Experience shows that when the width exceeds about 10 feet, it*

is difficult to keep the water from concentrating in low-flow channels. It is also difficult to construct the bottom level and without sloping to one side. Vegetated swales are best constructed by leveling the bottom after excavating. A single-width pass with a front-end loader produces a better result than a multiple-width pass.

7. Swales that are required to convey flood as well as SUSMP flows should be sized to convey the capital storm and include 2 feet of freeboard.
8. Gradual meandering bends in the swale are desirable for aesthetic purposes and to promote slower flow.

Bottom Slope

1. The longitudinal slope (along the direction of flow) shall be between 1% and 6%.
2. If longitudinal slopes are less than 1.5% and the soils are poorly drained (e.g., silts and clays), then underdrains shall be provided. A soils report to verify soils properties shall be provided for swales less than 1.5%.
3. If longitudinal slope exceeds 6%, check dams with vertical drops of 12 inches or less shall be provided to achieve a bottom slope of 6% or less between the drop structures.
4. The lateral (horizontal) slope at the bottom of the swale shall be zero (flat) to discourage channeling.

Water Depth and Dry Weather Flow Drain

1. Water depth should not exceed 4 inches (or 2/3 of expected vegetation height), except for frequently mowed turf swales, for which the depth should not exceed 2 inches.
2. The swale length must provide a minimum hydraulic residence time of 10 minutes.
3. A low flow drain shall be provided for dry weather flows extending the entire length of the swale. The drain shall have a minimum depth of 6 inches, and a width no more than 5% of the calculated bottom swale width; the width of the drain shall be in addition to the required bottom width. If an anchored plate is used for flow spreading at the swale inlet, the plate wall shall have v-notches (maximum top width = 5% of swale width) or holes to allow preferential exit of low flows into the drain. If an underdrain is installed as required below, the low flow drain shall be omitted.

Energy Dissipation

1. Vegetated swales may be designed either on-line or off-line. If the facility is on-line, velocities shall be maintained below the maximum flow design velocity of 3 feet per second to prevent scour and resuspension of deposited sediments.
2. The maximum SUSMP flow velocity shall not exceed 1.0 foot per second. *Intent: This maximum SUSMP flow velocity promotes settling and keeps vegetation upright.*

3. This velocity limitation combined with a maximum depth of 4 inches and bottom width of 10 feet results in a recommended maximum flow capacity of about 3.3 cfs, after accounting for the side slopes. The contributory drainage area to each swale is limited so as not to exceed this recommended maximum flow capacity.
4. The maximum flow velocity during the capital storm shall not exceed 3.0 foot per second. This can be accomplished by:
 - a. splitting roadside swales near high points in the road so that flows drain in opposite directions, mimicking flow patterns on the road surface.
 - b. limiting contributory drainage areas to long swales by diverting flows throughout the length of the swale at regular intervals, to the downstream stormwater conveyance system.
5. A flow spreader (see "Flow Spreaders" below and detail in Figure 3-2) shall be used at the inlet so that the entrance velocity is quickly dissipated and the flow is uniformly distributed across the whole swale. Energy dissipation controls shall be constructed of sound materials such as stones, concrete, or proprietary devices that are rated to withstand the energy of the influent flows.
6. If check dams are used to reduce the longitudinal slope, a flow spreader shall be provided at the toe of each vertical drop, with specifications described below.
7. If flow is to be introduced through curb cuts, place pavement slightly above the elevation of the vegetated areas. Curb cuts should be at least 12 inches wide to prevent clogging.

Flow Spreaders

1. An anchored plate flow spreader shall be provided at the inlet to the swale. Equivalent methods for spreading flows evenly throughout the width the swale are acceptable.
2. The top surface of the flow spreader plate shall be level, projecting a minimum of 2 inches above the ground surface of the water quality facility, or v-notched with notches 6 to 10 inches on center and 1 to 4 inches deep (use shallower notches with closer spacing).
3. A flow spreader plate shall extend horizontally beyond the bottom width of the facility to prevent water from eroding the side slope. The horizontal extent should be such that the bank is protected for all flows up to the capital design flow (on-line swales) or the maximum flow that will enter the WQ facility (off-line swales).
4. Flow spreader plates shall be securely fixed in place.
5. Flow spreader plates may be made of either concrete, stainless steel, or other durable material.
6. Anchor posts shall be 4-inch square concrete, tubular stainless steel, or other material resistant to decay.

Check Dams

If check dams are required, they can be designed out of a number of different materials, including riprap, earthen berms, or removal stop logs. Check dams must be placed as to achieve the desired slope (<6%), and desired velocity (not to exceed 3 fps during the capital storm or 1 fps during the SUSMP storm), at a maximum of 50 feet apart. If rip rap is used, the material should consist of well-graded stone consisting of a mixture of rock sizes. The following is an example of an acceptable gradation:

<u>Particle Size</u>	<u>% Passing</u>
24"	100
15"	75
9"	50
4"	10

Underdrains

If underdrains (not to be confused with a dry weather flow drain (see page 3-25 above)) are required, then they must meet the following criteria:

1. Underdrains must be made of slotted, polyvinyl chloride (PVC) pipe conforming to ASTM D 3034 or equivalent or corrugated high density polyethylene (HDPE) pipe conforming to AASHTO 252M or equivalent. *Intent: As compared to round-hole perforated pipe, slotted underdrains provide greater intake capacity, clog resistant drainage, and reduced entrance velocity into the pipe, thereby reducing the chances of solids migration.*
2. Slotted pipe shall have 2 to 4 rows of slots cut perpendicular to the axis of the pipe or at right angles to the pitch of corrugations. Slots shall have a width of 0.04-inch to 0.1-inch and shall have a length of 1-inch to 1.25-inch. Slots shall be spaced such that the pipe has a minimum of one square inch per lineal foot.
3. The pipe must be 6 inches or greater in diameter, so it can be cleaned without damage to the pipe. Clean-out risers with diameters equal to the underdrain pipe must be placed at the terminal ends of the underdrain and can be incorporated into the flow spreader and outlet structure to minimize maintenance obstacles in the swale. Intermediate clean-out risers may also be placed in the check dams or grade control structures. The cleanout risers shall be capped with a lockable screw cap.
4. The underdrain shall be placed parallel to the swale bottom and backfilled and bedded with six inches of drain rock. The following aggregate shall be used to provide a gravel blanket and bedding for the underdrain pipe to provide a 1-foot minimum depth around the top and sides of the slotted pipe.

<u>Sieve size</u>	<u>Percent Passing</u>
¾ inch	100
¼ inch	30-60
US No. 8	20-50
US No. 50	3-12
US No. 200	0-1

- The drain rock must be wrapped in a geotextile fabric meeting the following minimum materials requirements.

Geotextile Property	Value	Test Method
Trapezoidal Tear (lbs)	40 (min)	ASTM D4533
Permeability (cm/sec)	0.2 (min)	ASTM D4491
AOS (sieve size)	#60 - #70 (min)	ASTM D4751
Ultraviolet resistance	70% or greater	ASTM D4355

- The underdrain must infiltrate into the subsurface or drain freely to an acceptable discharge point.

Swale Divider

- If a swale divider is used, the divider should be constructed of a firm material that will resist weathering and not erode, such as concrete or compacted soil seeded with grass. Treated timber should not be used. Selection of divider material must take into account maintenance activities, such as mowing.
- The divider must have a minimum height of 1 inch greater than the water quality design water depth.
- Earthen berms should be no steeper than 2H:1V.
- Material other than earth shall be embedded to a depth sufficient to be stable.

Soils

- Turf swale soils shall be amended with 2 inches of well-rotted compost, unless the organic content is already greater than 10%. The compost shall be mixed into the native soils to a depth of 6 inches to prevent soil layering and washout of compost. The compost will contain no sawdust, green or under-composted material, or any other toxic or harmful substance. It should contain no un-sterilized manure which can lead to high levels of pathogen indicators (coliform bacteria) in the runoff.

Vegetation

Swales must be vegetated in order to provide adequate treatment of runoff. It is important to maximize water contact with vegetation and the soil surface.



- The swale area should be appropriately vegetated with a mix of erosion-resistant plant species that effectively bind the soil. A diverse selection of low growing plants that thrive under the specific site, climatic, and watering conditions should be specified. A mixture of dry-area and wet-area grass species that can continue to grow through silt deposits is most effective. Native or adapted grasses are preferred because they generally require less fertilizer, limited maintenance, and are more drought resistant than exotic plants. Consultation with a landscape or erosion control specialist is recommended for project-

specific recommendations on grass seed, fertilizer, and mulching applications to ensure healthy grass growth. Suitable plant types can also be found by referring to various online sources such as:

- CalFlora - a database of wild California plants that include plant characteristics and photos
<http://www.calflora.org>
 - The California Invasive Plant Council - a listing of invasive, non-native plants of California
<http://www.cal-ipc.org/>
 - L.A. River Master Plan Landscaping and Plant Palettes - a guidance document providing a listing of native plant communities in the Los Angeles area
http://ladpw.org/wmd/watershed/LA/LAR_planting_guidelines_webversion.pdf
 - Jepson Online Interchange For California Floristics - a database that provides information on identification, taxonomy, distribution, ecology, relationships, and diversity of California vascular plants.
<http://ucjeps.berkeley.edu/interchange.html>
 - VegSpec - a web-based decision support system that assists land managers in the planning and design of vegetative establishment practices
<http://ironwood.itc.nrcs.usda.gov/Netdynamics/Vegspec/pages/HomeVegspec.htm>
 - USDA Plants Database - an extensive database of native and non-native plants of the United States with over 100 plant characteristics
<http://plants.usda.gov/index.html>
2. Trees or shrubs may be used in the surrounding landscape as long as they do not excessively shade the swale.
 3. Above the design treatment elevation, a typical lawn mix or landscape plants can be used provided they do not shade the swale vegetation.
 4. Irrigation is required if the seed is planted in spring or summer. Use of a permanent irrigation system may help provide maximal water quality performance. Drought-tolerant grasses should be specified to minimize irrigation requirements.
 5. Vegetative cover should be at least 4 inches in height, ideally 6 inches. Swale water depth should ideally be 2 inches below the height of the shortest plant species and should not exceed 4 inches.
 6. Locate the swale in an area without excessive shade to avoid poor vegetative growth. For moderately shaded areas, shade tolerant plants should be used.
 7. Locate the swale away from large trees that may drop leaves or needles. Excessive tree debris may smother the grass or impede the flow through the swale. Landscape planter beds should be designed and located so that soil does not erode from the beds and enter a nearby swale.

Restricted Construction Materials

The use of treated wood or galvanized metal within the vegetated swale is prohibited.



NOTES:

- ① VEGETATED SIDE SLOPES AT 2H:1V MAXIMUM SLOPE. MOWED TURF SWALES AT 3H:1V MAXIMUM.
- ② GRASS HEIGHT SHALL BE 4" - 6" HIGH.
- ③ SWALE DIVIDER REQUIRED FOR BOTTOM WIDTHS > 10'. MINIMUM REQUIRED BOTTOM WIDTH IS 2' EXCLUDING WIDTH OF LOW FLOW CHANNEL. MAXIMUM BOTTOM WIDTH WITH DIVIDER IS 16'.
- ④ DEPTH OF FLOW FOR WATER QUALITY TREATMENT MUST NOT EXCEED TWO-THIRDS OF THE GRASS HEIGHT AND NOT GREATER THAN 4" (INFREQUENTLY MOWED) OR 2" (FREQUENTLY MOWED).
- ⑤ 6" PERFORATED UNDERDRAIN IN 9" DEEP COARSE AGGREGATE BED CONNECTED TO STORM DRAIN. REQUIRED FOR SLOPES < 1.5% OR AS NEEDED.
- ⑥ INLET PIPE WITH INLET PROTECTION.
- ⑦ IF NO UNDERDRAIN, LOW FLOW DRAIN SHALL EXTEND ENTIRE LENGTH OF SWALE AND SHALL HAVE A DEPTH OF 6" MINIMUM AND WIDTH NO MORE THAN 5% SWALE BOTTOM WIDTH. ANCHORED PLATE FLOW SPREADER IF USED, SHALL HAVE V-NOTCHES (MAX TOP WIDTH = 5% OF SWALE WIDTH) OR HOLES TO ALLOW PREFERENTIAL EXIT OF LOW FLOWS.
- ⑧ INSTALL CHECK DAMS OR GRADE CONTROL STRUCTURES FOR SLOPES > 6% AT 50' MAXIMUM SPACING TO ACHIEVE A MAXIMUM EFFECTIVE LONGITUDINAL SLOPE OF 6%. FLOW SPREADERS SHALL BE PROVIDED AT INLET AND AT THE BASE OF EACH CHECK DAM SEE FIGURE 3-2.
- ⑨ INSTALL ENERGY DISSIPATOR AT THE INLET OF VEGETATED SWALE.
- ⑩ SWALE LENGTH SHALL BE 100' OR LENGTH REQUIRED TO PROVIDE 10 MINUTES RESIDENCE TIME, WHICHEVER IS GREATER.
- ⑪ INSTALL APPROPRIATE OUTLET STRUCTURE. ACCOMMODATE LOW FLOW CHANNEL AND/OR UNDERDRAIN (IF PRESENT).
- ⑫ AMEND SOILS WITH 2" OF COMPOST TILLED INTO 6" OF NATIVE SOIL UNLESS NATIVE SOIL ORGANIC CONTENT > 10%.






Figure 3-1
VEGETATED SWALE FILTER




Inlet Flow Spreader Detail
(Not to Scale)



Check Dam and Flow Spreader Detail
(Not to Scale)

NOTES:

- ① TOP SURFACE OF FLOW SPREADER SHALL BE LEVEL AND SHALL PROJECT 2" MINIMUM ABOVE GROUND. V-NOTCHES AT 6 TO 10 INCHES ON CENTER AND 1 TO 4 INCHES DEEP SHALL BE ACCEPTABLE.
- ② FLOW SPREADER ANCHOR POSTS SHALL BE 4-INCH SQUARE CONCRETE, TUBULAR STEEL OR OTHER MATERIAL RESISTANT TO DECAY.
- ③ FLOW SPREADER PLATES SHALL HAVE A ROW OF PERFORATIONS AT THE BASE OF THE PLATE TO PREVENT PONDING FOR LONG DURATIONS.
- ④ CHECK DAM SHALL BE NO HIGHER THAN 12". CHECK DAM SPACING SHALL BE NO GREATER THAN 50 FEET APART.



V-Notched Flow Spreader Detail
(Not to Scale)

Figure 3-2
FLOW SPREADER AND CHECK DAM

Vegetated Swale Maintenance Standards

General Requirements

1. Inspect vegetated swales for erosion or damage to vegetation after every storm greater than 0.75" for on-line swales and at least twice annually for off-line swales, preferably at the end of the wet season to schedule summer maintenance and in the fall to ensure readiness for winter (see Appendix E for guidance on facility inspection). Additional inspection after periods of heavy runoff is recommended. Each swale should be checked for debris and litter and areas of sediment accumulation (see Appendix F for a vegetated swale inspection and maintenance checklist).
2. Swale inlets (curb cuts or pipes) should maintain a calm flow of water entering the swale. Remove sediment as needed at the inlet if vegetation growth is inhibited in greater than 10% of the swale or if the sediment is blocking even distribution and entry of the water. Following sediment removal activities, replanting and/or reseeding of vegetation may be required for reestablishment.
3. Flow spreaders should provide even dispersion of flows across the swale. Sediments and debris should be removed from the flow spreader if blocking flows. Splash pads should be repaired if needed to prevent erosion. Spreader level should be checked and leveled if necessary.
4. Side slopes should be maintained to prevent erosion that introduces sediment into the swale. Slopes should be stabilized and planted using appropriate erosion control measures when native soil is exposed or erosion channels are forming.
5. Swales should drain within 48 hours of the end of a storm. Till the swale if compaction or clogging occurs and revegetate. The perforated underdrain pipe, if present, should be cleaned if necessary.
6. Vegetation should be healthy and dense enough to provide filtering while protecting underlying soils from erosion:
 - Mulch should be replenished as needed to ensure survival of vegetation.
 - Vegetation, large shrubs or trees that interfere with landscape swale operation should be pruned.
 - Fallen leaves and debris from deciduous plant foliage should be removed.
 - Grassy swales should be mowed to keep grass 4" to 6" in height. Grass clippings shall be removed.
 - Invasive vegetation, such as Alligatorweed (*Alternanthera philoxeroides*), Halogeton (*Halogeton glomeratus*), Spotted Knapweed (*Centaurea maculosa*), Giant Reed (*Arundo donax*), Castor Bean (*Ricinus communis*), Perennial Pepperweed (*Lepidium latifolium*), and Yellow Starthistle (*Centaurea solstitialis*) must be removed and replaced with non-invasive species. Invasive species should never contribute more than 10% of the vegetated area. For more information on invasive weeds, including biology and control

of listed weeds, look at the “encycloweedia” located at the California Department of Food and Agriculture website at <http://www.cdffa.ca.gov/wma> or the California Invasive Plant Council website at <http://portal.cal-ipc.org/weedlist>.

- Dead vegetation should be removed if greater than 10% of area coverage or when swale function is impaired. Vegetation should be replaced and established before the wet season to maintain cover density and control erosion where soils are exposed.
7. Check dams (if present) should control and distribute flow across the swale. Causes for altered water flow and/or channelization should be identified and obstructions cleared. Check dams and swale should be repaired if damaged.
 8. The vegetated swale should be well maintained; trash and debris, sediment, visual contamination (e.g., oils), noxious or nuisance weeds, should all be removed.

Maintenance Standards

A summary of the routine and major maintenance activities recommended for vegetated swales is shown in Table 3-1. Detailed routine and major maintenance standards are listed in Tables 3-2 and 3-3.

Table 3-1: Vegetated Swale Routine and Major Maintenance Quick Guide

Inspection and Maintenance Activities Summary	
Routine Maintenance	• Remove excess sediment as needed • Removal trash and debris • Clean underdrain (where applicable) and/or unclog outlet to eliminate standing water • Clean and reset flow spreaders as needed to restore original function • Restore sunlight access to shaded regions. Remove overhanging tree branches as needed to prevent excessive shading. • Remove any evidence of visual contamination from floatables such as oil and grease • Mow routinely to maintain ideal grass height and to suppress weeds • Replace invasive vegetation with non-invasive species • Remove sediment and debris accumulation near inlet and outlet structures • Stabilize/repair minor erosion and scouring with gravel • Take photographs before and after maintenance (encouraged)
Major Maintenance	• Regrade swale bottom and reseed to mitigate ponding of water between storms or excessive erosion and scouring • Install or replace low flow channel using pea gravel media to better convey nuisance flows • Revegetate bare exposed portions of the swale to restore vegetation to original level of coverage • De-thatch grass to remove accumulated sediment and aerate compacted areas to promote infiltration

Table 3-2: Routine Maintenance Standards - Vegetated Swales

Defect or Problem	Condition When Maintenance is Needed	Results Expected When Maintenance Is Performed	Frequency
Sediment Accumulation	Sediment depth exceeds 2 inches or covers vegetation.	Sediment deposits on grass treatment area of the vegetated swale removed without significant disturbance of the vegetation. When finished, swale should be level from side to side and drain freely toward outlet. There should be no areas of standing water once inflow has ceased.	Annually prior to wet season After major storm events (>0.75 in/24 hrs) if spot checks of some basins indicate widespread damage/maintenance needs
Trash and Debris Accumulation	Any trash and debris which exceed 5 cubic feet per 1,000 square feet (one standard garbage can).	Trash and debris removed from vegetated swale.	
Standing Water	When water stands in the swale between storms and does not drain freely.	There should be no areas of standing water once inflow has ceased. Outlet structures and underdrain (if installed) shall drain freely.	
Flow Spreader	Flow spreader uneven or clogged so that flows are not uniformly distributed through entire swale width.	Spreader leveled and cleaned such that flows are distributed evenly over entire swale width.	
Excessive Shading	Vegetation growth is poor because sunlight does not reach swale.	Over-hanging limbs and brushy vegetation on side slopes are trimmed back.	
Erosion/ Scouring	Eroded or scoured swale bottom due to flow channelization or higher flows.	No erosion or scouring in swale bottom. For ruts or bare areas less than 12 inches wide, damaged areas repaired by filling with crushed gravel. Over time, the grass will have started to cover the rock.	
Visual Contaminants and Pollution	Any visual evidence of oil, gasoline, contaminants or other pollutants.	No visual contaminants or pollutants present.	Monthly (or as dictated by agreement between County and landscape contractor)
Vegetation Length	When the grass becomes excessively tall (greater than 10-inches); when nuisance weeds and other vegetation starts to take over.	Vegetation mowed or nuisance vegetation removed so that flow is not impeded. Grass should be mowed to a height of 4 to 6 inches (depending on landscape requirements). Grass clippings removed.	

Defect or Problem	Condition When Maintenance is Needed	Results Expected When Maintenance Is Performed	Frequency
Inlet/Outlet Blockage	Inlet/outlet areas clogged with sediment and/or debris.	Material removed so that there is no clogging or blockage in the inlet and outlet area.	
Low Flow Channel Overflow	Nuisance flows are ponding, swale is continually wet.	Low flow channel media is renewed to adequately convey nuisance flows.	

Table 3-3: Major Maintenance Standards - Vegetated Swales

Defect or Problem	Condition When Maintenance is Needed	Results Expected When Maintenance Is Performed	Frequency
Standing Water	When water stands in the swale between storms and does not drain freely.	There should be no areas of standing water once inflow has ceased. Any of the following may apply: improved grade from head to foot of swale, removed clogged check dams, added underdrains or converted to a wet biofiltration swale.	Annual – preferably at end of wet season or as needed (infrequent)
Erosion/ Scouring	Eroded or scoured swale bottom due to flow channelization, or higher flows.	No erosion or scouring in swale bottom. Bare areas greater than 12 inches wide are regraded and reseeded.	After major storm events (>0.75 in/24 hrs) if spot checks of some basins indicate widespread damage/ maintenance needs
Constant Baseflow	When small quantities of water continually flow through the swale, even when it has been dry for weeks and an eroded, muddy channel has formed in the swale bottom	No eroded, muddy channel on the bottom. A low-flow pea-gravel drain added to the length of the swale, or an underdrain installed.	
Poor Vegetation Coverage	When grass is sparse or bare or eroded patches occur in more than 10% of the swale bottom.	Vegetation coverage in more than 90% of the swale bottom. Poorly vegetated areas are replanted with plugs of grass from the upper slope and reseeded there, plugs planted in the swale bottom with no gaps, or reseeded into loosened, fertile soil.	Semiannual – at beginning and end of wet season

4. FILTER STRIPS

Definition

Filter strips are vegetated areas designed to treat sheet flow runoff from adjacent impervious surfaces or intensive landscaped areas such as golf courses. Filter strips decrease runoff velocity, filter out TSS and associated pollutants, and provide some infiltration into underlying soils. While some assimilation of dissolved constituents may occur, filter strips are generally more effective in trapping sediment and particulate-bound metals, nutrients, and pesticides. Nutrients that bind to sediment include phosphorus and ammonium; soluble nutrients include nitrate. Filter strips are more effective when the runoff passes through the vegetation and thatch layer in the form of shallow, uniform flow. Biological and chemical processes may help break down pesticides, uptake metals, and utilize nutrients that are trapped in the filter.

Filter strips rely on dense turf vegetation with a thick thatch, growing on a moderately permeable soil and are well suited to treat runoff from roads and highways, driveways, roof downspouts, small parking lots, and other impervious surfaces. They are also good for use as vegetated buffers between developed areas and natural drainages.

General Constraints and Siting Considerations

- High flow velocity - steep terrain and/or large tributary area may cause concentrated, erosive flows
- Sheet flow - shallow, evenly-distributed flow across entire width of strip required. The maximum flow path from a contributory impervious surface should not exceed 150 feet.
- Shallow grades - limited site slope may cause ponding
- Availability of pervious area adjacent to impervious area - filter strips require sheet flow from impervious areas

Multi-Use Opportunities

Filter strips can be easily integrated into roadside vegetated buffers or parking lot landscaping.

Filter Strip Design Specifications

The main challenge associated with filter strips is maintaining sheet flow, which is critical to performance of this BMP. If flows are concentrated then little or no treatment of stormwater runoff is achieved and erosive rilling is likely. The use of a level spreading device (e.g., gravel trench) to deliver shallow, evenly-distributed sheet flow to the strip is required. A filter strip is illustrated schematically in Figure 4-1.

Location

1. The use of filter strips is limited to gently sloping areas where the vegetative cover is robust and diffuse, and where shallow flow characteristics are possible.

2. The filter strip shall be located away from building or tree shadows to avoid poor plant growth.
3. Groundwater levels should be at least 2 ft lower than the strip surface to ensure that the filter strip does not remain wet between storms.

Tributary Area Length

1. Maximum length (in the direction of flow towards the filter strip) of the tributary area shall be 150 feet.
2. The lateral slope of the contributing area (parallel to the edge of the pavement) shall be 4% or less.
3. The longitudinal slope of the contributing area (parallel to the flow) should be 5% or less.

Sizing

Step 1: Calculate the design flow

The design flow is calculated as described in *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended).

Step 2: Calculate the design flow depth

The design flow depth (d_f) is calculated based on the width and the slope (parallel to the flow path) using a modified Manning's equation as follows:

$$d_f = [Q_{wq} n_{wq} / 1.49 W s^{0.5}]^{0.6} \quad (\text{Equation 4-1})$$

where:

- d_f = design flow depth (ft)
- Q_{wq} = design flow (cfs)
- W = width (perpendicular to flow = width of impervious surface contributing area (ft)
- s = slope (ft/ft) of strip parallel to flow, average over the whole width
- n_{wq} = Manning's roughness coefficient (0.25-0.3)

If d_f is greater than 1 inch, then a smaller slope is required, or a filter strip cannot be used.

Step 3: Calculate the design velocity

The design flow velocity is based on the design flow, design flow depth, and width of the strip:

$$V_{wq} = Q_{wq} / d_f W \quad (\text{Equation 4-2})$$

Step 4: Calculate the desired length of the filter strip

Determine the required length (L) to achieve a desired minimum residence time of 10 minutes using:

$$L = 60t_{hr}V_{wq} \quad (\text{Equation 4-3})$$

Where:

- L = minimum allowable strip length (ft)
- t_{hr} = hydraulic residence time (s)
- V_{wq} = design flow velocity (fps)

Geometry

1. The width of the filter strip vegetative surface should extend across the full width of the tributary area. The upstream boundary of the filter should be located contiguous to the developed area.
2. The filter strip should be at least 4 feet long (in direction of flow) to provide adequate water quality treatment.
3. Filter strips should be designed on slopes (parallel to the direction of flow) between 2% and 15%; steeper slopes tend to result in concentrated flow. Slopes less than 2% could pond runoff, and in poorly permeable soils, create a mosquito breeding habitat.
4. The lateral slope of strip (parallel to the edge of the pavement, perpendicular to the direction of flow) shall be 4% or less.
5. Grading should be even: a filter strip with uneven grading perpendicular to the flow path will develop flow channels over time.
6. The top of the strip should be installed 2 to 5 inches below the adjacent pavement to allow for vegetation and sediment accumulation at the edge of the strip. A beveled transition is acceptable and may be required per roadside design specifications.
7. Both the top and toe of the slope should be as flat as possible to encourage sheet flow and prevent channeling and erosion. For engineered vegetative strips, the facility surface should be graded flat prior to placement of vegetation.

Energy Dissipation / Level Spreading

Runoff entering a filter strip must not be concentrated. A flow spreader shall be installed at the edge of the pavement to uniformly distribute the flow along the entire width of the filter strip.

1. At a minimum, a gravel flow spreader (gravel-filled trench) shall be placed between the impervious area contributing flows and the filter strip, and meet the following requirements:
 - a) The gravel flow spreader shall be a minimum of 6 inches deep and shall be 12 inches wide.

- b) The gravel shall be a minimum of 1 inch below the pavement surface. *Intent: This allows sediment from the paved surface to be accommodated without blocking drainage onto the strip.*
 - c) Where the ground surface is not level, the gravel spreader must be installed so that the bottom of the gravel trench and the outlet lip are level.
 - d) Along roadways, gravel flow spreaders must be placed and designed in accordance with County road design specifications for compacted road shoulders.
2. A notched curb spreader and through-curb port spreader may only be used in conjunction with a gravel spreader to better ensure that water sheet-flows onto the strip, provided:
- a. Curb ports use fabricated openings that allow concrete curbing to be poured or extruded while still providing an opening through the curb to admit water to the filter strip. Openings in the curb shall be at regular intervals but at least every 6 feet. The width of each curb port opening shall be a minimum of 11 inches. Approximately 15 percent or more of the curb section length should be in open ports, and no port should discharge more than about 10 percent of the flow.
 - b. Interrupted curbs are sections of curb placed to have gaps spaced at regular intervals along the total width of the treatment area. At a minimum, gaps shall be every 6 feet to allow distribution of flows into the treatment facility before they become too concentrated. The opening shall be a minimum of 11 inches. As a general rule, no opening should discharge more than 10 percent of the overall flow entering the facility.
3. Energy dissipaters are needed in a filter strip if sudden slope drops occur, such as locations where flows in a filter strip pass over a rockery or retaining wall aligned perpendicular to the direction of flow. Adequate energy dissipation at the base of a drop section can be provided by a riprap pad.

Access

Access shall be provided at the upper edge of a filter strip to enable maintenance of the inflow spreader throughout the strip width and allow access for mowing equipment.

Water depth and Velocity

- 1. The design water depth should not exceed 1 inch.
- 2. Runoff flow velocities should not exceed approximately 1 foot per second across the vegetated surface.

Soils

- 1. Filter strip soils shall be amended with 2 inches of well-rotted compost, unless the organic content is already greater than 10%. The compost shall be mixed into the native soils to a depth of 6 inches to prevent soil layering and washout of compost. The compost will contain no sawdust, green or under-composted material, or any other toxic or harmful

substance. It should contain no un-sterilized manure which can lead to high levels of pathogen indicators (coliform bacteria) in the runoff.


Vegetation

1. The filter area should be densely vegetated with a mix of erosion-resistant plant species that effectively bind the soil. Native or adapted grasses are preferred because they generally require less fertilizer and are more drought resistant than exotic plants.
2. Sod can be used instead of grass seed, as long as there is complete coverage.
3. Irrigation shall be provided to establish the grass.


Trees or shrubs shall not be used because they shade the turf.

Restricted Construction Materials

The use of treated wood or galvanized metal anywhere inside the facility is prohibited.



Plan View
(Not to Scale)



Section A - A'
(Not to Scale)

NOTES:

- ① MAXIMUM LENGTH OF IMPERVIOUS TRIBUTARY AREA SHALL BE 150'.
- ② OPTIONAL SLOTTED WHEEL STOPS MAY BE USED.
- ③ GRAVEL TRENCH 6" DEEP BY 12" WIDE MIN SHALL BE PROVIDED.
- ④ VEGETATED FILTER STRIP SURFACE. SLOPE SHALL BE BETWEEN 2% TO 5%. WIDTH MUST BE EQUAL OR GREATER THAN THE WIDTH OF THE TRIBUTARY AREA.
- ⑤ CONVEYANCE SYSTEM WIDTH MUST BE EQUAL OR GREATER THAN THE WIDTH OF THE TRIBUTARY AREA.
- ⑥ INSTALL SWALE OR OTHER CONVEYANCE SYSTEM DOWNSTREAM OF FILTER STRIP.
- ⑦ TOP OF FILTER STRIP SHALL BE 2" - 5" BELOW TOP OF ADJACENT PAVEMENT.
- ⑧ AMEND SOILS WITH 2" OF COMPOST TILLED INTO 6" OF NATIVE SOIL UNLESS NATIVE SOIL ORGANIC CONTENT > 10%.

Figure 4-1
VEGETATED STRIP FILTER

Filter Strip Operations and Maintenance

General Requirements

Filter strips mainly require vegetation management; therefore little special training is needed for maintenance crews. Typical maintenance activities and frequencies include:

1. Inspect strips at least twice annually for erosion or damage to vegetation, preferably at the end of the wet season to schedule summer maintenance and in the fall to ensure the strip is ready for winter (see Appendix E for guidance on facility inspection). However, additional inspection after periods of heavy runoff is most desirable. The strip should be checked for debris and litter and areas of sediment accumulation (see Appendix F for dry extended detention basin inspection and maintenance checklist).
2. Mow as frequently as necessary (at least twice a year) for safety and aesthetics or to suppress weeds and woody vegetation.
3. Trash tends to accumulate in strip areas, particularly along roadways. The need for litter removal should be determined through periodic inspection. Litter should always be removed prior to mowing.
4. Regularly inspect vegetated buffer strips for pools of standing water. Vegetated filter strips can become a nuisance due to mosquito breeding in level spreaders (unless designed to dewater completely in less than 72 hours), in pools of standing water if obstructions develop (e.g. debris accumulation, invasive vegetation), and/or if proper drainage slopes are not implemented and maintained.
5. Activities that lead to ruts or depressions on the surface of the filter strip shall be prevented or the integrity of the strip shall be restored by leveling and reseeding. Examples are vehicle tracks, utility maintenance, and pedestrian (short-cut) tracks.

Maintenance Standards

A summary of the routine and major maintenance activities recommended for filter strips is shown in Table 4-1. Detailed Routine and major maintenance standards are listed in Tables 4-2 and 4-3.

Table 4-1: Filter Strip Routine and Major Maintenance Quick Guide

Inspection and Maintenance Activities Summary	
Routine Maintenance	• Remove excess sediment as needed • Stabilize/repair minor erosion and scouring with crushed gravel • Remove trash and debris • Remove any evidence of visual contamination from floatables such as oil and grease • Mow routinely to maintain ideal grass height and to suppress weeds • Remove invasive vegetation and revegetate with non-invasive species • Take photographs before and after maintenance (encouraged)
Major Maintenance	• Regrade and revegetate to repair damage from severe erosion/scour channelization and to restore sheet flow • Clean and reset flow spreaders as needed to restore original function

Table 4-2: Routine Maintenance – Filter Strips

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Sediment Accumulation	Sediment depth exceeds 2 inches or covers vegetation.	Sediment deposits removed, leveled so slope is even and flows pass evenly through strip.	Semi-annually, prior to wet season and after the wet season After major storm events (>0.75 in/24 hrs) if spot checks indicate widespread damage/maintenance needs
Erosion/Scouring	Eroded or scoured areas due to flow channelization, or higher flows.	No erosion or scouring evident. For ruts or bare areas less than 12 inches wide, damaged areas repaired by filling with crushed gravel. The grass will creep in over the rock in time.	
Flow Spreader Clogged/Uneven	Flow spreader uneven or clogged so that flows are not uniformly distributed through entire filter width.	Spreader leveled and cleaned so that flows are spread evenly over entire filter width.	
Visual Contaminants and Pollution	Any visual evidence of oil, gasoline, contaminants or other pollutants.	No visual contaminants or pollutants present.	

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Aesthetics	Minor vegetation removal and thinning. Mowing berms and surroundings	Facility is well kept.	Semi-annually (or as dictated by agreement between County and landscape contractor) Litter removal and mowing frequency is dependent on site conditions and desired aesthetics and should be done at a frequency to meet those objectives
Vegetation Length, Nuisance Weeds	When the grass becomes excessively tall (greater than 10-inches); when nuisance weeds and other vegetation starts to take over.	Grass mowed, nuisance vegetation controlled, such that flow is not impeded. Grass mowed to a height between 2-4 inches and clippings removed.	
Trash and Debris Accumulation	Trash and debris accumulated on the filter strip.	Trash and debris removed from filter.	
Noxious Weeds	Any evidence of noxious weeds.	All noxious weeds eradicated and future establishment controlled with use of Integrated Pest Management (IPM) techniques, if applicable. See http://www.ipm.ucdavis.edu/ for more information.	

Table 4-3: Major Maintenance – Filter Strips

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Erosion/Scouring	Bare spots greater than 12 inches	No erosion visible. Large, bare areas greater than 12 inches wide regraded and reseeded.	As needed

5. BIORETENTION

Definition

Bioretention areas are vegetated (i.e., landscaped) shallow depressions that provide storage, infiltration, and evapotranspiration. Bioretention areas also remove pollutants by filtering stormwater through plants adapted to the local climate and soil moisture conditions and an engineered soil mix. In bioretention areas, pore spaces, microbes, and organic material in the engineered soils help to retain water in the form of soil moisture and to promote the adsorption of pollutants (e.g., dissolved metals and petroleum hydrocarbons) into the soil matrix. Plants utilize soil moisture and promote the drying of the soil through transpiration. If no underdrain is provided, exfiltration of the stored water in the bioretention area engineered soil into the underlying soils occurs over a period of days. For areas with low permeability native soils or steep slopes, bioretention areas can be designed with an underdrain system that routes the treated runoff to the storm drain system rather than depending on infiltration. In this situation, treatment is achieved mainly through filtration and adsorption in the vegetation and engineered soils in the biofiltration area.

General Constraints and Siting Considerations

- Native soil infiltration rate - underdrain is required in low permeability soils
- Vertical relief and proximity to storm drain - site must have adequate relief between land surface and storm drain to permit vertical percolation through the soil media and collection and conveyance in underdrain to storm drain system
- Depth to groundwater - shallow groundwater table may not permit complete drawdown between storms

Multi-Use Opportunities

Bioretention areas can be applied in various settings, including:

- Individual lots for rooftop, driveway, and other on-lot impervious surface infiltration.
- Shared facilities located in common areas for individual lots.
- Areas within loop roads or cul-de-sacs.
- Landscaped parking lot islands.
- Within right-of-ways along roads.
- Common landscaped areas in apartment complexes or other multifamily housing designs.
- In parks and along open space edges.

Bioretention Design Specifications

Geotechnical and Landscape Considerations

1. Bioretention areas located within 50 feet of a sensitive steep slope shall incorporate an underdrain. A geotechnical report must be provided to address the potential effects of

infiltration on the steep slope if a bioretention area without an underdrain is sited within 200 feet of the slope or hazardous landslide area.

2. An underdrain should be provided for the bioretention area when native soils permeability is less than 0.5 inches/hour, as determined by an in-situ percolation test.

Pretreatment

1. Bioretention areas shall use a filter strip to pretreat and spread incoming flows from roadways. Bioretention areas that treat runoff from residential roofs, sidewalks, driveways, or other "cleaner" surfaces do not require pretreatment.
2. If sheet flow is conveyed to the treatment area over stabilized grassed areas, the site must be graded in such a way that minimizes erosive conditions. Sheet flow velocities shall not exceed 1 foot per second.

Sizing Criteria

Bioretention areas can be sized using one of two methods: a simple sizing method or a routing method. The simple sizing procedure is summarized below. Continuous simulation modeling, routing spreadsheets, and/or other forms of routing modeling that incorporate rainfall-runoff relationships and infiltrative (flow) capacities of bioretention may be used to size facilities. Alternative sizing methodologies should be prepared with good engineering practices. For the routing modeling method, refer to Section 10 - Sand Filters. A bioretention sizing worksheet and example are provided in Appendix B.

With either method, the runoff entering the facility must completely drain the ponding area and the planting soil within 48 hours. Bioretention provides storage above ground, in the voids of the planting soil, and (if used) in the voids of gravel drainage layer. Bioretention is to be sized, with or without underdrains, such that the SUSMP volume will fill the available ponding depth, the void spaces in the planting soil, and (if provided) the gravel drainage layer.

Step 1: Calculate the design volume

Bioretention areas should be sized to capture and treat the SUSMP volume (see *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended)).

Step 2: Determine the design percolation rate

The design percolation rate, P_{design} , will differ depending on whether the native soil percolation rate falls above or below a rate of 0.5 in/hr. Sites where the native soil percolation rate is equal to or exceeds 0.5 in/hr, measured per the Policy for New Percolation Basin Testing, Design, and Maintenance (see Appendix G), do not require the use of an underdrain, while sites where native soil percolation rates are less than 0.5 in/hr require the use of an underdrain.

Option 1: Determining the design percolation rate, P_{design} , with an underdrain

If the bioretention includes an underdrain, then the design percolation rate will be that of the planting soil. The planting soil design specifications listed below are assumed to have a design percolation rate of 2.5 in/hr.

Option 2: Determining the design percolation rate, P_{design} , of the native subsoil (no underdrain)

If the bioretention area does not include an underdrain, then the design percolation rate will be the limiting percolation rate (slowest) of the native subsoil, using in-situ tests described in Appendix G, and the planting soil. In most cases, the limiting percolation rate will be that of the native subsoil. It is important that adequate conservatism is incorporated in the selection of design percolation rates. The design percolation rate discussed here is the percolation rate of the underlying subsoil and not the percolation rate of the planting soil.

The design percolation rate may be calculated by applying correction factors to the field-measured percolation rate. A percolation testing correction factor applied to bioretention sizing of 0.25 (providing a safety factor of 4) should be applied to results of the percolation testing conducted per Appendix G.

$$P_{design} = P_{measured} \times F_{testing} \quad (\text{Equation 5-1})$$

Where:

- P_{design} = design percolation rate (in/hr)
- $P_{measured}$ = field measured percolation rate (in/hr)
- $F_{testing}$ = correction factor for testing method; use 0.25

Step 3: Calculate the bioretention surface area

Determine the bottom surface area of the bioretention (surface area at the base of sideslopes, not at the top of sideslopes) using the following equation:

$$A = \frac{(V_{design})(l)}{(t)(P_{design}/12)(d+l)} \quad (\text{Equation 5-2})$$

Where:

- V_{design} = SUSMP volume (ft³)
- P_{design} = design percolation rate (in/hr)
- d = ponding depth (ft) [max 1.5 ft]
- l = depth of planting media (ft) [min 2 ft]
- t = required drawdown time (hr) [max 48 hrs]

Gravel Drainage Layer. A gravel drainage layer should be provided where underlying native soil permeability is greater than 0.5 in/hr and percolation is allowed. The base of the drainage layer should have zero slope (level). The drawdown time for the gravel drainage layer should not exceed 72 hours. The planting soil and gravel layers should be separated with a thin, 2- to 4-inch layer of sand and a thin layer (nominally two inches) of #8 stone.

Determine the maximum depth of runoff that can be infiltrated within the required drain time (72 hr) as follows:

$$d_{\max} = \frac{P_{\text{design}}}{12} * t \quad (\text{Equation 5-3})$$

Where:

- $d_{\max}$ = the maximum depth of water that can be infiltrated within the required drain time (ft)
- P_{design} = native subsoil design percolation rate (in/hr) [measured percolation rate x 0.25]
- t = required drain time (hrs) [72 hours]

Choose the gravel drainage layer depth (l) such that:

$$d_{\max} \geq n * l \quad (\text{Equation 5-4})$$

Where:

- $d_{\max}$ = the maximum depth of water that can be infiltrated within the required drain time (ft)
- n = gravel drainage layer porosity (unitless)
- l = depth of gravel drainage layer (ft)

Calculate the infiltrating surface area (filter bottom area) required:

$$A = \frac{V_{\text{design}}}{\frac{TP_{\text{design}}}{12} + nl} * t \quad (\text{Equation 5-5})$$

Where:

- V_{design} = SUSMP volume (ft³)
- n = gravel drainage layer porosity (unitless)
- P_{design} = native subsoil design percolation rate (in/hr) [measured percolation rate x 0.25]
- l = depth of gravel drainage layer (ft)
- T = fill time (time to fill bioretention area with water) (hrs) [use 2 hours for most designs]
- A = surface area of gravel drainage layer (ft²)

Geometry

1. Bioretention areas shall be sized to capture and treat the SUSMP volume (see *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended)) with an 18-inch maximum ponding depth.
2. Planting soil depth shall be a minimum of 2 feet, although 3 feet is preferred. *Intent: The planting soil depth should provide a beneficial root zone for the chosen plant palette and adequate water storage for the water quality design volume. A deeper planting soil depth will provide a smaller surface area footprint.*
3. Bioretention areas shall be designed to drain in less than 48 hours. *Intent: Soils must be allowed to dry out periodically in order to restore hydraulic capacity to receive flows from subsequent storms, maintain percolation rates, maintain adequate soil oxygen levels for healthy soil biota and vegetation, and to provide proper soil conditions for biodegradation and retention of pollutants.*

Flow Entrance and Energy Dissipation

The following types of flow entrance can be used for bioretention cells:

1. Dispersed, low velocity flow across a landscape area. Dispersed flow may not be possible given space limitations or if the facility is controlling roadway or parking lot flows where curbs are mandatory.
2. Dispersed flow across pavement or gravel and past wheel stops for parking areas.
3. Flow spreading trench around perimeter of bioretention area. May be filled with pea gravel or vegetated with 3:1 side slopes similar to a swale. A vertical-walled open trench may also be used at the discretion of the County.
4. Curb cuts for roadside or parking lot areas: curb cuts should include rock or other erosion protection material in the channel entrance to dissipate energy. Flow entrance should drop 2 to 3 inches from curb line and provide an area for settling and periodic removal of sediment and coarse material before flow dissipates to the remainder of the cell.
5. Pipe flow entrance: Piped entrances, such as roof downspouts, should include rock, splash blocks, or other erosion protection material at the entrance to dissipate energy and disperse flows.
6. Woody plants (trees, shrubs, etc.) can restrict or concentrate flows and can be damaged by erosion around the root ball and shall not be placed directly in the entrance flow path.

Underdrains

If underdrains are required, then they must meet the following criteria:

1. 6-inch minimum diameter.

2. Underdrains must be made of slotted, polyvinyl chloride (PVC) pipe (PVC SDR 35 or approved equivalent). *Intent: As compared to round-hole perforated pipe, slotted underdrains provide greater intake capacity, clog resistant drainage, and reduced entrance velocity into the pipe, thereby reducing the chances of solids migration.*
3. Slotted pipe shall have 2 to 4 rows of slots cut perpendicular to the axis of the pipe or at right angles to the pitch of corrugations. Slots shall be 0.04 to 0.1-inch and shall have a length of 1-inch to 1.25-inch. Slots shall be longitudinally spaced such that the pipe has a minimum of one square inch per lineal foot.
4. Underdrains shall be sloped at a minimum of 0.5%.
5. Rigid non-perforated observation pipes with a diameter equal to the underdrain diameter shall be connected to the underdrain every 250 to 300 feet to provide a clean-out port as well as an observation well to monitor dewatering rates. The wells/cleanouts shall be connected to the perforated underdrain with the appropriate manufactured connections. The wells/cleanouts shall extend 6 inches above the top elevation of the bioretention facility mulch, and shall be capped with a lockable screw cap. The ends of underdrain pipes not terminating in an observation well/cleanout shall also be capped.
6. The following aggregate shall be used to provide a gravel blanket and bedding for the underdrain pipe. Place the underdrain on a bed of washed aggregate at a minimum thickness of 6 inches and cover with the same aggregate to provide a 1-foot minimum depth around the top and sides of the slotted pipe.

<u>Sieve size</u>	<u>Percent Passing</u>
¾ inch	100
¼ inch	30-60
US No. 8	20-50
US No. 50	3-12
US No. 200	0-1

7. At the option of the designer/geotechnical engineer, a geotextile fabric may be placed between the planting media and the drain rock. If a geotextile fabric is used it must meet the following minimum materials requirements.

Geotextile Property	Value	Test Method
Trapezoidal Tear (lbs)	40 (min)	ASTM D4533
Permeability (cm/sec)	0.2 (min)	ASTM D4491
AOS (sieve size)	#60 - #70 (min)	ASTM D4751
Ultraviolet resistance	70% or greater	ASTM D4355

Preferably, aggregate should be used in place of filter fabric to reduce the potential for clogging. This aggregate layer should consist of 2 - 4 inches of washed sand underlain with 2 inches of Choking Stone (Typically #8 or #89 washed).

8. The underdrain shall be elevated from the bottom of the bioretention facility by 6 inches within the gravel blanket to create a fluctuating anaerobic/aerobic zone below the drain

pipe. *Intent: denitrification within the anaerobic/anoxic zone is facilitated by microbes using forms of nitrogen (NO₂ and NO₃) instead of oxygen for respiration.*

9. The underdrain must drain freely to an acceptable discharge point. The underdrain can be connected to a downstream open conveyance (vegetated swale), to another bioretention cell as part of a connected treatment system, daylight to a vegetated dispersion area using an effective flow dispersion device, stored for reuse, or to a storm drain.

Overflow

An overflow device is required at the 18-inch ponding depth. The following, or equivalent, should be provided:

1. A vertical PVC pipe (SDR 35) shall be connected to the underdrain.
2. The overflow riser(s) should be 6 inches or greater in diameter, so it can be cleaned without damage to the pipe. The vertical pipe will provide access to cleaning the underdrains.
3. The inlet to the riser should be 6 inches above the planting media, and be capped with a spider cap to exclude floating mulch and debris.

Hydraulic Restriction Layers

Infiltration pathways may need to be restricted due to the close proximity of roads, foundations, or other infrastructure. A geomembrane liner may be placed along the vertical walls to reduce lateral flows. This liner shall have a minimum thickness of 30 mils.

Planting/Storage Media

1. The planting media placed in the cell shall be highly permeable and high in organic matter (e.g., loamy sand mixed thoroughly with compost amendment) and a surface mulch layer.
2. Planting media shall consist of 60 to 70% sand, 15 to 25% compost, and 10 to 20% clean topsoil. The organic content of the soil mixture should be 8% to 12%; the pH range should be 5.5 to 7.5.
3. Sand should be free of stones, stumps, roots or other similar objects larger than 5 millimeters, and have the following gradation:

Particle Size (ASTM D422)	% Passing
#4	100
#6	88-100
#8	79-97
#50	11-35
#200	5-15

4. Compost should be free of stones, stumps, roots or other similar objects larger than $\frac{3}{4}$ inches; have a particle size of 98% passing through $\frac{3}{4}$ " screen or smaller; and meet the following characteristics:

- Soluble Salt Concentration: < 10 mmhos/cm (dS/m)
- pH: 5.0-8.5
- Moisture: 30-60% wet weight basis
- Organic Matter: 30-65% dry weight basis
- Stability (Carbon Dioxide evolution rate): >80% relative to positive control
- Maturity (Seed emergence and seedling vigor): >80% relative to positive control
- Physical contaminants: < 1% dry weight basis

5. Topsoil shall be free of stones, stumps, roots or other similar objects larger than 2 inches, and have the following characteristics:

- Soluble salts: < 4.0 mmhos/cm (dS/m)
- pH range: 5.5 to 7.0
- Organic matter: > 5%
- Carbon to Nitrogen Ratio: < 20:1
- Moisture content: 25-55%

Particle Size (ASTM D422, D1140)	% Passing
$\frac{3}{4}$ "	98
Sand (0.05 - 2.0 mm)	50-75
Silt (0.002 - 0.05 mm)	15-40
Clay	< 5

6. The bioretention area shall be covered with 2 – 4 inches (average 3 inches) of mulch at the start and an annual placement of 1-2 inches of mulch beneath plants. *Intent: this will help sustain nutrient levels, suppress weeds, and maintain infiltrative capacity.* Mulch shall be:

- Well-aged, shredded or chipped woody debris or plant material. Well-aged mulch is defined as mulch that has been stockpiled or stored for at least twelve (12) months. Compost meeting the requirements above may also be used (compost is less likely to float and is a better source for organic materials).
- Free of weed seeds, soil, roots and other material that is not bole or branch wood and bark.
- A maximum of 2 to 3 inches thick (*intent: thicker applications can inhibit proper oxygen and carbon dioxide cycling between the soil and atmosphere*).
- Grass clippings or pure bark shall not be used as mulch.

7. Planting media design height shall be marked appropriately, such as a collar on the vertical riser (if installed), or with a stake inserted 2 feet into the planting media and notched to show bioretention surface level and ponding level.

8. The bioretention soil mix shall be tested and meet the following criteria:

Item	Criteria	Test Method
Corrected pH	5.5 – 7.5	ASTM D4972
Magnesium	Minimum 32 ppm	*
Phosphorus (Phosphate - P_2O_5)	Not to exceed 69 ppm	*
Potassium (K_2O)	Minimum 78 ppm	*
Soluble Salts	Not to exceed 500 ppm	*

* Use authorized soil test procedures.

Should the pH fall outside of the acceptable range, it may be modified with lime (to raise) or iron sulfate plus sulfur (to lower). The lime or iron sulfate must be mixed uniformly into the soil mix prior to use in bioretention facilities.

Should the soil mix not meet the minimum requirement for magnesium, it may be modified with magnesium sulfate. Likewise, should the soil mix not meet the minimum requirement for potassium, it may be modified with potash. Magnesium sulfate and potash must be mixed uniformly into the soil mix prior to use in bioretention facilities.

Limestone. Limestone shall contain not less than 85 percent calcium and magnesium carbonates. Dolomitic (magnesium) limestone shall contain at least 10 percent magnesium as magnesium oxide and 85 percent calcium and magnesium carbonates.

Limestone shall conform to the following gradation:

Sieve Size	Minimum Percent Passing By Weight
No. 10	100
No. 20	98
No. 100	50

Iron Sulfate. Iron sulfate shall be a constituent of an approved horticultural product produced as a fertilizer for supplying iron and as a soil acidifier.

Magnesium Sulfate. Magnesium sulfate shall be a constituent of an approved horticultural product produced as a fertilizer.

Potash. Potash (potassium oxide) shall be a constituent of an approved horticultural product produced as a fertilizer.

Plants

1. Prior to installation, a licensed landscape architect shall certify that all plants, unless otherwise specifically permitted, conform to the standards of the current edition of American Standard for Nursery Stock as approved by the American Standards Institute, Inc. All plant grades shall be those established in the current edition of American Standards for Nursery Stock.



2. Shade trees shall have a single main trunk. Trunks shall be free of branches below the following heights:

CALIPER (in)	HEIGHT (ft)
1-1/2 to 2-1/2	5
3	6

- Plant materials shall be tolerant of summer drought, ponding fluctuations, and saturated soil conditions for 48 hours.
- It is recommended that a minimum of three tree, three shrubs, and three herbaceous groundcover species be incorporated to protect against facility failure due to disease and insect infestations of a single species. Plant rooting depths shall not damage underdrain if present. Slotted or perforated underdrain pipe should be more than 5 feet from tree locations (if space allows).
- Native plant species and/or hardy cultivars that are not invasive and do not require chemical inputs shall be used to the maximum extent practicable.

Restricted Construction Materials

The use of treated wood or galvanized metal anywhere inside the facility is prohibited.



NOTES

- ① OVERFLOW DEVICE: VERTICAL RISER OR EQUIVALENT.
- ② PERFORATED 6" MIN PVC PIPE UNDERDRAIN SYSTEM (AS NEEDED). WHERE SOIL CONDITIONS ALLOW, OMIT THE UNDERDRAIN AND INSTALL AN APPROPRIATELY SIZED GRAVEL DRAINAGE LAYER (TYPICALLY A WASHED 57 STONE) BENEATH THE PLANTING MEDIA FOR ENHANCED INFILTRATION.
- ③ OPTIONAL CHOKING GRAVEL LAYER.
- ④ 2' MIN PLANTING MIX; 3' PREFERRED.

Figure 5–1
BIORETENTION

Bioretention Operations and Maintenance

General Requirements

Bioretention areas require annual plant, soil, and mulch layer maintenance to ensure optimum infiltration, storage, and pollutant removal capabilities. In general, bioretention maintenance requirements are typical landscape care procedures and include:

1. **Watering:** Plants should be selected to be drought tolerant and not require watering after establishment (2 to 3 years). Watering may be required during prolonged dry periods after plants are established.
2. **Erosion control:** Inspect flow entrances, ponding area, and surface overflow areas periodically, and replace soil, plant material, and/or mulch layer in areas if erosion has occurred (see Appendix E for guidance on facility inspection and Appendix F for a bioretention inspection and maintenance checklist). Properly designed facilities with appropriate flow velocities should not have erosion problems except perhaps in extreme events. If erosion problems occur the following should be reassessed: (1) flow velocities and gradients within the cell, and (2) flow dissipation and erosion protection strategies in the pretreatment area and flow entrance. If sediment is deposited in the bioretention area, immediately determine the source within the contributing area, stabilize, and remove excess surface deposits.
3. **Plant material:** Depending on aesthetic requirements, occasional pruning and removing of dead plant material may be necessary. Replace all dead plants and if specific plants have a high mortality rate, assess the cause and, if necessary, replace with more appropriate species. Periodic weeding is necessary until plants are established. The weeding schedule should become less frequent if the appropriate plant species and planting density have been used and, as a result, undesirable plants excluded.
4. **Nutrient and pesticides:** The soil mix and plants are selected for optimum fertility, plant establishment, and growth. Nutrient and pesticide inputs should not be required and may degrade the pollutant processing capability of the bioretention area, as well as contribute pollutant loads to receiving waters. By design, bioretention facilities are located in areas where phosphorous and nitrogen levels are often elevated and these should not be limiting nutrients. If in question, have soil analyzed for fertility.
5. **Mulch:** Replace mulch annually in bioretention facilities where heavy metal deposition is likely (e.g., contributing areas that include industrial and auto dealer/repair parking lots and roads). In residential lots or other areas where metal deposition is not a concern, replace or add mulch as needed to maintain a 2 to 3 inch depth at least once every two years.
6. **Soil:** Soil mixes for bioretention facilities are designed to maintain long-term fertility and pollutant processing capability. Estimates from metal attenuation research suggest that metal accumulation should not present an environmental concern for at least 20 years in bioretention systems. Replacing mulch in bioretention facilities where heavy metal

deposition is likely provides an additional level of protection for prolonged performance. If in question, have soil analyzed for fertility and pollutant levels.

Maintenance Standards

A summary of the routine and major maintenance activities recommended for bioretention areas is shown in Table 5-1. Detailed Routine and major maintenance standards are listed in Tables 5-2 and 5-3.

Table 5-1: Bioretention Routine and Major Maintenance Quick Guide

Inspection and Maintenance Activities Summary	
Routine Maintenance	• Repair small eroded areas and ruts by filling with gravel. Overseed bare areas to reestablish vegetation • Remove trash and debris and rake surface soils to mitigate ponding • Remove accumulated fine sediments, dead leaves and trash to restore surface permeability • Remove any evidence of visual contamination from floatables such as oil and grease • Eradicate weeds and prune back excess plant growth that interferes with facility operation. Remove invasive vegetation and replace with non-invasive species • Remove sediment and debris accumulation near inlet and outlet structures to alleviate clogging • Clean and reset flow spreaders (if present) as needed to restore original function • Mow routinely to maintain ideal grass height and to suppress weeds • Periodically observe function under wet weather conditions
Major Maintenance	• Repair structural damage to flow control structures including inlet, outlet and overflow structures • Clean out under-drain, if present, to alleviate ponding. Replace media if ponding or loss of infiltrative capacity persists and revegetate • Regrade and revegetate to repair damage from severe erosion/scour channelization and to restore sheet flow • Take photographs before and after major maintenance (encouraged)

Table 5-2: Routine Maintenance – Bioretention

Defect or Problem	Condition When Maintenance is Needed	Results Expected When Maintenance Is Performed	Frequency
Erosion	Splash pads or spreader incorrectly placed; eroded or scoured areas due to flow channelization, or higher flows.	No erosion on surface of basin. No erosion or scouring evident. For ruts or bare areas less than 12 inches wide, damaged areas repaired by filling with crushed gravel. The grass will creep in over the rock in time.	Annually prior to wet season. After major storm events (>0.75 in/24 hrs) if spot checks of some basins indicate widespread damage/maintenance needs
Standing Water	When water stands in the basin between storms and does not drain freely (with 36- 48 hours after storm event).	Water drains completely from basin as designed and surface is clear of trash and debris. Underdrains (if installed) are cleared.	
Loss of Surface Permeability	Accumulation of fine sediments, dead leaves, trash and other debris on surface	Surface permeability restored. Surface layer removed and replaced with fresh mulch.	
Visual Contaminants and Pollution	Any visual evidence of oil, gasoline, contaminants or other pollutants.	No visual contaminants or pollutants present.	Monthly (or as dictated by agreement between County and landscape contractor)
Vegetation	Weeds, excessive plant growth, plants interfering with basin operation, plants diseased or dying	Basin tidy, plants healthy and pruned. Any plants that interfere with function are removed. Invasive or non-acclimated plants replaced.	
Inlet/Overflow	Inlet/outlet areas clogged with sediment and/or debris.	Material removed so that there is no clogging or blockage of the inlet or overflow area.	
Trash and Debris	Any trash and debris which exceed 5 cubic feet per 1,000 square feet (one standard garbage can).	Trash and debris removed and facility looks well kept.	

Table 5-3: Major Maintenance – Bioretention

Defect or Problem	Condition When Maintenance is Needed	Results Expected When Maintenance Is Performed	Frequency
Standing water	When water stands in the basin between storms and does not drain freely (with 36- 48 hours after storm event).	Filter media (sand, gravel, and topsoil) and vegetation removed and replaced.	Annually prior to wet season
Erosion/ Scouring	Bare spots greater than 12 inches	No erosion on surface of basin. Large bare areas are regraded and reseeded/replanted.	As needed

6. INFILTRATION FACILITIES

Definition

Infiltration facilities included in this manual include infiltration basins and infiltration trenches. In general, infiltration facilities are similar to stormwater detention systems but are constructed with a highly permeable base that is specifically designed to infiltrate runoff. It is usually not practical to infiltrate runoff at the same rate that it is generated; therefore, these facilities generally include both a storage component and a drainage component.

Infiltration basins are usually shallow with flat, vegetated bottoms and side slopes and can be incised by excavating a depression below the existing grade or constructed above grade by constructing a perimeter berm.

Infiltration trenches are long, narrow, rock-filled trenches that receive stormwater runoff from small drainage areas. These facilities may include a shallow depression at the surface, but the majority of runoff is stored in the void space between the stones and infiltrates through the sides and bottom of the trench.

Pretreatment BMPs such as swales, filter strips, and sediment forebays/basins/manholes that minimize sediment loads to infiltration facilities are recommended to increase longevity and reduce the maintenance burden of infiltration facilities.

Infiltration facilities are ideal for hydromodification control, where surface runoff volume reductions are desired. Infiltration facilities are also good candidates for the removal of fine sediment, particulate bound pollutants, and bacteria. The primary pollutant removal processes in infiltration facilities include volume and associated pollutant load reduction, sedimentation, filtration, and adsorption. Sedimentation of coarse particles should, however, be minimized in infiltration facilities through the use of appropriate pretreatment devices to prevent clogging. Infiltration facilities can be used to provide complete reduction of pollutant loads to downstream receiving water systems. Ideal sites for infiltration facilities are areas with permeable soils and depth to seasonally high groundwater levels that is at least 10 feet below the existing ground surface. Infiltration facilities should not be used for industrial sites or locations where hazardous materials spills may occur.

General Constraints and Siting Considerations

- Slope stability - infiltration facilities are not permitted near steep slope hazard areas
- Setbacks - a minimum setback from structures or leach fields is required for infiltration facilities
- Native soil infiltration rate - performance can be limited by the permeability of native soils
- Depth to groundwater - a vertical separation is required between the infiltration surface and the shallow groundwater table to ensure that the facility will completely drain between storms and that infiltrating water will receive adequate treatment through the soils before it reaches the groundwater

- Depth to bedrock or impervious soil layer - a shallow confining layer may inhibit complete infiltration of SUSMP volume
- Contaminated soils - infiltration facilities are not permitted at sites with existing soil contamination
- Surface space availability - large footprint required
- High sediment loading rates - may clog quickly if sediment loads are high (e.g., unstabilized site) or flows are not adequately pretreated

Multi-Use Opportunities

Under special circumstances an infiltration basin may be combined with a detention basin to provide both water quality control and peak flow control. However, this practice is not recommended at sites receiving high sediment loadings due to the potential for clogging and the associated maintenance burden. Infiltration basins may also be integrated into the design of a park or playfield. Recreational multi-use facilities must be inspected after every storm and may require a greater maintenance frequency than dedicated water quality basins as to ensure aesthetics and public safety are not compromised. Any planned multi-use facility must obtain approval by the affected County department(s).

Infiltration Facility Design Specifications

Geotechnical Considerations

Due to the potential to contaminate groundwater, cause slope instability, impact surrounding structures, and potential for insufficient infiltration capacity, an extensive geotechnical site investigation must be undertaken early in the site planning process to verify site suitability for the installation of infiltration facilities. Soil infiltration rates and the water table depth should be evaluated to ensure that conditions are satisfactory for proper operation of an infiltration facility. See Appendix G, Policy for New Percolation Basin Testing, Design, and Maintenance.

The applicant must demonstrate through infiltration testing, soil logs, and the written opinion of a licensed civil engineer that sufficiently permeable soils exist on site to allow the construction of a properly functioning infiltration facility.

1. Infiltration facilities require a minimum soil infiltration rate of 0.5 inches/hour. If infiltration rates exceed 2.4 inches/hour, then the runoff should be fully treated in an upstream BMP prior to infiltration to protect groundwater quality. Pretreatment for coarse sediment removal is required in all instances.
2. Groundwater separation must be at least 10 feet from the basin or trench bottom to the measured groundwater elevation and at least 100 horizontal feet from any drinking water wells. Measurements of groundwater levels must be made during the time when water level is expected to be at a maximum (i.e., toward the end of the wet season).
3. Infiltration facilities are not suitable to collect runoff from sites that use or store chemicals or hazardous materials outside. [*Note: Infiltration facilities are not suitable for industrial*

sites or locations where spills can occur. In these areas, one of the other BMPs in this manual should be used].

4. Infiltration facilities are not suitable for un-remediated "brownfield sites" where there is known groundwater or soil contamination.
5. Sites with a slope greater than 25% (4:1) shall be excluded. A geotechnical analysis and report addressing slope stability are required if located on slopes greater than 15%.
6. An infiltration facility must not be located within 15 feet of a 2:1 or greater slope. The geotechnical report must address the potential effects of infiltration on the stability of the slope if the facility is sited within 200 feet of the slope or a mapped landslide.

Site Geotechnical Investigation

1. A geotechnical report shall state whether the site is suitable for the proposed infiltration basin, and shall recommend a design infiltration rate (see "Design Infiltration Rate" under the "Sizing Criteria" section). The geotechnical investigation should be such that a good understanding is gained as to how the stormwater runoff will move in the soil (horizontally or vertically) and if there are any geological conditions that could inhibit the movement of water.

Setbacks

1. Infiltration facilities shall be setback a minimum of 100 feet from proposed or existing septic system drain fields and drinking water wells.
2. Infiltration facilities shall be setback a minimum of 15 feet from any 2:1 or steeper slope.
3. Infiltration facilities shall be setback 8 feet from any structural foundation. The 8-foot setback may be reduced to a minimum of 5 feet if geotechnical evaluations address the potential impacts of the facility's phreatic surface on adjacent structural foundations.

Pretreatment

Pretreatment is provided for infiltration facilities in order to reduce the sediment load entering the facility and maintain the infiltration rate of the basin. Pretreatment refers to design features that provide settling of large particles before runoff reaches a management practice; easing the long-term maintenance burden. Pretreatment is important for all structural stormwater management practices, but it is particularly important for infiltration practices. To ensure that pretreatment mechanisms are effective, designers shall incorporate sediment reduction practices. Sediment reductions BMPs may include vegetated swales, vegetated filter strips, sedimentation basins or forebays, sedimentation manholes and hydrodynamic separation devices. The use of at least two pretreatment devices is highly recommended for infiltration facilities.

For design specification of selected pre-treatment devices, refer to:

- Filter Strip (Section 4)

- Vegetated Swales (Section 3)
- Proprietary Devices (Section 11)

Sizing Criteria

As with sand filters, infiltration facilities can be sized using one of two methods: a simple sizing method or a routing modeling method. With either method the SUSMP volume must be completely infiltrated within 72 hours. Infiltration basins provide the majority of storage above ground while infiltration trenches provide the majority of storage in the voids of the rock fill. The simple sizing procedures provided below can be used for either infiltration basins or trenches. For the routing modeling method, refer to Section 10 - Sand Filters.

Step 1: Calculate the design volume

Infiltration facilities shall be sized to capture and infiltrate the SUSMP volume (see *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended)).

Step 2: Determine the design percolation rate

The percolation rate will decline between maintenance cycles as the surface becomes occluded and particulates accumulate in the infiltrative layer. Monitoring of actual facility performance has shown that the full-scale infiltration rate is far lower than the rate measured by small-scale testing. It is important that adequate conservatism is incorporated in the selection of design percolation rates. For infiltration trenches, the design percolation rate discussed here is the percolation rate of the underlying soils and not the percolation rate of the filter media bed (refer to the "Facility Geometry" section for the recommended composition of the filter media bed for infiltration trenches).

A simplified method may be used to determine the design percolation rate by applying correction factors to the field measured percolation rate. These factors take into account uncertainty in measurement procedure, depth to water table or impermeable strata, infiltration facility geometry, and long term reductions in permeability due to biofouling and accumulation of fines.

$$P_{design} = P_{measured} \times F_{testing} \times F_{plugging} \times F_{geometry} \quad (\text{Equation 6-1})$$

Where:

P_{design}	=	design percolation rate (in/hr)
$P_{measured}$	=	measured percolation rate (per Policy for New Percolation Basin Testing, Design, and Maintenance, Appendix G or as amended) (in/hr)
F	=	correction factor

$F_{testing}$ takes into account uncertainties in the testing method and is 0.5.

$F_{plugging}$ accounts for reductions in infiltration rates over the long term caused by plugging of soils. The factor is:

- 0.7 for loams and sandy loams
- 0.8 for fine sands and loamy sands
- 0.9 for medium sands
- 1.0 for coarse sands or cobbles or for any facility preceded by a full specification filter strip or vegetated swale.

$F_{geometry}$ accounts for the influence of facility geometry and depth to the water table or impervious strata on the actual infiltration rate. $F_{geometry}$ must be between 0.25 and 1.0 as determined by the following equation:

$$F_{geometry} = 4 D/W + 0.05 \quad (\text{Equation 6-2})$$

Where:

- D = depth from the bottom of the facility to the maximum wet-season water table elevation or nearest impervious layer, whichever is less (ft)
 W = width of the facility (ft)

Note that adjusted percolation rate (P_{design}) may be different for basins and trenches installed in the same location due to differences in dimension.

Step 3: Calculate the surface area

Determine the size of the required infiltrating surface by assuming the SUSMP volume will fill the available ponding depth plus the void spaces based on the computed porosity of the filter media (normally about 32%).

1. Determine the maximum depth of runoff that can be infiltrated within the required drain time (72 hr) as follows:

$$d_{max} = \frac{P_{design}}{12} t \quad (\text{Equation 6-3})$$

Where:

- t = required drain time (hrs) [Use 72 hours]
 P_{design} = design percolation rate of underlying soils (in/hr)
 d_{max} = the maximum depth of water that can be infiltrated within the required drain time (ft)

2. Choose the ponding depth (d_p) and/or trench depth (d_t) such that:

$$d_{max} \geq d_p \quad \text{For Infiltration Basins} \quad (\text{Equation 6-4})$$

$$d_{max} \geq n_t d_t + d_p \quad \text{For Infiltration Trenches} \quad (\text{Equation 6-5})$$

Where:

- d_p = ponding depth (ft)
 n_t = trench fill aggregate porosity (unitless)
 d_t = depth of trench fill (ft)
 d_{max} = the maximum depth of water that can be infiltrated within the required drain time (ft)

3. Calculate infiltrating surface area (filter bottom area) required:

$$A = \frac{WQ_v}{((TP_{design}/12) + d_p)} \quad \text{For Infiltration Basins} \quad (\text{Equation 6-6})$$

$$A = \frac{WQ_v}{((TP_{design}/12) + n_t d_t + d_p)} \quad \text{For Infiltration Trenches} \quad (\text{Equation 6-7})$$

(Adapted from Georgia Stormwater Manual: <http://www.georgiastormwater.com/vol2/3-2-5.pdf>)

Where:

- WQ_v = design water quality volume (ft³)
 n_t = trench fill aggregate porosity (unitless)
 P_{design} = design percolation rate (in/hr)
 d_p = ponding depth (ft)
 d_t = depth of trench fill (ft)
 T = fill time (time to fill to max ponding depth with water) (hrs) [use 2 hours for most designs]

Facility Geometry**Infiltration Basins**

1. Infiltration basins shall be designed and constructed with the flattest bottom slope possible to promote uniform ponding and infiltration across the facility.
2. A sediment forebay is required unless adequate pretreatment is provided in a separate pretreatment unit (e.g. upstream hydrodynamic device or vegetated swale) to address sediment loads, or the tributary catchment is mostly impervious. The sediment forebay, if present, shall have a volume equal to 25% of the total infiltration basin volume.
3. The forebay shall be designed with a minimum length to width ratio of 2:1 and must completely drain to the main basin through an 8-inch minimum low-flow outlet.
4. All inlets shall enter the sediment forebay. If there are multiple inlets into the forebay, the length-to-width ratio shall be based on the average flowpath length for all inlets.
5. Side-slopes shall be no steeper than 3H:1V.

Infiltration Trench

1. Infiltration trenches shall be at least 24 inches wide and 3 to 5 feet deep.
2. The longitudinal slope of the trench should not exceed 3%
3. The filter bed media layers shall have the following composition and thickness:
 - Top layer (top 2 inches of pea gravel)
 - Middle layer (3-5 feet of washed 2 to 6-inch gravel). Void space should be in the range of 30 percent to 40 percent.
 - Bottom layer (6 inches of sand or fabric equivalent)
4. An observation well should be installed at the lower end of the infiltration trench to check for water levels and drawdown time. A typical observation well consists of a slotted PVC well screen, 4 to 6 inches in diameter, capped with a lockable, above-ground lid. Ensure that the screened interval is short and placed near the bottom of the trench to avoid piping.

Embankments

1. Embankments are earthen slopes or berms used to detain or redirect the flow of water.
2. The minimum top width of all berm embankments shall be 20 feet, or as approved by the Geotechnical and Materials Division.
3. Basin berm embankments must be constructed on native consolidated soil (or adequately compacted and stable fill soils analyzed by a licensed geotechnical engineer) free of loose surface soil materials, roots, and other organic debris.
4. Earthworks shall be in accordance with Section 300-6 of the Standard Specifications for Public Works Construction, most recent edition.
5. Basin berm embankments greater than 4 feet in height must be constructed by excavating a key equal to 50% of the berm embankment cross-sectional height and width. This requirement may be waived if specifically recommended by a licensed geotechnical engineer.
6. The berm embankment shall be constructed of compacted soil (95% minimum dry density, modified proctor method per ASTM D1557), placed in 6-inch lifts.
7. Low growing native or non-invasive perennial grasses shall be planted on downstream embankment slopes. See the Vegetation Management on Embankment Dams of Public Works' Debris Control Facilities, Attachment B, for a recommended plant list.

Additional Control Functions

Infiltration basins can be designed to provide channel protection, and/or flood control by providing storage capacity in excess of that provided for water quality and incorporating outlet controls. The additional storage and outlet structure should be provided per the requirements

outlined in the Extended Detention Basins section of this document (see Section 2). Note that the selected outlet structure shall not be designed to drain the water quality volume and shall be similar to outlet structures that maintain a permanent pool (see Section 8 - Wetponds and Lakes).

Drainage

1. The bottom of infiltration bed must be native soil, over-excavated to at least one foot in depth and the soil replaced uniformly without compaction. Amending the excavated soil with 2-4 inches (~15-30%) of coarse sand is recommended.
2. The use of vertical piping, either for distribution or infiltration enhancement shall not be allowed to avoid device classification as a Class V injection well per 40 CFR146.5(e)(4).
3. The hydraulic conductivity of the subsurface layers should be sufficient to ensure a maximum 72-hr drawdown time. An observation well shall be incorporated to allow observation of drain time.
4. For infiltration basins, an underdrain shall be installed within the bottom layer to provide drainage in case of standing water. The underdrain shall be operated by opening a valve, which shall be closed during normal operation. Cleanouts shall be provided for the underdrain.

Emergency Overflow

There must be an overflow route for stormwater flows that overtop the facility or in case the infiltration facility becomes clogged.

1. For online facilities, the overflow channel must be able to safely convey flows from the capital storm to the downstream conveyance system or other acceptable discharge point. Sizing is based on the LACDPW Hydraulics and Hydrology/Sedimentation manuals.

Vegetation

Infiltration Basin

1. A thick mat of drought tolerant grass should be established on the basin floor and side-slopes following construction. Grasses can help prevent erosion and increase evapotranspiration and their rhizomes discourage compaction within the root zone helping to maintain the surface infiltration rates. Additionally, the active growing vegetation can help break up surface crusts that accumulate from sedimentation of fine particulates.
2. Grass may need to be irrigated during establishment.
3. Facility will not be accepted by the County/Flood Control District until vegetation is well established and functioning.

Infiltration Trench

1. Infiltration trenches shall be kept free of vegetation.
2. Trees and other large vegetation should be planted away from trenches such that drip lines do not overhang infiltration beds.

Maintenance Access

Infiltration Basin

Infiltration basins require access provisions similar to dry extended detention basins (Section 2).

A maintenance access road(s) shall be provided to the drainage structures associated with the basin (e.g., inlet, emergency overflow or bypass structures). Manhole and catch basin lids must be in or at the edge of the access road.

An access ramp to the basin bottom is required to facilitate the entry of sediment removal and vegetation maintenance equipment without compaction of the basin bottom and side slopes.

Access roads shall meet the following design criteria:

1. All access ramps and roads shall be paved with a minimum of 6 inches of concrete over 3 inches of crushed aggregate base material. This requirement may be modified depending on the soil conditions and intended use of the road at the discretion of the Department.
2. Maximum grade shall be 12% unless otherwise approved by the Department.
3. Centerline turning radius shall be 40 feet, minimum.
4. Access roads less than 500 ft long shall have 12 feet wide pavement within a minimum 15 feet wide bench. Access roads greater than 500 feet long shall have 16 feet wide pavement within a minimum 20 feet wide bench.
5. All access roads shall terminate with turnaround areas of 40 feet by 40 feet. A hammer type turn around area or a circle drive around the top of the facility is also acceptable.
6. Adequate double-drive gates and commercial driveways are required at street crossings. Gates should be located a minimum of 25 feet from the street curb except in residential areas where the gates may be located along the property line provided there is adequate site distance to see oncoming vehicles at the posted speed limit.

Infiltration Trench

1. The facility and outlet structures must all be safely accessible during wet and dry weather conditions.
2. An access road along the entire length of the trench is required unless the trench is located along an existing road or parking lot that can be safely used for maintenance access.

3. If the infiltration facility becomes plugged and fails, then access is needed to excavate the facility to remove and replace the filter bed media, as well as to increase all dimensions of the facility by 2 inches to provide a fresh surface for infiltration. To prevent damage and compaction, access must be able to accommodate a backhoe working at "arms length" from the berm.

Construction

1. Infiltration facilities shall not be hydraulically connected to the storm drain system until all contributing drainage areas are stabilized (e.g., with vegetation or pavement) as shown on the Contract Plans and to the satisfaction of the Engineer. Infiltration facilities shall not be used as sediment control facilities.
2. To preserve and avoid the loss of infiltration capacity, the following construction guidelines must be specified:
 - The entire area draining to the facility must be stabilized before construction begins. If this is infeasible, a diversion berm must be placed around the perimeter of the infiltration site to prevent sediment entrance during construction and landscape establishment.
 - Compaction of the subgrade with heavy equipment should be minimized to the maximum extent possible. If the use of heavy equipment on the base of the facility cannot be avoided, the infiltrative capacity should be restored by tilling or aerating prior to placing the infiltrative bed.
 - The exposed soils must be inspected by a soil engineer after excavation to confirm that soil conditions are suitable.

Landscaping


Landscaping outside of the basin, but within the easement/right-of-way, is required for infiltration basins and must adhere to the following criteria so as not to hinder maintenance operations:

1. No trees or shrubs may be planted within 10 feet of inlet or outlet pipes or manmade drainage structures such as spillways, flow spreaders, or earthen embankments. Species with roots that seek water, such as willow or poplar, shall not be used within 50 feet of pipes or manmade structures. Weeping willow (*Salix babylonica*) should not be planted in or near detention basins.
2. Prohibited non-native plant species will not be permitted. For more information on invasive weeds, including biology and control of listed weeds, look at the "encycloweedia" located at the California Department of Food and Agriculture website at <http://www.cdfa.ca.gov/wma> or the California Invasive Plant Council website at <http://portal.cal-ipc.org/weedlist>.

3. Other resources for identifying suitable plant types for specific BMP areas can be found by consulting a nurseryman, arborist, landscape architect or referring to various online sources such as:
- CalFlora - a database of wild California plants that include plant characteristics and photos
<http://www.calflora.org>
 - L.A. River Master Plan Landscaping and Plant Palettes - a guidance document providing a listing of native plant communities in the Los Angeles area
http://ladpw.org/wmd/watershed/LA/LAR_planting_guidelines_webversion.pdf
 - a. Jepson Online Interchange For California Floristics - a database that provides information on identification, taxonomy, distribution, ecology, relationships, and diversity of California vascular plants.
<http://ucjeps.berkeley.edu/interchange.html>
 - VegSpec - a web-based decision support system that assists land managers in the planning and design of vegetative establishment practices
<http://ironwood.itc.nrcs.usda.gov/Netdynamics/Vegspec/pages/HomeVegspec.htm>
 - USDA Plants Database - an extensive database of native and non-native plants of the United States with over 100 plant characteristics
<http://plants.usda.gov/index.html>

Restricted Construction Materials


The use of treated wood or galvanized metal anywhere inside the facility is prohibited.



NOTES:

- ① MAINTENANCE RAMP SHOULD BE PAVED. SLOPE SHOULD NOT EXCEED 12%. MAINTENANCE RAMP SHOULD PROVIDE ACCESS TO BOTH THE FIRST CELL AND MAIN BASIN.
- ② UPSTREAM PRETREATMENT SHALL BE PROVIDED. SEDIMENT FOREBAY WITH VOLUME EQUAL TO 25% OF TOTAL INFILTRATION BASIN VOLUME MAY BE USED IN LIEU OF UPSTREAM PRETREATMENT. DEPTH SHALL BE 4' MIN TO 8' MAX PLUS AN ADDITIONAL 1 FOOT MIN SEDIMENT STORAGE DEPTH.
- ③ RIP RAP APRON OR OTHER ENERGY DISSIPATION.
- ④ EXTEND EARTHEN BERM ACROSS ENTIRE WIDTH OF THE INFILTRATION BASIN.
- ⑤ INFILTRATION BASIN BOTTOM AND SIDE SLOPES SHALL BE PLANTED WITH DROUGHT TOLERANT VEGETATION. DEEP ROOTED VEGETATION PREFERRED FOR BASIN BOTTOM. NO TOPSOIL SHALL BE ADDED TO INFILTRATION BASIN BED.
- ⑥ SIZE OUTLET PIPE TO PASS CAPITAL DESIGN PEAK FLOW FOR ON-LINE INFILTRATION BASINS AND WATER QUALITY PEAK FLOW FOR OFF-LINE INFILTRATION BASINS.
- ⑦ WATER QUALITY OUTLET STRUCTURE. SEE FIGURE 7-2 AND FIGURE 7-3 FOR DETAILS.
- ⑧ OVER EXCAVATE BASIN BOTTOM 1 FOOT. RE-PLACE EXCAVATED MATERIAL UNIFORMLY WITHOUT COMPACTION. AMENDING EXCAVATED MATERIAL WITH 2" - 4" OF COARSE SAND IS RECOMMENDED FOR SOILS WITH BORDER LINE INFILTRATION CAPACITY.
- ⑨ INSTALL EMERGENCY OVERFLOW SPILLWAY AS NEEDED. SEE FIGURE 2-4 FOR DETAILS
- ⑩ EMBANKMENT SIDE SLOPES SHALL BE NO STEEPER THAN 3H:1V BOTH OUTSIDE AND INSIDE.
- ⑪ INSTALL OPTIONAL 6" MINIMUM DIAMETER PERFORATED PIPE UNDERDRAIN. INSTALL AT 0.5% MINIMUM SLOPE.

Figure 6-1
INFILTRATION BASIN



Infiltration Facility Operations and Maintenance

General Requirements

Infiltration facility maintenance should include frequent inspections to ensure that water infiltrates into the subsurface completely within the recommended infiltration time of 72 hours or less after a storm (see Appendix E for guidance on facility inspection and Appendix F for an infiltration inspection and maintenance checklist).

Maintenance and regular inspections are of primary importance if infiltration basins and trenches are to continue to function as originally designed. A specific maintenance plan shall be developed specific to each facility outlining the schedule and scope of maintenance operations, as well as the documentation and reporting requirements. The following are general maintenance requirements:

1. Regular inspection should determine if the sediment pretreatment structures require routine maintenance.
2. If water is noticed in the basin more than 72 hours after a major storm or in the observation well of the infiltration trench more than 48 hours after a major storm, the infiltration facility may be clogged. Maintenance activities triggered by a potentially clogged facility include:
 - Check for debris/sediment accumulation, rake surface and remove sediment (if any) and evaluate potential sources of sediment and vegetative or other debris (e.g., embankment erosion, channel scour, overhanging trees, etc). If suspected upland sources are outside of the County's jurisdiction, additional pretreatment operations (e.g., trash racks, vegetated swales, etc.) may be necessary.
 - For basins, removal of the top layer of native soil may be required to restore infiltrative capacity.
 - For trenches, assess the condition of the top aggregate layer for sediment buildup and crusting. Remove top layer of pea gravel and replace. If slow draining conditions persist, entire trench may need to be excavated and replaced.
3. Any debris or algae growth located on top of the infiltration facility should be removed and disposed of properly.
4. Facilities should be inspected annually. Trash and debris should be removed as needed, but at least annually prior to the beginning of the wet season.
5. Site vegetation should be maintained as frequently as necessary to maintain the aesthetic appearance of the site, and as follows:
 - Vegetation, large shrubs, or trees that limit access or interfere with basin operation should be pruned or removed.

- Slope areas that have become bare should be revegetated and eroded areas should be regraded prior to being revegetated.
 - Grass should be mowed to 4"-9" high and grass clippings should be removed.
 - Fallen leaves and debris from deciduous plant foliage should be raked and removed.
 - Invasive vegetation, such as Alligatorweed (*Alternanthera philoxeroides*), Halogeton (*Halogeton glomeratus*), Spotted Knapweed (*Centaurea maculosa*), Giant Reed (*Arundo donax*), Castor Bean (*Ricinus communis*), Perennial Pepperweed (*Lepidium latifolium*), and Yellow Starthistle (*Centaurea solstitialis*) must be removed and replaced with non-invasive species. Invasive species should never contribute more than 25% of the vegetated area. For more information on invasive weeds, including biology and control of listed weeds, look at the "encycloweedia" located at the California Department of Food and Agriculture website at <http://www.cdffa.ca.gov/wma> or the California Invasive Plant Council website at <http://portal.cal-ipc.org/weedlist>.
 - Dead vegetation should be removed if it exceeds 10% of area coverage. Vegetation should be replaced immediately to maintain cover density and control erosion where soils are exposed.
6. For infiltration basins, sediment buildup exceeding 50% of the forebay sediment storage capacity, as indicated by the steel markers, should be removed. Sediment from the remainder of the basin should be removed when 6 inches of sediment accumulates. Sediments should be tested for toxic substance accumulation in compliance with current disposal requirements if visual or olfactory indications of pollution are noticed. If toxic substances are encountered at concentrations exceeding thresholds of Title 22, Section 66261 of the California Code of Regulations, the sediment must be disposed of in a hazardous waste landfill and the source of the contaminated sediments should be investigated and mitigated to the extent possible.
7. Following sediment removal activities, replanting and/or reseedling of vegetation may be required for reestablishment.

Maintenance Standards

A summary of the routine and major maintenance activities recommended for infiltration facilities is shown in Table 6-1. Detailed routine and major maintenance standards are listed in Tables 6-2 and 6-3.

Table 6-1: Infiltration Facility Routine and Major Maintenance Quick Guide

Inspection and Maintenance Activities Summary	
Routine Maintenance	• Remove trash and debris as required • Repair and reseed erosion near inlet if necessary • Remove any visual evidence of contamination from floatables such as oil and grease • Clean under-drain (if present) and outlet piping to alleviate ponding and restore infiltrative capacity. • Remove minor sediment accumulation, debris and obstructions near inlet and outlet structures as needed • Mow routinely to maintain ideal grass height and to suppress weeds • Periodically observe function under wet weather conditions • Take photographs before and after maintenance (encouraged)
Major Maintenance	• Clean out under-drains if present to alleviate ponding. Replace media if ponding or loss of infiltrative capacity persists and revegetate • Repair structural damage to flow control structures including inlet, outlet and overflow structures • De-thatch grass to remove accumulated sediment and aerate compacted areas to promote infiltration

Table 6-2: Routine Maintenance – Infiltration Facilities

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Trash & Debris	Any trash and debris which exceed 5 cubic feet per 1,000 square feet (one standard garbage can). In general, there should be no visual evidence of dumping. If less than threshold, all trash and debris will be removed as part of next scheduled maintenance.	Trash and debris cleared from site.	Annually prior to wet season. After major storm events (>0.75 in/24 hrs) if spot checks indicate widespread damage/maintenance needs. Litter removal is dependent on site conditions and desired aesthetics and should be done at a frequency to meet those objectives.
Inlet Erosion	Visible evidence of erosion occurring near inlet structures.	Eroded areas repaired/reseeded	
Visual Contaminants and Pollution	Any evidence of oil, gasoline, contaminants or other pollutants.	No contaminants or pollutants present.	
Slow Drain Time	Standing water long after storm has passed (after 48 to 72 hours), or visual inspection of wells (if available) indicates that design drain times are not being achieved.	Water drains within 48 to 72 hours. Drainage pipe is cleared, accumulated litter on surface is removed, and top 1-2" of soil is raked or replaced.	
Inlets Blocked	Trash and debris or sediment blocking inlet structures.	Inlets clear and free of trash and debris.	Monthly (or as dictated by agreement between County and landscape contractor).
Appearance of Poisonous, Noxious or Nuisance Vegetation	Excessive grass and weed growth. Noxious weeds, woody vegetation establishing, Turf growing over rock filter.	Vegetation is mowed or trimmed to restore function. Weeds are removed to prevent noxious and nuisance plants from becoming established.	

Table 6-3: Major Maintenance – Infiltration Facilities

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Standing Water	Standing water long after storm has passed (after 24 to 48 hours), or visual inspection of wells (if available) indicates that design drain times are not being achieved	Design infiltration rate restored, either through excavation and filter media replacement or surface sediment removal. If applicable, underdrain cleaned, reset or replaced.	As needed

7. STORMWATER WETLAND BASINS

Definition

A stormwater wetland basin is a treatment system consisting of a sediment forebay and a permanent micro-pool with aquatic vegetation covering a significant portion of the basin. Stormwater wetland basins typically include components such as an inlet with energy dissipation, a sediment forebay for settling out coarse solids, and to facilitate maintenance, a base with shallow sections (1 to 2 feet deep) planted with emergent vegetation, deeper areas or micro pools (3 to 5 feet deep) , and a water quality outlet structure. The aquatic vegetation and the associated biological unit processes are a fundamental part of stormwater wetland basins. Therefore, it is critical that dry weather base flows exceed evaporation and infiltration losses to prevent loss of aquatic vegetation and to avoid stagnation and vector problems. In situations where dry weather flows are inadequate to support a wetland basin sized for the entire water quality design volume, an additional source of water may be needed during summer months. Otherwise, the wetland should be sized based on the available flow and the design should incorporate extended detention up to the water quality storm volume.

It is important to note the difference between stormwater wetlands and wetlands that are constructed as part of mitigation requirements. Constructed mitigation wetlands are intended to provide fully functional habitat similar to the habitat they replace. Stormwater wetlands are a treatment BMP designed to capture and treat pollutants to protect receiving waters, including natural wetlands and other ecologically significant habitat. The accumulation of pollutants in sediment and vegetation of stormwater wetlands may impact the health of aquatic biota. As such, periodic sediment and vegetation removal within stormwater wetlands may be required. These maintenance activities may temporarily interrupt the use of stormwater wetlands by wildlife.

The applications for stormwater wetlands include peak flow attenuation, volume reduction, and pollutant removal. The pollutant removal processes that occur in wetlands include sedimentation, filtration, plant uptake and storage, and microbially-mediated transformations. Other benefits provided by stormwater wetlands include opportunities for education and aesthetics. In theory, there are no limitations to the size of the tributary area to a stormwater wetland; however, stormwater wetlands are typically used for treating areas larger than 10 acres.

Factors that favor the selection of stormwater wetlands over other kinds of BMPs include enhanced treatment capability (including dry-weather flow treatment), aesthetics, and the ability to mitigate large tributary areas. Factors that may limit the use of stormwater wetland basins include overly permeable soils and/or non-existent base flows, public acceptance with regards to the potential for vector infestation, large footprint to treated area ratios (up to 12% percent of tributary area, dependant on overall imperviousness of the tributary area) and high initial capital cost of implementation.

General Constraints and Siting Considerations

- Availability of base flows - stormwater wetlands require a regular source of water to support wetland biota

- Slope stability - stormwater wetlands are not permitted near 2:1 (H:V) slopes
- Surface space availability - large footprint required
- Compatibility with flood control - basins must not interfere with flood control functions of existing conveyance and detention structures

Multi-Use Opportunities

Provided adequate surcharge storage, a stormwater wetland may be combined with a flood control basin to provide both water quality control and peak flow control. Stormwater wetlands can also be designed with wildlife viewing areas and walking trails around the perimeter to provide passive recreation. Any planned multi-use facility must obtain special approval by the LACDPW.

Stormwater Wetland Basin Design Specifications

Basin Sizing and Geometry

1. Stormwater wetland basins shall be sized to capture and treat the SUSMP volume (see *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended)). If extended detention is included, then the extended detention volume must provide at least 12 hours detention of 20% of the water quality storm.
2. Stormwater wetlands should consist of at least two cells including a sediment forebay and a wetland basin (see Figure 7-1).
3. The sediment forebay must contain between 10 and 20 percent of the total basin volume.
4. The depth of the sediment forebay should be between 4 and 8 feet.
5. One foot of sediment storage shall be provided in the sediment forebay.
6. The "berm" separating the two cells shall be uniform in cross-section and shaped such that its downstream side gradually slopes to the main wetland basin.
7. The top of the berm shall be either at the water quality design water surface or submerged 1 foot below the water quality design water surface, as with wetponds. Correspondingly, the side slopes of the berm must meet the following criteria:
 - a) If the top of the berm is at the water quality design water surface, the berm side slopes shall be no steeper than 3:1 (H:V).
 - b) If the top of berm is submerged 1 foot, the upstream side slope may be a max of 2:1 (H:V).
8. The wetland basin should be designed with a "naturalistic" shape and a range of depths intermixed throughout the wetland basin to a maximum of 5 feet. See Table 7-1 for a recommended depth distribution.

Table 7-1: Recommended Distribution of Depths in Wetland Basin

Depth Range (feet)	Percent by Area
0.1 to 1	15
1 to 3	55
3 to 5	30

9. The flowpath length-to-width ratio should be a minimum of 3:1, but preferably at least 4:1 or greater. *Intent: a high flow path length to width ratio will maximize fine sediment removal.*
10. The minimum freeboard shall be 2 feet above the maximum water surface elevation for online basins and 1 foot above the maximum water surface elevation for offline basins.
11. Wetland pools should be designed such that the residence time for dry weather flows is no greater than 7 days. *Intent: Minimize vector and stagnation issues.*

Water Supply

1. Water balance calculations shall be provided to demonstrate that adequate water supply will be present to maintain a permanent pool of water during a drought year when precipitation is 50% of average for the site. Water balance calculations shall include evapotranspiration, infiltration, precipitation, spillway discharge, and nuisance flow (where appropriate).
2. Where water balance indicates that losses will exceed inputs, a source of water shall be provided to maintain the basin water surface elevation throughout the year. The water supply shall be of sufficient quantity and quality to not have an adverse impact on the stormwater wetland water quality.

Soils Considerations

1. Stormwater wetland implementation in areas with high permeability soils (>0.1 in/hr) requires liners to increase the chances of maintaining permanent pools and/or micro-pools in the basin. Liners can be either synthetic materials or imported lower permeability soils (i.e., clays). The water balance assessment should determine whether a liner is required. The following conditions can be used as a guideline.
 - a) The wetland basin must retain water for at least 10 months of the year.
 - b) The sediment forebay must retain at least 3 feet of water year-round.

Many wetland plants can adapt to periods of summer drought, so a limited drought period is allowed in the wetland basin. This may allow for a soil liner rather than a geosynthetic liner. The sediment forebay must retain water year-round for presettling to be effective.

2. If low permeability soils are used for the liner, a minimum of 18 inches of native soil amended with good topsoil or compost (one part compost mixed with 3 parts native soil) must be placed over the liner. If a synthetic material is used, a soil depth of 2 feet is recommended to prevent damage to the liner during planting.

Buffer Zone

1. A minimum of 25 feet buffer shall be provided around the top perimeter of the stormwater wetland.

Energy Dissipation

1. The inlet to the stormwater wetland shall be submerged with the inlet pipe invert a minimum of 2 feet from the pond bottom (not including sediment storage). The top of the inlet pipe should be submerged at least 1 foot, if possible. *Intent: The inlet is submerged to dissipate energy of the incoming flow. The distance from the bottom is set to minimize resuspension of settled sediments. Alternative inlet designs that accomplish these objectives are acceptable.*
2. Energy dissipation controls must also be used at the outlet from the stormwater wetland unless the basin discharges to a storm drain or hardened channel.
3. Consult the LACDPW Design Division or Land Development Division for type and design of energy dissipation structure.

Vegetation

The wetland cell shall be planted with emergent wetland plants following the recommendations of a wetlands specialist.

Outlet Structure and Spillway

1. An outlet pipe and outlet structure shall be provided. The outlet pipe may be a perforated riser strapped to a manhole (see Figure 7-2) or placed in an embankment, suitable for extended detention, or may be back-sloped to a catch basin with a grated opening (jail house window) or manhole with a cone grate (birdcage) (see Figure 7-3). The grate or birdcage openings provide an overflow route should the basin outlet pipe become clogged.
2. The wetland outlet pipe shall be sized, at a minimum, to pass flows above the water quality design peak flow for off-line basins or flow from the capital storm for on-line basins.
3. Spillways shall meet the California Department of Water Resources, Division of Safety of Dams *Guidelines for the Design and Construction of Small Embankment Dams* (<http://damsafety.water.ca.gov/docs/GuidelinesSmallDams.pdf>).

Online Basins

1. Online basins must have an emergency overflow spillway to prevent overtopping of the walls or berms should blockage of the riser occur based on a downstream risk assessment.
2. The overflow spillway must be sized to pass flow from the capital storm.

Offline Basins

1. An emergency overflow spillway or an emergency overflow riser must be provided. The emergency overflow must be designed to pass the SUSMP peak flow, with a minimum of 2 feet of freeboard, directly to the downstream conveyance system or another acceptable discharge point. Where an emergency overflow spillway would discharge to a steep slope, an emergency overflow riser, *in addition* to the spillway shall be provided.
2. The emergency overflow spillway shall be armored to withstand the energy of the spillway flows (Figure 2-4). The spillway shall be armored full width, beginning at a point midway across the berm embankment and extending downstream to where emergency overflows reenters the conveyance system.

Side Slopes

1. Interior side slopes up to the emergency overflow water surface shall be no steeper than 3:1 (H:V), unless stabilization has been approved by a licensed geotechnical engineer.
2. Exterior side slopes shall be no steeper than 2:1 (H:V), unless stabilization has been approved by a licensed geotechnical engineer.
3. For any slope (interior or exterior) greater than 2:1 (H:V) a geotechnical report must be submitted and approved by the County's Geotechnical and Materials Engineering Division.

Embankments

1. Embankments are earthen slopes or berms used for detaining or redirecting the flow of water.
2. The minimum top width of all berm embankments shall be 20 feet, or as approved by the geotechnical engineer and the LACDPW Materials Division.
3. Basin berm embankments must be constructed on native consolidated soil (or adequately compacted and stable fill soils analyzed by a licensed geotechnical engineer) free of loose surface soil materials, roots, and other organic debris.
4. Earthworks shall be in accordance with Section 300-6 of the Standard Specifications for Public Works Construction, most recent edition.
5. Basin berm embankments greater than 4 feet in height must be constructed by excavating a key equal to 50% of the berm embankment cross-sectional height and width. This requirement may be waived if specifically recommended by a licensed geotechnical engineer.
6. The berm embankment shall be constructed of compacted soil (95% minimum dry density, modified proctor method per ASTM D1557), placed in 6-inch lifts.

7. Low growing native perennial grasses shall be planted on downstream embankment slopes. See the Vegetation Management on Embankment Dams of Public Works' Debris Control Facilities, Attachment B, for a recommended plant list.

Fencing

Safety is provided by fencing of the facility.

1. Fences shall be designed and constructed in accordance with Title 11, Section 11.48 of the Los Angeles County Code and must be located at or above the overflow water surface elevation. Shrubs (County approved, California-adapted species) can be used to hide the fencing.

Right-of-Way

1. Wetland basins and associated access roads to be maintained by the County shall be dedicated in fee to Los Angeles County with appropriate access.

Maintenance Access

Maintenance access road(s) shall be provided to the control structure and other drainage structures associated with the basin (e.g., inlet, emergency overflow or bypass structures). Manhole and catch basin lids must be in or at the edge of the access road.

An access ramp is required for removal of sediment with a backhoe or loader and truck. The ramp must extend to the basin bottom to avoid damage to vegetation planted on the basin slope.

Access roads shall meet the following design criteria:

1. All access ramps and roads shall be paved with a minimum of 3 inches of concrete over 4 inches of crushed aggregate base material. This requirement may be modified depending on the soil conditions and intended use of the road at the discretion of the Department.
2. Maximum grade shall be 125% unless otherwise approved by the Department.
3. Centerline turning radius shall be 40 feet, minimum.
4. Access roads less than 500 ft long shall have 12 feet wide pavement within a minimum 15 feet wide bench. Access roads greater than 500 feet long shall have 16 feet wide pavement within a minimum 20 feet wide bench.
5. All access roads shall terminate with turnaround areas of 40 feet by 40 feet. A hammer type turn around area or a circle drive around the top of the facility is also acceptable
6. Adequate double-drive gates and commercial driveways are required at street crossings. Gates should be located a minimum of 25 feet from the street curb except in residential areas where the gates may be located along the property line provided there is adequate site distance to see oncoming vehicles at the posted speed limit.


Landscaping Outside of the Facility

Site landscaping is required and must adhere to the following criteria so as not to hinder maintenance operations:

1. No trees or shrubs may be planted within 10 feet of inlet or outlet pipes or man-made drainage structures such as spillways, flow spreaders, or earthen embankments. Species with roots that seek water, such as willow or poplar, shall not be used within 50 feet of pipes or manmade structures. Weeping willow (*Salix babylonica*) should not be planted in or near detention basins.
2. Prohibited non-native plant species will not be permitted. For more information on invasive weeds, including biology and control of listed weeds, look at the "encycloweedia" located at the California Department of Food and Agriculture website at <http://www.cdfa.ca.gov/wma> or the California Invasive Plant Council website at <http://portal.cal-ipc.org/weedlist>.

Restricted Construction Materials


The use of treated wood or galvanized metal anywhere inside the facility is prohibited. The use of galvanized fencing is permitted if in accordance with the fencing requirement above.




NOTES:

- ① INLET PIPE SHOULD BE SUBMERGED WITH A MINIMUM OF 2' DISTANCE FROM THE BOTTOM
- ② SEDIMENT FOREBAY. FORE BAY VOLUME SHALL EQUAL 10% TO 20% OF TOTAL WETLAND VOLUME. FOREBAY DEPTH SHALL BE 4' MIN TO 8' MAX PLUS AN ADDITIONAL 1' MIN SEDIMENT STORAGE DEPTH.
- ③ RIP RAP APRON OR OTHER INLET ENERGY DISSIPATION.
- ④ BERM AT DESIGN WATER SURFACE ELEVATION OR SUBMERGED 1' BELOW DESIGN WATER SURFACE ELEVATION. EXTEND BERM ACROSS ENTIRE WIDTH OF THE WETLAND.
- ⑤ WETLAND VEGETATION. PLANTING SCHEME MUST BE DESIGNED BY A WETLAND ECOLOGIST.
- ⑥ EMBANKMENT SIDE SLOPES SHALL BE NO STEEPER THAN 2H:1V OUTSIDE AND 3H:1V INSIDE
- ⑦ SIZE OUTLET PIPE TO PASS CAPITAL DESIGN PEAK FLOW FOR ONLINE AND WATER QUALITY PEAK FLOW FOR OFFLINE BASINS.
- ⑧ WATER QUALITY OUTLET STRUCTURE. SEE FIGURE 7-2 AND FIGURE 7-3 FOR DETAILS.
- ⑨ MAINTENANCE RAMP SHOULD BE PAVED. SLOPE SHOULD NOT EXCEED 12%.
- ⑩ MAINTENANCE RAMP SHOULD PROVIDE ACCESS TO BOTH THE FOREBAY AND MAIN BASIN.


Figure 7-1
STORMWATER WETLAND BASIN



Perforated Riser Detail
(Not to Scale)




Section A - A'
(Not to Scale)



NOTES:

- ① RISER PIPE SHALL BE SIZED TO PROVIDE 36 TO 48-HOUR FULL BRIM DRAW DOWN TIME.
- ② TOTAL OUTLET CAPACITY: CAPITAL DEVELOPED PEAK FLOW FOR ON-LINE BASINS AND WATER QUALITY DESIGN FLOW FOR OFF-LINE BASINS.
- ③ SCREEN OPENINGS SHALL BE AT LEAST $\frac{1}{4}$ " AND SHALL NOT EXCEED THE DIAMETER OF THE PERFORATIONS ON THE RISER.
- ④ RISER PIPE PERFORATION DIAMETER SHALL BE NO LESS THAN $\frac{1}{2}$ " AND NO MORE THAN 2"
- ⑤ MINIMUM PIPE DIAMETER (D) IS 2'
- ⑥ RISER PIPE MATERIAL IS CMP

Figure 7-2
RISER OUTLET



Inverted Pipe Outlet Structure
(Not to Scale)

NOTES:

- ① SIZE OUTLET PIPE SYSTEM TO PASS CAPITAL PEAK FLOW FOR ON-LINE PONDS AND WATER QUALITY PEAK FLOW FOR OFF-LINE PONDS.
- ② VALVE MAY BE LOCATED INSIDE MANHOLE OR OUTSIDE WITH APPROVED OPERATIONAL ACCESS
- ③ INVERT OF DRAIN SHALL BE 6" MINIMUM BELOW TOP OF INTERNAL BERM. LOWER PLACEMENT IS DESIRABLE. INVERT SHALL BE 6" MINIMUM ABOVE BOTTOM OF POND.
- ④ OUTLET PIPE INVERT SHALL BE AT WETPOOL WATER SURFACE ELEVATION

Figure 7-3
INVERTED PIPE OUTLET

Stormwater Wetland Basin Maintenance Standards

General Requirements

Maintenance is critical if stormwater wetland basins are to function as originally designed. A specific maintenance plan shall be developed for each facility outlining the schedule and scope of maintenance operations, as well as the documentation and reporting requirements. The following are general maintenance requirements:

1. The stormwater wetland basin should be inspected annually and inspections after major storm events are encouraged (see Appendix E for guidance on BMP facility inspection and Appendix F for a wetland basin inspection and maintenance checklist). Trash and debris should be removed as needed, but at least annually prior to the beginning of the wet season.
2. Site vegetation should be maintained as frequently as necessary to maintain the aesthetic appearance of the site and to prevent clogging of outlets, creation of dead volumes, and barriers to mosquito fish to access pooled areas, and as follows:
 - Vegetation, large shrubs, or trees that limit access or interfere with basin operation should be pruned or removed.
 - Slope areas that have become bare should be revegetated and eroded areas should be regraded prior to being revegetated.
 - Invasive vegetation, such as Alligatorweed (*Alternanthera philoxeroides*), Halogeton (*Halogeton glomeratus*), Spotted Knapweed (*Centaurea maculosa*), Giant Reed (*Arundo donax*), Castor Bean (*Ricinus communis*), Perennial Pepperweed (*Lepidium latifolium*), and Yellow Starthistle (*Centaurea solstitialis*) must be removed and replaced with non-invasive species. Invasive species should never contribute more than 25% of the vegetated area. For more information on invasive weeds, including biology and control of listed weeds, look at the "encycloweedia" located at the California Department of Food and Agriculture website at <http://www.cdfa.ca.gov/wma> or the California Invasive Plant Council website at <http://portal.cal-ipc.org/weedlist>.
 - Dead vegetation should be removed if it exceeds 10% of area coverage. This does not include seasonal die-back where roots would grow back later in colder areas. Vegetation should be replaced immediately to maintain cover density and control erosion where soils are exposed.
3. Sediment buildup exceeding 6 inches over the storage capacity in the first cell should be removed. Sediments should be tested for toxic substance accumulation in compliance with current disposal requirements visual or olfactory indications of pollution are noticed. If toxic substances are encountered at concentrations exceeding thresholds of Title 22, Section 66261 of the California Code of Regulations, the sediment must be disposed of in a hazardous waste landfill.
4. Following sediment removal activities, replanting and/or reseedling of vegetation may be required for reestablishment.

Maintenance Standards

A summary of the routine and major maintenance activities recommended for wetland basins is shown in Table 7-2. Detailed routine and major maintenance standards listed in Tables 7-3 and 7-4 are intended to be measures to determine if maintenance actions are required as identified through inspection. They are not intended to be measures of the facility's required condition at all times between inspections.

Table 7-2: Wetland Basin Routine and Major Maintenance Quick Guide

Inspection and Maintenance Activities Summary	
Routine Maintenance	• Removal trash and debris • Remove minor sediment accumulation near inlet and outlet structures • Stabilize/Repair eroded banks and fill in animal burrows if present • Remove any evidence of visual contamination from floatables such as oil and grease • Eliminate pests and conditions suitable for creating ideal breeding habitat • Install or repair pond liner to ensure that first cell maintains a permanent pool • Remove algae mats as often as needed to prevent coverage of more than 20% of pond surface • Mow berms routinely if applicable to maintain aesthetic appeal and to suppress weeds
Major Maintenance	• Remove dead, diseased, or dying trees and woody vegetation that interfere with facility maintenance. • Correct problems associated with berm settlement • Repair berm/dike breaches and stabilize eroded parts of the berm • Repair and rebuild spillway as needed to reverse the effects of severe erosion • Remove sediment build up in forebay and main basin area to restore original sediment holding capacity • Regrade main basin bottom to restore bottom slope and eliminate the incidence of standing pools • Aerate compacted areas to promote infiltration if volume reductions are desired • Repair or replace gates, fences, flow control structures, and inlet/outlet structures as needed to maintain full functionality

Table 7-3: Routine Maintenance Standards – Stormwater Wetland Basins

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Trash & Debris	Any trash and debris which exceed 5 cubic feet per 1,000 sf of pond area (one standard garbage can). In general, there should be no visual evidence of dumping. If less than threshold all trash and debris will be removed as part of next scheduled maintenance. If trash and debris is observed blocking or partially blocking an outlet structure or inhibiting flows between cells, it should be removed quickly	Trash and debris cleared from site.	Annually prior to wet season After major storm events (>0.75 in/24 hrs) if spot checks of some basins indicate widespread damage/ maintenance needs
Sediment Accumulation	Sediment accumulation in basin bottom that exceeds the depth of sediment zone plus 6 inches in the sediment forebay. If sediment is blocking an inlet or outlet, it should be removed.	Sediment cleaned out.	
Erosion	Erosion of basin side slopes and/or scouring of basin bottom.	Slopes should be stabilized using appropriate erosion control measure(s) and repair methods.	
Oil Sheen on Water	Prevalent and visible oil sheen.	No oil sheen present.	
Noxious Pests	Visual observations or receipt of complaints of numbers of pests that would not be naturally occurring and could pose a threat to human or aquatic health.	Vectors controlled per LACDPW standards.	
Water Level	First cell empty, doesn't hold water.	Line the first cell to maintain at least 4 feet of water. The first cell must remain full to control turbulence of the incoming flow and reduce sediment resuspension.	

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Aesthetics	Minor vegetation removal and thinning. Mowing berms and surroundings	Facility is well kept.	Monthly (or as dictated by agreement between County and landscape contractor)
Noxious Weeds	Any evidence of noxious weeds.	Eradicate all noxious weeds; control and prevent the spread of all noxious weeds. Use Integrated Pest Management techniques, if applicable. See http://www.ipm.ucdavis.edu/ for more information.	

Table 7-4: Major Maintenance Standards – Stormwater Wetland Basins

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Tree Growth	Tree growth does not allow maintenance access or interferes with maintenance activity (i.e., slope mowing, silt removal, vactoring, or equipment movements). If trees are not interfering, do not remove. Dead, diseased, or dying trees should be removed.	Trees do not hinder maintenance activities. Remove dead, diseased, or dying trees. (Use a certified Arborist to determine health of tree or removal requirements)	Annual or as needed (infrequent) After major storm events (>0.75 in/24 hrs) if spot checks of some basins indicate widespread damage/maintenance needs.
Settling of Berm	If settlement is apparent. Settling can be an indication of more severe problems with the berm or outlet works. A geotechnical engineer should be consulted to determine the source of the settlement if the dike/berm is serving as a dam.	Dike is built back to the design elevation.	
Piping through Berm	Discernable water flow through basin berm. Ongoing erosion with potential for erosion to continue. A licensed geotechnical engineer should be called in to inspect and evaluate condition and recommend repair of condition.	Piping eliminated. Erosion potential resolved and berm stability achieved.	

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Tree and Large Shrub Growth on Downstream Slope of Embankments	Tree and large shrub growth on downstream slopes of embankments may prevent inspection and provide habitat for burrowing rodents.	Trees and large shrubs should be removed. All dead roots should be removed if practical. Otherwise, dead roots should be removed to a minimum of 36 inches below grade and replaced with cement grout to 12 inches below grade. The top 12 inches of the root holes should be filled with compacted, in-situ soils. The area facility engineer may require additional root removal if necessary for dam safety or maintenance purposes.	
Erosion on Spillway	Rock is missing and soil is exposed at top of spillway or outside slope.	Rocks and pad depth are restored to design standards.	
Gate/Fence Damage	Damage to gate/fence, including missing locks and hinges	Gate/Fence repaired.	

8. SAND FILTERS

Definition

A sand filter operates much like a bioretention facility; however, instead of filtering stormwater through engineered soils, stormwater is filtered through a constructed sand bed with an underdrain system. Runoff enters the filter and spreads over the surface. As flows increase, water backs up on the surface of the filter where it is held until it can percolate through the sand. The treatment pathway is vertical (downward through the sand). High flows in excess of the design volume are bypassed. Water that has percolated through the sand is collected via a perforated underdrain system before being conveyed to the downstream storm drainage system or to an infiltration facility. As stormwater passes through the sand, pollutants are trapped in the small pore spaces between sand grains or are adsorbed to the sand surface. Over time, bacteria can grow in the sand bed and provide some biological treatment. However, continuous dry weather flows would be required to maintain the moisture required by the bacteria.

A sand filter may be used in nearly all developments where site characteristics provide adequate hydraulic head to effectively operate the filter. Approximately 4 ft of elevation difference is recommended between the inlet and outlet of the filter. Landscape uses of sand filters are limited due to the small numbers of plant species that can survive in sand. Large trees and shrubs that generate leaf litter should not be located near a sand filter, as the leaves tend to clog the surface of the filter and reduce infiltrative capacity.

Sand filters are designed to prevent water backup in the sand layer, as saturated sands can lead to anoxic conditions where metals and phosphorus can be mobilized. The underdrain system must flow freely. In areas with high groundwater tables that could potentially flood the underdrain system, an impermeable liner must be provided.

Sand filters have a propensity to clog under high sediment loads; therefore, in areas with high predicted sediment load, pretreatment must be provided.

General Constraints and Siting Considerations

- High loading rates - may clog quickly if flows are not adequately pretreated
- Vertical relief and proximity to storm drain - site must have adequate relief between land surface and storm drain to permit vertical percolation through the sand filter and collection and conveyance in underdrain to storm drain system

Sand Filter Design Specifications

Basin Sizing and Geometry

1. Sand Filters shall be sized to capture and infiltrate the SUSMP volume (see *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended)).
2. Sand filters may be designed in any geometric configuration, but rectangular with a 1.5:1 length-to-width ratio or greater is preferred (See Figure 8-1).

3. Sand depth must be at least 24 inches, but 36 inches is preferred.
4. Depth of storage over the sand bed shall be 6 feet maximum.
5. Sand filters should be placed off-line to prevent scouring of the filter bed by high flows. The overflow structure must be designed to pass the SUSMP peak flow rate.

Sizing Methodology

A sand filter is designed with two parts: (1) a temporary storage reservoir to store runoff, and (2) a sand filter bed through which the stored runoff must percolate. Usually the storage reservoir is simply placed directly above the filter, and the floor of the reservoir pond is the top of the sand bed. For this case, the storage volume also determines the hydraulic head over the filter surface, which increases the rate of flow through the sand.

Two methods are available for sizing sand filters: a simple method and a routing modeling method. The simple method uses standard values to define filter hydraulic characteristics for determining the sand surface area. This method is useful for planning purposes, for a first approximation to begin iterations in the detailed method, or when use of the detailed computer model is not desired or not available. The simple method very often results in a larger filter than the routing method.

Background

Sand filter design is based on Darcy's law:

$$Q = KiA \quad \text{(Equation 8-1)}$$

Where,

- Q = the water quality design flow (cfs)
- K = hydraulic conductivity (fps)
- A = surface area perpendicular to the direction of flow (sf)
- i = hydraulic gradient (ft/ft) for a constant head and constant media depth, computed as follows:

$$i = \frac{h + l}{l} \quad \text{(Equation 8-2)}$$

Where,

- h = average depth of water above the filter (ft), defined for this design as $d/2$
- d = maximum storage depth above the filter (ft)
- l = thickness of sand media (ft)

Darcy's law underlies both the simple and the routing methods of design. The filtration rate V_f , or more correctly, $1/V_f$, is the direct input in the sand filter design. The relationship between

the filtration rate V and hydraulic conductivity K is revealed by equating Darcy's law and the equation of continuity, $Q = VA$. Specifically:

$$Q = KiA \quad \text{and} \quad Q = VA \quad \text{So,} \quad VA = KiA \quad \text{or:} \quad V = Ki \quad (\text{Equation 8-3})$$

Where,

V = filtration rate (ft/s)

Note that $V \neq K$. That is, the filtration rate is not the same as the hydraulic conductivity, but they do have the same units (distance per time). K can be equated to V by dividing V by the hydraulic gradient i , which is defined above.

The hydraulic conductivity K does not change with head nor is it dependent on the thickness of the media, only on the characteristics of the media and the fluid. A design hydraulic conductivity of 1 inch per hour (2 feet per day) used in this simple sizing method is based on bench-scale tests of conditioned rather than clean sand (KCSWDM, 2005) and represents the average sand bed condition as silt is captured and held in the sand bed.

Unlike the hydraulic conductivity, the filtration rate V changes with head and media thickness, although the media thickness is constant in the sand filter design.

Simple Sizing Method

The simple sizing method does not route flows through the filter. It determines the size of the filter based on the simple assumption that inflow is immediately discharged through the filter as if there were no storage volume. An adjustment factor (0.7) is applied to compensate for the greater filter size resulting from this method. Even with the adjustment factor, the simple method generally produces a larger filter size than the routing method.

Step 1: Determine maximum storage depth of water

Determine the maximum water storage depth (d) above the sand filter. This depth is defined as the depth at which water begins to overflow the reservoir pond, and it depends on the site topography and hydraulic constraints. The depth is chosen by the designer, but shall be 6 feet or less.

Step 2: Calculate the design flow

Determine SUSMP volume (V_{wq}) (see *A Manual for the Standard Urban Storm Water Mitigation Plan*, LACDPW, September 2002 (or as amended)).

Step 3: Calculate the sand filter area

Determine the sand filter area using the following equation:

$$A_{sf} = \frac{V_{wq}RL}{Kt(h+L)} \quad (\text{Equation 8-4})$$

Where,

- A_{sf} = surface area of the sand filter bed (ft²)
- V_{wq} = water quality design volume (ft³)
- R = routing adjustment factor (use $R = 0.7$)
- L = sand bed depth (ft)
- K = design hydraulic conductivity (use 2 ft/day)
- t = drawdown time (use 1 day)
- h = average depth of water above the filter (ft), (use $d/2$ with d from Step 1)

Routing Method

A continuous runoff model, such as US EPA's SWMM Model, can be used to optimally size a sand filter. A continuous simulation model consists of three components: a representative long term period of rainfall data (≈ 20 years or greater) as the primary model input; a model component representing the tributary area to the sand filter that takes into account the amount of impervious area, soil types of the pervious area, vegetation, evapotranspiration, etc.; and a component that simulates the sand filter. Using this method, the filter should be sized to capture and treat the WQ design volume from the post-development tributary area.

The continuous simulation model routes predicted tributary runoff to the sand filter, where treatment is simulated as a function of the infiltrative (flow) capacity of the sand filter and the available storage volume above the sand filter. In a continuous runoff model such as SWMM, the physical parameters of the sand filter are represented with stage-storage-discharge relationships. Due to the computational power of ordinary desktop computers, long-term continuous simulations generally take only minutes to run. This allows the modeler to run several simulations for a range of sand filter sizes, varying either the surface area of the filter (and resulting flow capacity) or the storage capacity above the sand filter, or both. Sufficient continuous model simulations should be completed so that results encompass the WQ design volume capture goal.

Model results should be plotted for both varying storage depths above the filter and for varying filter surface area (and resulting flow capacity) while keeping all other parameters constant. The resulting relationship of percent capture as a function of sand filter flow and storage capacity can be used to optimally size a sand filter based on site conditions and restraints.

In addition to continuous simulation modeling, routing spreadsheets and/or other forms of routing modeling that incorporate rainfall-runoff relationships and infiltrative (flow) capacities of sand filters may be used to size facilities. Alternative sizing methodologies should be prepared with good engineering practices.

Sand Specification

Ideally the effective diameter of the sand, d_{10} , should be just small enough to ensure a good quality effluent while preventing penetration of stormwater particles to such a depth that they cannot be removed by surface scraping (~ 2 -3 inches). This effective diameter usually lies in the range 0.20-0.35 mm. In addition, the coefficient of uniformity, $C_u = d_{60}/d_{10}$, should be less than 3.

The sand in a filter should consist of a medium sand with very little fines meeting ASTM C 33 size gradation (by weight) or equivalent as given in the table below.

U.S. Sieve Size	Percent Passing
3/8 inch	100
U.S. No. 4	95 to 100
U.S. No. 8	80 to 100
U.S. No. 16	50 to 85
U.S. No. 30	25 to 60
U.S. No. 50	5 to 30
U.S. No. 100	Less than 10

Finally, the silica (SiO_2) content of the sand should be greater than 95% by weight.

Underdrains

1. Several underdrain systems can be used in a sand filter design:
 - a. A central underdrain collection pipe with lateral collection pipes in an 8 inch minimum gravel backfill or drain rock bed.
 - b. Longitudinal pipes in an 8 inch minimum gravel backfill or drain rock bed, with a collection pipe at the outfall.
 - c. Small sand filters may utilize a single underdrain pipe in an 8 inch minimum gravel backfill or drain rock bed.
2. All underdrain pipes and connectors must be 6 inches or greater so they can be cleaned without damage to the pipe. Clean-out risers with diameters equal to the underdrain pipe must be placed at the terminal ends of all pipes and extend to the surface of the filter. A valve box should be provided for access to the cleanouts and the cleanout assembly must be water tight to prevent short circuiting of the sand filter.
3. The underdrain pipe must be sized and perforated as to ensure free draining of the sand filter bed. Round perforations must be at least 1/2-inch in diameter and the pipe must be laid with holes downward.
4. The maximum perpendicular distance between any two lateral collection pipes or from the edge of the filter and the collection pipes shall be 9 feet.
5. All pipes must be placed with a minimum slope of 0.5%.
6. The invert of the underdrain outlet must be above the seasonal high groundwater level.
7. At least 8 inches of gravel backfill must be maintained over all underdrain piping, and at least 6 inches must be maintained on both side and beneath the pipe to prevent damage by heavy equipment during maintenance. Either drain rock or gravel backfill may be used between pipes.

8. The bottom gravel layer should have a diameter at least 2X the size of the openings into the drainage system. The grains should be hard, preferably rounded, with a specific gravity of at least 2.5, and free of clay, debris and organic impurities.
9. Either a geotextile fabric or a two-inch transition gradation layer (preferred) must be placed between the sand layer and the drain rock or gravel backfill layer. If a geotextile is used, one inch of drain rock or gravel backfill should be placed above the fabric. This allows for a transitional zone between sand and gravel and may reduce pooling of water at the liner interface. The geotextile must meet the following minimum materials requirements.

Geotextile Property	Value	Test Method
Trapezoidal Tear (lbs)	40 (min)	ASTM D4533
Permeability (cm/sec)	0.2 (min)	ASTM D4491
AOS (sieve size)	#60 - #70 (min)	ASTM D4751
Ultraviolet resistance	70% or greater	ASTM D4355

Pretreatment

Pretreatment must be provided for sand filters in order to reduce the sediment load entering the filter. Pretreatment refers to design features that provide settling of large particles before runoff reaches a management practice, easing the long-term maintenance burden. To ensure that pretreatment mechanisms are effective, designers shall incorporate practices such as vegetated swales, vegetated filter strips, or sediment forebays, or proprietary devices such as hydrodynamic separators.

For design specification of pre-treatment devices, refer to:

- Filter Strip (see Section 4)
- Vegetated Swales (see Section 3)
- Sediment Forebays (See Section 2 – Dry Extended Detention Basins)
- Hydrodynamic Separators (See Section 9 – Proprietary Devices)

Flow Spreading

1. A flow spreader shall be installed at the inlet along one side of the filter to evenly distribute incoming runoff across the filter and to prevent erosion of the filter surface.
 - a. If the sand filter is curved or an irregular shape, a flow spreader shall be provided for a minimum of 20 percent of the filter perimeter.
 - b. If the length-to-width ratio of the filter is 2:1 or greater, a flow spreader must be located on the longer side and for a minimum length of 20 percent of the facility perimeter.
 - c. In other situations, use good engineering judgment in positioning the spreader.
2. Erosion protection shall be provided along the first foot of the sand bed adjacent to the flow spreader. Geotextile weighted with sand bags at 15-foot intervals may be used. Quarry spalls may also be used.

Vegetation

1. The use of vegetation in sand filters is optional. However, no top soil should be added to the sand filter bed because the fine-grained materials (silt and clay) reduce the hydraulic capacity of the filter.
2. Growing grass or other vegetation requires the selection of species that can tolerate the demanding environment of a sand filter bed. Plants not receiving sufficient dry weather flows must be able to withstand long periods of drought during summer periods, followed by periods of saturation during storm events. A horticultural specialist should be consulted for advice on species selection.
3. A sod grown in sand may be used on the sand surface as long as there is no clay in the sand substrate and the particle size gradation of the substrate meets the sand filter specifications. No other sod shall be used due to the high clay content in most sod soils.
4. To prevent uses that could compact and damage the filter surface, permanent structures are not permitted on sand filters (e.g. playground equipment).

Emergency Overflow Structure

Sand filters may only be placed off-line, but an emergency overflow must still be provided in the event the filter becomes clogged. The overflow structure must be able to safely convey flows from the SUSMP storm to the downstream conveyance system or other acceptable discharge point (Figure 2-4).

Side Slopes

1. Interior side slopes up to the emergency overflow water surface shall be no steeper than 3H:1V, unless stabilization has been approved by a licensed geotechnical engineer.
2. Exterior side slopes shall be no steeper than 2H:1V, unless stabilization has been approved by a licensed geotechnical engineer.
3. For any slope (interior or exterior) greater than 2H:1V a geotechnical report must be submitted and approved by the County's Geotechnical and Materials Engineering Division.
4. Pond walls may be vertical retaining walls, provided: (a) they are constructed of reinforced concrete, (b) a fence, which prevents access, is provided along the top of the wall (see fencing below) or further back, and (c) the design is stamped by a licensed civil engineer and approved by the County.

Embankments

1. Embankments are earthen slopes or berms used for detaining or redirecting the flow of water.
2. The minimum top width of all berm embankments shall be 20 feet, or as approved by the geotechnical engineer and the Los Angeles County Materials Division.

3. Basin berm embankments must be constructed on native consolidated soil (or adequately compacted and stable fill soils analyzed by a licensed geotechnical engineer) free of loose surface soil materials, roots, and other organic debris.
4. Earthworks shall be in accordance with Section 300-6 of the Standard Specifications for Public Works Construction, most recent edition.
5. Basin berm embankments greater than 4 feet in height must be constructed by excavating a key equal to 50% of the berm embankment cross-sectional height and width. This requirement may be waived if specifically recommended by a licensed geotechnical engineer.
6. The berm embankment shall be constructed of compacted soil (95% minimum dry density, modified proctor method per ASTM D1557), placed in 6-inch lifts.

Fencing

Safety is provided by fencing of the facility.

1. Fences shall be designed and constructed in accordance with Title 11, Section 11.48 of the Los Angeles County Code and must be located at or above the overflow water surface elevation. Shrubs (County approved, California-adapted species) can be used to hide the fencing.

Right-of-Way

1. Sand filters to be maintained by the County shall be in a lot or easement dedicated in fee to Los Angeles County with appropriate access.

Maintenance Access

Maintenance access road(s) shall be provided to the control structure and other drainage structures associated with the basin (e.g., inlet, emergency overflow or bypass structures). Manhole and catch basin lids must be in or at the edge of the access road.

An access ramp is required for removal of sediment with a backhoe or loader and truck. The ramp must extend to the bottom of the sand filter.

Access roads shall meet the following design criteria:

1. All access ramps and roads shall be paved with a minimum of 3 inches concrete over 4 inches of crushed aggregate base material. This requirement may be modified depending on the soil conditions and intended use of the road at the discretion of the Department.
2. Maximum grade shall be 12% unless otherwise approved by the Department.
3. Centerline turning radius shall be 40 feet, minimum.

4. Access roads less than 500 ft long shall have 12 feet wide pavement within a minimum 15 feet wide bench. Access roads greater than 500 feet long shall have 16 feet wide pavement within a minimum 20 feet wide bench.
5. All access roads shall terminate with turnaround areas of 40 feet by 40 feet. A hammer type turn around area or a circle drive around the top of the facility is also acceptable.
6. Adequate gates and commercial driveways are required at street crossings. Gates should be located a minimum of 25 feet from the street curb except in residential areas where the gates may be located along the property line provided there is adequate site distance to see oncoming vehicles at the posted speed limit.



Landscaping Outside of the Facility

A sand filter can add aesthetics to a site and should be incorporated into a project's landscape design. Interior side slopes may be stepped with flat areas to provide informal seating with a game or play area below. Perennial beds may be planted above the overflow water surface elevation. Large shrubs and trees are not recommended, however, as shading limits evaporation and falling leaves can clog the filter surface. If a sand filter area is intended for recreational uses, such as a volleyball area, the interior side slopes of the filter embankment should be no steeper than 3:1 and may be stepped.

1. No trees or shrubs may be planted within 10 feet of inlet or outlet pipes or manmade drainage structures such as spillways, flow spreaders, or earthen embankments. Species with roots that seek water, such as willow or poplar, shall not be used within 50 feet of pipes or manmade structures.
2. Prohibited non-native plant species will not be permitted. For more information on invasive weeds, including biology and control of listed weeds, look at the "encycloweedia" located at the California Department of Food and Agriculture website at <http://www.cdffa.ca.gov/wma> or the California Invasive Plant Council website at <http://portal.cal-ipc.org/weedlist>.

Restricted Construction Materials

The use of treated wood or galvanized metal anywhere inside the facility is prohibited. The use of galvanized fencing is permitted if in accordance with the Fencing requirement above.



NOTES:

- ① INSTALL MAINTENANCE ACCESS ROAD AND RAMP TO BOTTOM OF SAND FILTER. MAINTENANCE RAMP SHOULD BE PAVED. SLOPE SHOULD NOT EXCEED 12%.
- ② UPSTREAM PRETREATMENT SHALL BE PROVIDED. RECOMMENDED PRETREATMENT OPTIONS INCLUDE SEDIMENTATION / HYDRODYNAMIC DEVICES AND VEGETATED BMPs. IN THE ABSENCE OF PRETREATMENT, INCLUDE SEDIMENT FOREBAY WITH VOLUME EQUAL TO 10-20% OF TOTAL SAND FILTER VOLUME.
- ③ FLOW SPREADER TO EVENLY DISTRIBUTE FLOWS ALONG AT LEAST 20% OF PERIMETER.
- ④ FILTER BED SHALL BE A 24" MINIMUM SAND LAYER ON TOP OF 8" MINIMUM GRAVEL OR DRAIN ROCK BACKFILL.
- ⑤ 6" MINIMUM DIAMETER PERFORATED PIPE UNDERDRAIN. INSTALL AT 0.5% MINIMUM SLOPE
- ⑥ INSTALL GEOTEXTILE FABRIC OR TRANSITIONALLY GRADED AGGREGATE BETWEEN SAND AND GRAVEL LAYER.
- ⑦ VEGETATION MAY BE PLANTED ON TOP OF FILTER BED. NO TOP SOIL SHALL BE ADDED TO FILTER BED.
- ⑧ SIZE OUTLET PIPE STRUCTURE TO PASS WATER QUALITY DESIGN STORM AND INCLUDE AN EMERGENCY OVERFLOW.
- ⑨ EMERGENCY OVERFLOW STRUCTURE.
- ⑩ SIDE SLOPES SHOULD NOT EXCEED 3:1 UNLESS APPROVED BY AN ENGINEER. SIDE SLOPES SHALL NOT EXCEED 2:1 WITHOUT A SUPPORTING GEOTECHNICAL REPORT.
- ⑪ $\frac{3}{4}$ " - $1\frac{1}{2}$ " WASHED DRAIN ROCK OR GRAVEL LAYER.




Figure 8-1
SAND FILTER

Sand Filter Maintenance Standards

General Requirements

Sand filters are subject to clogging by fine sediment, oil and grease, and other debris (e.g., trash and organic matter such as leaves). Filters and pretreatment facilities should be inspected every 6 months during the first year of operation (see Appendix E for guidance on BMP facility inspection and Appendix F for a sand filter inspection and maintenance checklist). Inspection should also occur immediately following a storm event to assess the filtration capacity of the filter. Once the filter is performing as designed, the frequency of inspection may be reduced to once per year.

Most of the maintenance should be concentrated on the pretreatment practices, such as buffer strips and swales upstream of the trench to ensure that sediment does not reach the infiltration trench. Regular inspection should determine if the sediment removal structures require routine maintenance.

Maintenance Standards

A summary of the routine and major maintenance activities recommended for sand filters is shown in Table 8-1. Detailed routine and major maintenance standards are listed in Tables 8-2 and 8-3.

Table 8-1: Sand filter Routine and Major Maintenance Quick Guide

Inspection and Maintenance Activities Summary	
Routine Maintenance	• Remove trash and debris • Repair and reseed erosion near inlet • Remove any evidence of visual contamination from floatables such as oil and grease • Clean under-drain and outlet piping to alleviate ponding and restore infiltrative capacity if needed • Clean and reset flow spreaders as needed to maintain even distribution of low flows • Remove minor sediment accumulation, debris and obstructions near inlet and outlet structures as needed • Mow, weed and trim routinely (where applicable) to maintain ideal grass height and to suppress weeds
Major Maintenance	• Scrape top 2 – 4 inches of sand and replace with clean sand to restore filtration rate • Clean out under-drains if present to alleviate ponding. Replace media if ponding or loss of infiltrative capacity persists and revegetate as needed • Reset settled piping, add fill material to maintain original pipe flow line elevations • Repair structural damage to flow control structures including inlet, outlet and overflow structures

Table 8-2: Routine Maintenance – Sand Filters

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Trash & Debris	Any trash and debris which exceed 5 cubic feet per 1,000 square feet of filter bed area (one standard garbage can). In general, there should be no visual evidence of dumping. If less than threshold all trash and debris will be removed as part of next scheduled maintenance.	Trash and debris cleared from site.	Annually prior to wet season After major storm events (>0.75 in/24 hrs) if spot checks indicate widespread damage/maintenance needs Litter removal is dependent on site conditions and desired aesthetics and should be done at a frequency to meet those objectives
Inlet Erosion	Visible evidence of erosion occurring near flow spreader outlets.	Eroded areas repaired/reseeded.	
Slow Drain Time	Standing water long after storm has passed (after 24 to 48 hours) and/or flow through the overflow pipes occurs frequently.	Water drains within 48 hours. This is achieved through removing accumulated litter on surface, removing and renewing top 2-4" of sand. If this does not cure the problem, backflush the drainage pipe. If this does not cure problem, then see major maintenance.	
Concentrated Flow	Flow spreader uneven or clogged so that flows are not uniformly distributed across the sand filter.	Level the spreader and clean so that flows are spread evenly over the sand filter bed.	
Appearance of Poisonous, Noxious or Nuisance Vegetation	Excessive grass and weed growth. Noxious weeds, woody vegetation establishing.	Mowing, weeding and trimming to restore function and prevent noxious and nuisance plants from establishing.	Monthly (or as dictated by agreement between County and landscape contractor)

Table 8-3: Major Maintenance – Sand Filters

Defect	Conditions When Maintenance Is Needed	Results Expected When Maintenance Is Performed	Frequency
Standing Water	Standing water long after storm has passed (after 24 to 48 hours), and/or flow through the overflow pipes occurs frequently.	Design infiltration rate achieved, either through excavation and filter media replacement. If the underdrain is clogged, filter fabric must be removed and the pipe cleaned.	As needed
Pipe Settlement	If piping has visibly settled more than 1 inch.	Pipe is returned to original height. Add fill material to bring pipe back to grade. If erosion is evident around pipe, inspect for cracks or leaks.	

9. PROPRIETARY DEVICES

Definition

Proprietary devices are commercial products that typically aim at providing stormwater treatment in space-limited applications, often using patented innovative technologies. The most commonly encountered classes of proprietary stormwater management controls include hydrodynamic separation, catch basin insert technologies, cartridge filter-type controls, and proprietary biotreatment devices.

Hydrodynamic separation devices (alternatively, swirl concentrators) are devices that remove trash, debris, and coarse sediment from incoming flows using screening, gravity settling, and centrifugal forces generated by forcing the influent into a circular motion. By having the water move in a circular fashion, rather than a straight line, it is possible to obtain significant removal of suspended sediments and attached pollutants with less space as compared to wet vaults and other settling devices. Hydrodynamic devices were originally developed for combined sewer overflows (CSOs), where they were used primarily to remove coarse inorganic solids. Hydrodynamic separation has been adapted for stormwater treatment by several manufacturers and is currently used to remove trash, debris, and other coarse solids down to sand-sized particles. Several types of hydrodynamic separation devices are also designed to remove floating oils and grease using sorbent media. For more information on specific hydrodynamic devices and their vendors refer to Table 9-1 or check the Yellow Pages link at www.BMPLA.org for vendor contact information.

Catch basin inserts are manufactured filters or fabric placed in a drop inlet to remove sediment and debris and may include sorbent media to remove floating oils and grease. There are a multitude of inserts of various shapes and configurations, typically falling into one of three groups: socks, boxes, and trays. The sock-type filters are typically constructed of a fabric, usually polypropylene. The fabric may be attached to a frame or the grate of the inlet may hold the sock. Socks are meant for vertical (drop) inlets. Boxes are constructed of plastic or wire mesh. Typically a polypropylene "bag" is placed in the wire mesh box and the bag takes the form of the box. Most box products are one box; that is, settling and filtration through media occur in the same box. Other products consist of one or more trays or mesh grates. The trays may hold different types of media. Filtration media vary by manufacturer. Types include polypropylene, porous polymer, treated cellulose, and activated carbon. Inserts are an easy and inexpensive retrofitting option because drain inlets are already a component of most standard drainage systems. Inserts are usually only suitable for mitigating relatively small tributary areas (less than 1 acre). For more information on specific catch basin inserts and their vendors refer to Table 9-1 or check the Yellow Pages link at www.BMPLA.org for vendor contact information.

Cartridge filter-type controls typically consist of a series of vertical filters contained in a vault or catch basin that provide treatment through filtration and sedimentation. The vault may be divided into multiple chambers where the first chamber acts as a pre-settling basin for removal of coarse sediment while another chamber acts as the filter bay and houses the filter cartridges. The performance and capacity of a cartridge filter installation depends on the properties of the media contained in the cartridges. Cartridge filter manufacturers often provide an array of

media types each with varying properties, targeting various pollutants and a range of particle sizes. Commonly used media include media that target solids, such as perlite, and media that target both dissolved and non-dissolved constituents, such as compost leaf media, zeolite, and iron-infused polymers. Manufacturers try to distinguish their products through innovative designs that aim at providing self cleaning and draining, uniformly loaded, and clog resistant cartridges that functional properly over a wide range of hydraulic loadings and pollutant concentrations. For more information on specific cartridge filter models and their vendors refer to Table 9-1 or check the Yellow Pages link at www.BMPLA.org for vendor contact information.

Proprietary biotreatment devices are devices that are manufactured to mimic natural systems such as wetlands by incorporating plants, soil, and microbes engineered to provide treatment at higher flow rates or higher volumes and with smaller footprints than their natural counterparts. Incoming flows are typically filtered through natural media (mulch, compost, soil, plants, microbes, etc) and either infiltrated or collected by an underdrain and delivered to the storm system. Tributary areas for biotreatment devices tend to be limited to 0.5 to 1.0 acres.

The vendors of the various proprietary BMPs provide detailed documentation for device selection, sizing, and maintenance requirements. Tributary area sizes are limited to the capacities of the largest available model. The latest manufacturer supplied documentation must be used for sizing and selection of all proprietary devices. Links to the websites of a number of vendors of proprietary devices is included in Table 9-1 or check the Yellow Pages link at www.BMPLA.org for vendor contact information.

General Design Specifications

Proprietary BMP vendors are constantly updating and expanding their product lines, so refer to the latest design guidance from the vendors. General guidelines on the performance, sizing, and operation and maintenance of proprietary devices are provided through LACDPW Watershed Division.

Expected Performance

For hydrodynamic devices, it has been stated with respect to CSOs that the practical lower limit of hydrodynamic separation is a particle with a settling velocity of 12 to 16.5 feet per hour (0.10 to 0.14 cm/s). As such, the focus for hydrodynamic separation in CSOs has been with settleable solids generally 200 microns and larger, given the presence of the lighter organic solids. For inorganic sediment, the above settling velocity range represents a particle diameter of 50 to 100 microns. Thus hydrodynamic separation devices are effective for removal of coarse sediment, trash, and debris, and are useful as pretreatment in combination with other types of BMPs that target smaller particle sizes.

Catch basin inserts come in such a wide range of configurations that it is practically impossible to generalize the expected performance. Inserts should mainly be used for catching coarse sediments and floatable trash, and are effective as pretreatment in combination with other types of BMPs. Trash and large objects can greatly reduce the effectiveness of catch basin inserts with respect to sediment and hydrocarbon capture. Frequent maintenance and the use of screens and grates to keep trash out may decrease the likelihood of clogging and prevent obstruction and bypass of incoming flows.

Cartridge filters have been proven to provide efficient removals for both dissolved and non-dissolved constituents. Cartridge filters are, however, less adept at handling high flow rates as compared to catch basin inserts and hydrodynamic devices, mainly due to the enhanced treatment provided through the filtration mechanism.

Proprietary biotreatment devices are relatively new compared to the other types of proprietary treatment devices included in this document. Therefore, there are fewer third party studies on proprietary biotreatment devices and the available performance information is mostly vendor-supplied. According to the vendors, like their natural counterparts, proprietary biotreatment devices are highly efficient at mitigating dissolved metals, nutrients, and suspended solids.

More detailed performance information is available from the vendors of each class of proprietary device. The performance numbers are typically presented as percent removals rather than effluent quality measurements and can be found on the vendor websites using the links provide in Table 9-1.

Sizing

Hydrodynamic devices, catch basin inserts and cartridge filters are flow-based BMPs and therefore should be sized to capture and treat the SUSMP peak flow rate if used as a standalone BMP. Proprietary biotreatment devices on the other hand include both volume-based and flow-based BMPs. Volume-based proprietary devices should be sized to capture and treat the water quality design volume if used as a standalone BMP.

Auxiliary components of proprietary devices such as sorbent media, screens, baffles, and sumps are selected based on site specific conditions such as the loading that is expected and the desired frequency of maintenance. Sizing of proprietary devices is reduced to a simple process whereby a model can simply be selected from a table or a chart based on a few known quantities (tributary area, location, design flow rate, design volume, etc). A few of the manufacturers either size the devices for potential clients or offer calculators on their websites that simplify the design process even further and lessens the possibility of using obsolete design information.

For the latest sizing guidelines, refer to the manufacturer's website.

Operation and Maintenance

Hydrodynamic Separation Devices

Hydrodynamic separators do not have any moving parts and are consequently not maintenance intensive. Maintenance is important, however, to ensure that they are operating as efficiently as possible. Proper maintenance involves frequent inspections throughout the first year of installation, especially after major storm events. The systems are considered full when the sediment level is within one foot of the unit's top, at which point it must be cleaned out. Removal of sediment can be performed with a sump vac or vactor truck. Some hydrodynamic separator systems may contribute to mosquito breeding if they hold standing water between storms.

Refer to manufacturer's guidelines for inspection and maintenance activities.

Catch Basin Inserts

Catch basin inserts can be maintenance intensive due to their susceptibility for accumulating trash and debris. Regular maintenance activities include the cleanup and removal of accumulated trash and sediment, while major maintenance activities include replacing filter media (if used) and or repairing/replacing geotextile fabrics. There are a number of proprietary catch basin inserts and proper maintenance procedures should be determined based on manufacturer's recommendations for the selected catch-basin insert.

Cartridge filters

Maintenance activities include periodically removing captured trash, debris, and sediment from the vault floor, typically twice per year depending on the accumulation rate, using a sump vac or vactor truck. The media in media filters has to be replaced when it becomes saturated, typically about once every other year, also depending on the pollutant accumulation rate. The manufacturers of these devices typically provide contract operation and maintenance services.

All stormwater vaults that contain standing water can become a breeding area for mosquitoes. Manufacturers have developed systems to completely drain the vault, such as a perforated pipe installed in the bottom of the vault that is encased in a filter sock to prevent clogging.

Biotreatment Devices

Maintenance of biotreatment devices can be provided by the manufacturers and typically consists of routine inspection and hand removal of accumulated trash and debris. As opposed to other proprietary treatment devices, no vactor trucks or mechanical maintenance is needed.

Online Resources

Table 9-1 provides a list of links to the websites of several proprietary stormwater management controls manufactures current as of January 2009. Note that this is not an exclusive list of the proprietary products that are available. Also check the BMPLA Yellow Pages (www.BMPLA.org). The products listed in Table 9-1 and in the BMPLA Yellow Pages are proprietary and nonproprietary products that are meant to improve or eliminate pollution associated with urban runoff and stormwater. The phrase "Best Management Practice" is a common term used in Federal, State, and local regulations to label these types of products, activities, and services. Usage of the term does not imply that some products, activities, or services are better than others, or that the County of Los Angeles evaluates or decides which product, activity, or service should be listed. The inclusion of vendors, manufacturers, and products on this list in no way represents an endorsement or guarantee of effectiveness as a result of the use of these products, nor for any compliance issues regarding the Americans with Disabilities Act. Please contact the vendor and follow the manufacturers' specifications for preparation, installation, and maintenance of these products.

Table 9-1: Proprietary Device Manufacturer Websites

Category	Device	Manufacturer	Website
Catch Basin Insert	Curb Inlet Basket, Grate Inlet Skimmer	Suntree Technologies Inc.	www.suntreetech.com
Catch Basin Insert	Ultra-CurbGuard	UltraTech International, Inc.	www.Stormwater-Products.com
Catch Basin Insert	Hydro-Kleen	Hydro Compliance Management, Inc.	www.HydroCompliance.com
Catch Basin Insert	The Hydro-Cartridge®	Advanced Aquatic International, Inc.	www.hydro-cartridge.com
Catch Basin Insert	Streamguard™ Catch Basin Insert	B & B Marketing Corp	http://www.b-bmarketingcorp.com/streamguard.htm
Catch Basin Insert	Aqua-Guardian™ Catch Basin Insert	Aquashield, Inc.	http://aquashieldinc.com/aqua-guardian.htm
Catch Basin Insert	Ultra-Urban Filter	AbTech Industries	www.abtechindustries.com
Catch Basin Insert	FloGard+Plus, PerkFilter™ Percolation Filter	KriStar Enterprises, Inc.	www.kristar.com
Cartridge Filter	StormScreen™, StormFilter™	Stormwater 360°	http://www.contech-cpi.com/stormwater/products/filtration/stormfilter/15
Hydrodynamic Device	BaySaver Separation System	BaySaver Inc.	www.baysaver.com
Hydrodynamic Device	V2B1™ Stormwater Treatment System	Environment 21, LLC	http://www.env21.com/V2B1.html
Hydrodynamic Device	Aqua-Swirl™ Concentrator	Aquashield, Inc.	http://www.aquashieldinc.com/aqua-swirl.html
Hydrodynamic Device	Vortechs™ Stormwater Treatment System	Contech Construction Products Inc.	http://www.contech-cpi.com/stormwater/products/hydrodynamic_separation/vortechs/72
Hydrodynamic Device	Downstream Defender™	Hydro International	http://www.hydro-international.biz/stormwater/downstream.php
Hydrodynamic Device	Continuous Deflective Separation (CDS) Unit,	Contech Construction Products Inc.	http://www.contech-cpi.com/stormwater/products/hydrodynamic_separation/cds/558
Hydrodynamic Device	CrystalStream	CrystalStream Technologies	www.crystalstream.com
Proprietary Biotreatment	Filtrerra	Americast	http://www.americastusa.com/index.php/filtrerra/
Proprietary Biotreatment	StormTreat Systems	StormTreat Systems Inc	http://www.stormtreat.com/home.htm

Note: Web links last accessed in January 2009

10. REFERENCES

- County of Los Angeles Department of Public Works (1991). Design Manual Debris Dams and Basins, Los Angeles County Flood Control District. October, 1979.
- County of Los Angeles Department of Public Works (2002). Development Planning for Stormwater Management – A Manual for the Standard Urban Stormwater Mitigation Plan (SUSMP), September 2002. http://dpw.lacounty.gov/wmd/NPDES/SUSMP_MANUAL.pdf
- County of Los Angeles Department of Public Works (2004). Technical Manual for Stormwater Best Management Practices in the County of Los Angeles, February 2004.
- County of Los Angeles Department of Public Works (2006). Hydrology Manual. <http://dpw.lacounty.gov/services/publications.cfm>
- County of Los Angeles Flood Control District (1982). Design Manual Hydraulic, March 1982. <http://dpw.lacounty.gov/services/publications.cfm>
- Geosyntec (2006). *Los Angeles County-Wide Structural BMP Prioritization Methodology*. Submitted by Heal the Bay and the County and City of Los Angeles to the Regional Water Quality Control Board, Los Angeles Region. SWRCB Agreement Number: 03-203-554-0. <http://dpw.lacounty.gov/wmd/bmpmethod/overview.shtm>
- King County Surface Water Design Manual, 2005. King County, Washington Department of Natural Resources and Parks. January 24, 2005. <http://www.kingcounty.gov/environment/waterandland/stormwater/documents/surface-water-design-manual.aspx>
- Northern Virginia Planning District Commission, Division of Environmental Services (2000). “Maintaining Your BMP”. http://www.stormwatercenter.net/Manual_Builder/Maintenance_Manual/9%20-%20BMP%20Maint%20Ed%20Materials%20and%20Links/maintaining_bmps.pdf
- Santa Clara Valley Urban Runoff Pollution Prevention Program (SCVURPP) Fact Sheets (2003). SCVURPP C.3 Guidance Manual. http://www.scvurppp-w2k.com/guidance_tools.htm
- State Water Resources Control Board (2006). *California Nonpoint Source Encyclopedia*. Prepared by Tetra Tech, Inc. [Online] <http://www.swrcb.ca.gov/nps/docs/encyclopedia/encyclopedia.pdf>
- Stormwater Best Management Practices Handbook (2003). California Stormwater Quality Association. <http://www.cabmphandbooks.com/>
- Stormwater Management Manual (2004) City of Portland Bureau of Environmental Services. Portland, Oregon. <http://www.portlandonline.com/bes/index.cfm?c=35117>

Strecker, E.; Huber, W.; Heaney, J.; Bodine, D.; Sansalone, J.; Quigley, M.; Leisenring, M.; Pankani, D.; and Thayumanavan, A. (2005). "Critical Assessment of Stormwater Treatment and Control Selection Issues." Final report to the Water Environment Research Foundation. WERF 02-SW-1.

Technical Guidance Manual for Stormwater Quality Control Measures. (2002). Ventura Countywide Stormwater Quality Management Program.
http://www.vcstormwater.org/documents/programs_planninglanddevelopment/tech-man1-03.pdf

UDFCD, Urban Drainage and Flood Control District (1999). Urban Storm Drainage Criteria Manual. Denver, CO.
http://oldhome.udfcd.org/usdcm/usdcm_orders.htm

11. ACKNOWLEDGMENTS

Document Preparation Team

The following members of the BMP Stormwater BMP Design and Maintenance Manual Technical Advisory Committee contributed to the formulation of this document:

Steve Sheridan – Land Development Division

Amir Ibrahim – Land Development Division

Steve Burger – Land Development Division

Amir Alam – Geotechnical and Materials Engineering Division

Bill Depoto – Watershed Management Division

Joe Gaydosh – Road Maintenance Division

Ron Lacayo – Flood Maintenance Division

Mitch Miller – Building and Safety Division

Tim Smith – Environmental Programs Division

Jim Thurow – Design Division

Special Acknowledgement

Public Works would like to acknowledge and thank the following individuals for providing technical support in the formulation of this document.

Ms. Lisa Austin, P.E. and Marc Leisenring, P.E.
Geosyntec Consultants
2566 Overland Avenue, Suite 670
Los Angeles, California 90064
Office: (310) 839-6040
E-mail: laustin@Geosyntec.com/mleisenring@Geosyntec.com

A special thank you to Corey Harpole, Newhall Land, who provided funding and moral support in the formulation of this document.

APPENDIX A GLOSSARY

Best Management Practice (BMP): Methods, measures, or practices designed and selected to reduce or eliminate the discharge of pollutants to surface waters from point and nonpoint source discharges including storm water. BMPs include structural and nonstructural controls, and operation and maintenance procedures, which can be applied before, during, and/or after pollution producing activities.

Bioretention Facility: A facility that utilizes soil infiltration and both woody and herbaceous plants to remove pollutants from stormwater runoff. Runoff is typically captured and infiltrated over a period of 24 to 48 hours.

Capacity: The capacity of a stormwater drainage facility is the flow volume or rate that the facility (e.g., pipe, pond, vault, swale, ditch, drywell, etc.) is designed to safely contain, receive, convey, reduce pollutants from, or infiltrate stormwater to meet a specific performance standard. There are different performance standards for pollution reduction, flow control, conveyance, and destination/ disposal, depending on location.

Catch Basin: A structural facility located just below the ground surface, used to collect stormwater runoff for conveyance purposes. Generally located in streets and parking lots, catch basins have grated lids, allowing stormwater from the surface to pass through for collection. Catch basins also include a sumped bottom and submerged outlet pipe (downturned 90 degree elbow, hood, or baffle board) to trap coarse sediment and oils.

Check Dam: Small temporary barrier, grade control structure, or dam constructed across a swale, drainage ditch, or area of concentrated flow with the intent to slow or stop runoff.

Control Device: A device used to hold back or direct a calculated amount of stormwater to or from a stormwater management facility. Typical control structures include vaults or manholes fitted with baffles, weirs, or orifices.

Conveyance: The transport of stormwater from one point to another.

Detention Facility: A facility designed to receive and hold stormwater and release it at a slower rate, usually over a number of hours. The full volume of stormwater that enters the facility is eventually released.

Detention Tank, Vault, or Oversized Pipe: A structural subsurface facility used to provide flow control for a particular drainage basin.

Drainage Basin: A specific area that contributes stormwater runoff to a particular point of interest, such as a stormwater management facility, drainageway, wetland, river, or pipe.

Embankment: A long artificial mound of stone or earth; built to hold back water.

Extended Detention Basin: A surface vegetated basin used to provide flow control for a particular drainage basin. Stormwater temporarily fills the extended detention pond during large storm events and is slowly released over a number of hours, reducing peak flow rates.

Filter Strip: A gently sloping, densely grassed area used to filter, slow, and infiltrate stormwater.

Flow Control Facility: Any structure or drainage device that is designed, constructed, and maintained to collect, retain, infiltrate, or detain surface water runoff during and after a storm event for the purpose of controlling post-development quantity leaving the site.

Flow Control: The practice of limiting the release of peak flow rates, flow durations, and volumes from a site. Flow control is intended to protect downstream properties, infrastructure, and natural resources from the increased stormwater runoff flow rates and volumes resulting from development.

Hydrodynamic Separation: Flow-through structures with a settling or separation unit to remove sediments and other pollutants in which no outside power source is required, because the energy of the flowing water allows the sediments to efficiently separate. Depending on the type of unit, this separation may be by means of swirl action or indirect filtration.

Impervious Surface / Area: A hard surface area which either prevents or retards the entry of water into the soil as under natural conditions prior to development. A hard surface area which causes water to run off the surface in greater quantities or at an increased rate of flow from the flow present under natural conditions prior to development. Common impervious surfaces include, but are not limited to, roof tops, walkways, patios, driveways, parking lots or storage areas, concrete or asphalt paving, gravel roads, packed earthen materials, and oiled, macadam or other surfaces which similarly impede the natural infiltration of stormwater.

Infiltration Trench: A linear excavation, backfilled with gravel, used to filter pollutants and infiltrate stormwater.

Infiltration: The percolation of water into the ground.

Integrated Pest Management Plan (IPMP): A balanced approach to pest management which incorporates the many aspects of plant health care in ways that mitigate harmful environmental impacts and protect human health.

Landscaping: The vegetation (plantings), topsoil, rocks, and other surface elements associated with stormwater facility design.

Open Channel: A fluid passageway which allows part of the fluid to be exposed to the atmosphere.

Operations and Maintenance (O&M): The continuing activities required to keep stormwater management facilities and their components functioning in accordance with design objectives.

Outfall / Outlet: A location where collected and concentrated water is discharged. Outfalls can include discharge from stormwater management facilities, drainage pipe systems, and constructed open channels.

Planter Box: A structural facility filled with topsoil and gravel and planted with vegetation. The planter is completely sealed, and a perforated collection pipe is placed under the soil and gravel, along with an overflow provision, and directed to an acceptable destination point. The stormwater planter receives runoff from impervious surfaces, which is filtered and retained for a period of time.

Pollutant: An elemental or physical material that can be mobilized or dissolved by water or air and creates a negative impact to human health and/ or the environment. Pollutants include suspended solids (sediment), heavy metals (such as lead, copper, zinc, and cadmium), nutrients (such as nitrogen and phosphorus), bacteria and viruses, organics (such as oil, grease, hydrocarbons, pesticides, and fertilizers), floatable debris, and increased temperature.

Pollutants of Concern: Pollutants that exhibit one or more of the following characteristics: current loadings or historic deposits of the pollutant are impacting the beneficial uses of a receiving water, elevated levels of the pollutant are found in sediments of a receiving water and/or have the potential to bioaccumulate in organisms therein, or the detectable inputs of the pollutant are at concentrations or loads considered potentially toxic to humans and/or flora and fauna.

Pollution Reduction: The practice of filtering, retaining, or detaining surface water runoff during and after a storm event for the purpose of maintaining or improving surface and/or groundwater quality.

Practicable: Available and capable of being done, after taking into consideration cost, existing technology, and logistics in light of overall project purpose.

Public Facility: A street, right-of-way, sewer, drainage, stormwater management, or other facility that is either currently owned by the City/County or will be conveyed to the City/County for maintenance responsibility after construction.

Retention Facility: A facility designed to receive and hold stormwater runoff. Rather than storing and releasing the entire runoff volume, retention facilities permanently retain a portion of the water on-site, where it infiltrates, evaporates, or is absorbed by surrounding vegetation. In this way, the full volume of stormwater that enters the facility is not released off-site.

Roadway: Any paved surface used to carry vehicular traffic (cars/trucks, forklifts, farm machinery, or any other large machinery).

Runoff: Stormwater flows across the ground surface during and after a rainfall event. Also simply referred to as stormwater.

Stormwater: Water runoff that originates as precipitation on a particular site, basin, or watershed. Also referred to as runoff.

Stormwater Management: The overall culmination of techniques used to reduce pollutants from, detain and/or retain, and provide a destination for stormwater to best preserve or mimic the natural hydrologic cycle, to accomplish goals of reducing combined sewer overflows or basement sewer backups, or to fit within the capacity of existing infrastructure.

Surface Conveyance: The transport of stormwater on the ground surface from one point to another.

Total Suspended Solids (TSS): Matter suspended in stormwater excluding litter, debris, and other gross solids exceeding 1 millimeter in diameter.

Underground Injection Control (UIC): A federal program under the Safe Drinking Water Act, which regulates the injection of water below ground. The intent of the program is to protect groundwater aquifers, primarily those used as a source of drinking water, from contamination.

Vegetated Facilities: Stormwater management facilities that rely on plantings to enhance their performance. Plantings can provide wildlife habitat and enhance many facility functions, including infiltration, pollutant removal, water cooling, flow calming, and prevention of erosion.

Vegetated Swale: A long and narrow, trapezoidal or semicircular channel, planted with a variety of trees, shrubs, and grasses or with a dense mix of grasses. Stormwater runoff from impervious surfaces is directed through the swale, where it is slowed and in some cases infiltrated, allowing pollutants to settle out. Check dams are often used to create small ponded areas to facilitate infiltration.

Water Body: Water bodies include coastal waters, rivers, sloughs, continuous and intermittent streams and seeps, ponds, lakes, aquifers, and wetlands.

Watercourse: A channel in which a flow of water occurs, either continuously or intermittently, with some degree of regularity. Watercourses may be either natural or artificial.

APPENDIX B BMP Sizing Worksheets

Dry Extended Detention Basin Worksheet

Step 1: Determine SUSMP volume	
1-1. Enter drainage area, A	A = _____ acres
1-2. Enter impervious fraction, Imp	Imp = _____
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = _____
1-4. Enter design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended)), P_i	P_i = _____ in
1-5. Calculate rainfall depth, $P = P_i/12$	P = _____ ft
1-6. Calculate SUSMP volume, $V_{wg} = 43560 \cdot P \cdot A \cdot C$	V_{wg} = _____ ft ³
Step 2: Calculate the volume of the active basin	
2-1. Calculate basin active volume (includes SUSMP volume + sediment storage volume), $V_a = 1.05V_{wg}$	V_a = _____ ft ³
Step 3: Determine Detention Basin Location and Preliminary Geometry Based on Site Constraints	
3-1. Based on site constraints, determine the basin geometry and the storage available by developing an elevation-storage relationship for the basin. For this simple example, assume a trapezoidal geometry for cell 1 (forebay) and cell 2.	
3-2. Enter the total surface area of the basin footprint based on site constraints, A_{tot}	A_{tot} = _____ ft ²
3-3. Enter the length of the basin footprint based on site constraints, L_{tot} (L:W = 1.5:1 min)	L_{tot} = _____ ft
3-4. Calculate the width of the basin footprint, $W_{tot} = A_{tot} / L_{tot}$	W_{tot} = _____ ft
3-5. Enter interior side slope as length per unit height (min = 3), Z	Z = _____
3-6. Enter desired freeboard depth, d_{fb} (min: 2 ft on-line; 1 ft offline)	d_{fb} = _____ ft
3-7. Calculate the length of the active volume surface area including the internal berm but excluding freeboard, $L_{av-tot} = L_{tot} - 2Zd_{fb}$	L_{av-tot} = _____ ft
3-8. Calculate the width of the active volume surface area including the internal berm but excluding freeboard, $W_{av-tot} = W_{tot} - 2Zd_{fb}$	W_{av-tot} = _____ ft
3-9. Calculate the total active volume surface area including the internal berm and excluding freeboard, $A_{av-tot} = L_{av-tot} \cdot W_{av-tot}$	A_{av-tot} = _____ ft ²
3-10. Enter the width of the internal berm (6 ft min), W_{berm}	W_{berm} = _____ ft
3-11. Enter the length of the internal berm, $L_{berm} = W_{av-tot}$	L_{berm} = _____ ft
3-12. Calculate the area of the berm, $A_{berm} = W_{berm} \cdot L_{berm}$	A_{berm} = _____ ft ²
3-13. Calculate the SUSMP surface area excluding the internal berm and freeboard, $A_{av} = A_{av-tot} - A_{berm}$	A_{av} = _____ ft ²

Step 4: Determine Dimensions of Cell 1	
4-1. Enter the percent of V_a in Cell 1 (25% required), $\%V_1$	$\%V_1 =$ %
4-2. Calculate the active volume of Cell 1, $V_1 = (V_a \cdot \%V_1)/100$	$V_1 =$ ft ³
4-3. Enter a desired average depth for the active volume of Cell 1, d_1	$d_1 =$ ft
4-4. Calculate the surface area for the active volume of Cell 1, $A_1 = V_1 / d_1$	$A_1 =$ ft ²
4-5. Enter the width of Cell 1, $W_1 = W_{wq-tot} = L_{berm}$	$W_1 =$ ft
4-6. Calculate the length of Cell 1 (Note: inlet and outlet should be configured to maximize the residence time), $L_1 = A_1 / W_1$	$L_1 =$ ft
Step 5: Determine Dimensions of Cell 2	
5-1. Calculate the active volume of Cell 2, $V_2 = V_a - V_1$	$V_2 =$ ft ³
5-2. Calculate the surface area of the active volume of Cell 2, $A_2 = A_{av} - A_1$	$A_2 =$ ft ²
5-3. Calculate the average depth for the active volume of Cell 2, $d_2 = V_2 / A_2$	$d_2 =$ ft
5-4. Enter the width of Cell 2, $W_2 = W_1 = W_{av-tot} = L_{berm}$	$W_2 =$ ft
5-5. Calculate the length of Cell 2, $L_2 = A_2 / W_2$	$L_2 =$ ft
5-6. Calculate the width of Cell 2 at half of d_2 , $W_{mid2} = W_2 - Zd_2$	$W_{mid2} =$ ft
5-7. Calculate the length of Cell 2 at half of d_2 , $L_{mid2} = W_2 - Zd_2$	$L_{mid2} =$ ft
5-8. Verify that the length-to-width ratio of Cell 2 at half of d_2 is at least 1.5:1 with $\geq 2:1$ preferred. If the length-to-width ratio is less than 1.5:1, modify input parameters until a ratio of at least 1.5:1 is achieved. If the input parameters cannot be modified as a result of site constraints, another site for the basin should be chosen, $LW_{mid2} = L_{mid2} / W_{mid2}$	$LW_{mid2} =$
Step 6: Ensure Design Requirements and Site Constraints are Achieved	
6-1. Check design requirements and site constraints. Modify design geometry until requirements are met. If the chosen site for the basin is inadequate to meet the design requirements, choose a new location or alternative treatment BMP.	
Step 7: Size Outlet Structure	
7-1. Refer to Appendix C for pond outlet structure sizing methodologies and examples. The total drawdown time for the basin should be 36-48 hours. The outlet structure shall be designed to release the bottom 50% of the detention volume (half-full to empty) over 24-32 hours, and the top half (full to half-full) in 12-16 hours. A primary overflow should be sized to pass the peak flow rate from the developed capital design storm.	

Step 8: Determine Emergency Spillway Requirements

8-1. For online basins, an emergency overflow spillway should be sized to pass the capital design storm in order to prevent overtopping of the walls or berms in the event that a blockage of the riser occurs. For offline basins, an emergency spillway or riser should be sized to pass the SUSMP storm. For sites where the emergency spillway discharges to a steep slope, an emergency overflow riser, in addition to the spillway should be provided.

Dry Extended Detention Basin Design Example

Step 1: Determine SUSMP Volume

For this design example, a 10-acre residential development with a 60% total impervious area is considered.

Step 1: Determine SUSMP volume		
1-1. Enter drainage area, A	A =	10 acres
1-2. Enter impervious fraction, Imp	Imp =	0.60
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C =	0.59
1-4. Enter design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended)), P_i	P_i =	1.2 in
1-5. Calculate rainfall depth, $P = P_i/12$	P =	0.10 ft
1-6. Calculate SUSMP volume, $V_{wg} = 43560 \cdot P \cdot A \cdot C$	V_{wg} =	25,700 ft ³

Step 2: Calculate Volume of the Active Basin and the Forebay Basin

Step 2: Calculate the design volume of the active basin		
2-1. Calculate basin active design volume (includes SUSMP + sediment storage volume), $V_a = 1.05V_{wg}$	V_a =	26,985 ft ³

Step 3: Determine Detention Basin Location and Preliminary Geometry Based on Site Constraints

The detention basin in this example has an internal berm separating the forebay (Cell 1) and the main basin (Cell 2). The internal berm elevation is 2 ft below the elevation of the SUSMP volume within the entire basin. The berm length is equal to the width of the basin when filled to the active design volume.

Step 3: Determine Detention Basin Location and Preliminary Geometry Based on Site Constraints		
3-1. Based on site constraints, determine the basin geometry and the storage available by developing an elevation-storage relationship for the basin. For this simple example, assume a trapezoidal geometry for cell 1 (forebay) and cell 2.		
3-2. Enter the total surface area of the basin footprint based on site constraints, A_{tot}	A_{tot} =	11,000 ft ²
3-3. Enter the length of the basin footprint based on site constraints, L_{tot} (L:W = 1.5:1 min)	L_{tot} =	200 ft
3-4. Calculate the width of the basin footprint, $W_{tot} = A_{tot} / L_{tot}$	W_{tot} =	55 ft
3-5. Enter interior side slope as length per unit height (min = 3), Z	Z =	3

Step 3: Determine Detention Basin Location and Preliminary Geometry Based on Site Constraints		
3-6. Enter desired freeboard depth, d_{fb} (min: 2 ft on-line; 1 ft offline)	$d_{fb} =$	2 ft
3-7. Calculate the length of the active volume surface area including the internal berm but excluding freeboard, $L_{av-tot} = L_{tot} - 2Zd_{fb}$	$L_{av-tot} =$	188 ft
3-8. Calculate the width of the active volume surface area including the internal berm but excluding freeboard, $W_{av-tot} = W_{tot} - 2Zd_{fb}$	$W_{av-tot} =$	43 ft
3-9. Calculate the total active volume surface area including the internal berm and excluding freeboard, $A_{av-tot} = L_{av-tot} \cdot W_{av-tot}$	$A_{av-tot} =$	8,084 ft ²
3-10. Enter the width of the internal berm (6 ft min), W_{berm}	$W_{berm} =$	6 ft
3-11. Enter the length of the internal berm, $L_{berm} = W_{av-tot}$	$L_{berm} =$	43 ft
3-12. Calculate the area of the berm, $A_{berm} = W_{berm} \cdot L_{berm}$	$A_{berm} =$	258 ft ²
3-13. Calculate the SUSMP surface area excluding the internal berm and freeboard, $A_{av} = A_{av-tot} - A_{berm}$	$A_{av} =$	7,826 ft ²

Step 4: Calculate Dimensions of Cell 1

Calculate the dimensions of the forebay (Cell 1) based on the active design volume for Cell 1 (25% of V_a) and a desired average depth, d_1 . The width of the forebay, W_1 , is equivalent to the length of the berm, L_{berm} , and the width of Cell 2, W_2 .

Step 4: Determine Dimensions of Cell 1		
4-1. Enter the percent of V_a in Cell 1 (25% required), $\%V_1$	$\%V_1 =$	25 %
4-2. Calculate the active volume of Cell 1 (including sediment storage), $V_1 = (V_a \cdot \%V_1)/100$	$V_1 =$	6,746 ft ³
4-3. Enter a desired average depth for the active volume of Cell 1, d_1	$d_1 =$	5 ft
4-4. Calculate the surface area for the active volume of Cell 1, $A_1 = V_1 / d_1$	$A_1 =$	1,349 ft ²
4-5. Enter the width of Cell 1, $W_1 = W_{wq-tot} = L_{berm}$	$W_1 =$	43 ft
4-6. Calculate the length of Cell 1 (<u>Note</u> : inlet and outlet should be configured to maximize the residence time), $L_1 = A_1 / W_1$	$L_1 =$	31 ft

Step 5: Calculate the Dimensions of Cell 2

Calculate the dimensions of the main basin (Cell 2) based on the active design volume for Cell 2 and a desired average depth, d_2 . A calculation of the length, L_{mid2} , and width, W_{mid2} , at half basin depth, d_2 , is conducted in order to verify that the length-to-width ratio at half d_2 is greater than 1.5:1.

Step 5: Calculate the dimensions of Cell 2		
5-1. Calculate the active volume of Cell 2, $V_2 = V_a - V_1$	$V_2 =$	20,239 ft ³
5-2. Calculate the surface area of the active volume of Cell 2, $A_2 = A_{av} - A_1$	$A_2 =$	6,477 ft ²
5-3. Calculate the average depth of the active volume of Cell 2, $d_2 = V_2 / A_2$	$d_2 =$	3 ft
5-4. Enter the width of Cell 2, $W_2 = W_1 = W_{av-tot} = L_{berm}$	$W_2 =$	43 ft
5-5. Calculate the length of Cell 2, $L_2 = A_2 / W_2$	$L_2 =$	151 ft
5-6. Calculate the width of Cell 2 at half of d_2 , $W_{mid2} = W_2 - Zd_2$	$W_{mid2} =$	34 ft
5-7. Calculate the length of Cell 2 at half of d_2 , $L_{mid2} = W_2 - Zd_2$	$L_{mid2} =$	52 ft
5-8. Verify that the length-to-width ratio of Cell 2 at half of d_2 is at least 1.5:1 with $\geq 2:1$ preferred. If the length-to-width ratio is less than 1.5:1, modify input parameters until a ratio of at least 1.5:1 is achieved. If the input parameters cannot be modified as a result of site constraints, another site for the basin should be chosen, $LW_{mid2} = L_{mid2} / W_{mid2}$	$LW_{mid2} =$	1.6

Step 6: Ensure Design Requirements and Site Constraints are Achieved

Check design requirements and site constraints. Modify design geometry until requirements are met. If the chosen site for the basin is inadequate to meet the design requirements, choose a new location or an alternative treatment BMP.

Step 7: Size Outlet Structure

Refer to Appendix C for basin outlet structure sizing methodologies and examples. The total drawdown time for the basin should be 36-48 hours. The outlet structure shall be designed to release the bottom 50% of the detention volume (half-full to empty) over 24-32 hours, and the top half (full to half-full) in 12-16 hours. A primary overflow should be sized to pass the peak flow rate from the developed capital design storm.

Step 8: Determine Emergency Spillway Requirements

For online basins, an emergency overflow spillway should be sized to pass the capital design storm in order to prevent overtopping of the walls or berms in the event that a blockage of the riser occurs. For offline basins, an emergency spillway or riser should be sized to pass the SUSMP storm. For sites where the emergency spillway discharges to a steep slope, an emergency overflow riser, in addition to the spillway should be provided.

Vegetated Swale Worksheet

Step 1: Determine SUSMP flow	
1-1. Enter drainage area, A (acres)	A = _____ acres
1-2. Enter impervious fraction, Imp (eg. 60% = 0.60)	Imp = _____
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = _____
1-4. Enter design rainfall intensity, i (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for sizing methods for flow-based controls)	i = _____ in/hr
1-5. Calculate SUSMP flow, $Q_{wq} = C \cdot i \cdot A$	$Q_{wq} =$ _____ cfs
Step 2: Calculate swale bottom width	
2-1. Enter Manning's roughness coefficient for shallow flow conditions (use 0.2), n_{wq}	$n_{wq} =$ _____
2-2. Enter expected vegetation height, y_a	$y_a =$ _____ ft
2-3. Calculate design flow depth, $y = 2/3 y_a$ (0.17 for mowed turf)	y = _____ ft
2-4. Enter longitudinal slope (along direction of flow), s_f	$s_f =$ _____ ft/ft
2-5. Calculate bottom width of swale, $b = Q_{wq} n_{wq} / 1.49 y^{1.67} s_f^{0.5}$	b = _____ ft
2-6. If b is between 2 and 10 feet, go to Step 3	
2-7. If b is less than 2 ft, assume b = 2 ft and recalculate flow depth, $y = (Q_{wq} n_{wq} / 2.98 s_f^{0.5})^{0.6}$	y = _____ ft
2-8. If b is greater than 10 ft, one of the following design adjustments must be made: 1) increase the longitudinal slope to a maximum of 0.06 ft/ft (check dams may be used to achieve this), and repeat steps 2-3 to 2-5 above. 2) increase the design flow depth to a maximum of 4 in (0.33 ft) and repeat steps 2-2 to 2-5 above. 3) include a flow splitter longitudinally along the swale bottom (Figure 3-1) that extends at least three-quarters of the swale length (beginning at the inlet).	
Step 3: Determine design flow velocity	
3-1. Enter side slope length per unit height (e.g. 3 if side slope are 3H :1V), Z	Z = _____
3-2. Calculate the cross-sectional area of flow at design depth, $A_{wq} = b \cdot y + Z \cdot y^2$	$A_{wq} =$ _____ ft ²
3-3. Calculate design flow velocity, $V_{wq} = Q_{wq} / A_{wq}$	$V_{wq} =$ _____ ft/s

Step 4: Calculate swale length	
4-1. Enter target residence time (10 minutes minimum)	$t_{HR} =$ s
4-2. Calculate swale length, $L = 60t_{HR}V_{wq}$	$L =$ ft
4-3. If L is too long for the site, proceed to Step 5 to adjust the swale layout	
4-4. If L is greater than 100 ft and will fit within the constraints of the site skip to Step 6	
4-5. If L is less than 100 ft, increase the length to a minimum of 100 ft leaving the bottom width unchanged, skip to Step 6	
Step 5: Adjust swale layout to fit within site constraints	
5-1. Choose a reduced swale length, L_f	$L_f =$ ft
5-2. Recalculate flow velocity, $V_{wq} = L_f / (60t_{HR})$	$V_{wq} =$ ft/s
5-3. Recalculate cross-sectional area, $A_{wq} = Q_{wq} / V_{wq}$	$A_{wq} =$ ft ²
5-4. Calculate an increased bottom width $b_f = Q / (V_{wq}y)$	$b_f =$ ft
5-5. Recalculate longitudinal slope, $s_f = [Q_{wq}n_{wq} / (1.49A_{wq}y^{2/3})]^2$	$s_f =$ %
5-6. If s_f is between 1.5% and 6%, the swale design is acceptable for water quality, proceed to Step 6	
5-7. If s_f is between 1% and 1.5%, the swale design is acceptable for water quality with underdrains (see design requirements). Proceed to Step 6. 2. If longitudinal slopes are less than 1.5% and the soils are poorly drained (e.g., silts and clays), then underdrains shall be provided. A soils report to verify soils properties shall be provided for swales less than 1.5%.	
5-8. If s_f is <1%, the swale design is unacceptable. Consider subdividing drainage area and repeat all above steps, or choose a different BMP for the site.	
Step 6: Provide conveyance capacity for flows higher than Q_{wq} (if swale is on-line)	
6-1. If the swale already includes a high-flow bypass to convey flows higher than the SUSMP flow rate, skip this step and verify that all parameters meet design requirements to complete sizing	
6-2. If swale does not include a high-flow bypass, check the swale size for capital storm peak flow conveyance (Refer to Design Manual Hydraulic, Section C, "Criteria for Hydraulic Design: Open Channels". Calculate the capital peak flow velocity, V_p	$V_p =$ ft/s
6-3. If $V_p > 3.0$ feet per second, return to Step 2 and increase the bottom width or flatten the longitudinal slope as necessary to reduce the capital storm peak flow velocity to 3.0 feet per second or less. If the longitudinal slope is flattened, the swale bottom width must be recalculated (Step 2) and must meet all design criteria.	

Vegetated Swale Design Example

Step 1: Determine SUSMP Flow

For this design example, a 10-acre residential development with a 60% total impervious area is considered. Flow-based sizing Method 1 as described in A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) is assumed. Therefore, the design intensity is 0.2 in/hr.

Step 1: Determine SUSMP flow	
1-1. Enter drainage area, A (acres)	A = 10 acres
1-2. Enter impervious fraction, Imp	Imp = 0.60
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = 0.59
1-4. Enter design rainfall intensity, i (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for sizing methods for flow-based controls)	i = 0.2 in/hr
1-5. Calculate SUSMP flow, $Q_{wg} = C \cdot i \cdot A$	$Q_{wg} = 1.18$ cfs

Step 2: Calculate Swale Bottom Width

The swale bottom width is calculated based on Manning's equation. The grass height in the swale will be maintained at 4-inches. Therefore, the design depth is assumed to be 2/3 of 4 inches, or 2.7 inches (0.22 ft). The default Manning's roughness coefficient is assumed appropriate for expected vegetation density and design depth.

Step 2: Calculate swale bottom width	
2-1. Enter Manning's roughness coefficient for shallow flow conditions (0.2 typical), n_{wg}	$n_{wg} = 0.2$
2-2. Enter expected vegetation height, y_g	$y_g = 0.5$ ft
2-3. Calculate design flow depth, $y = 2/3 y_g$ (0.33 ft for mowed turf)	$y = 0.33$ ft
2-4. Enter longitudinal slope (along direction of flow), s_f	$s_f = 0.04$ ft/ft
2-5. Calculate bottom width of swale, $b = Q_{wg} n_{wg} / 1.49 y^{1.67} s_f^{0.5}$	$b = 5.0$ ft
2-6. If b is between 2 and 10 feet, go to Step 3	

Step 3: Determine Design Flow Velocity

The side slopes are will be designed as 3H :1V, so $Z = 3$.

Step 3: Determine design flow velocity	
3-1. Enter side slope length per unit height (e.g. 3 if side slope are 3H :1V), Z	Z = 3
3-2. Calculate the cross-sectional area of flow at design depth, $A_{wq} = b \cdot y + Z \cdot y^2$	$A_{wq} = 2.0 \text{ ft}^2$
3-3. Calculate design flow velocity, $V_{wq} = Q_{wq} / A_{wq}$	$V_{wq} = 0.6 \text{ ft/s}$

Step 4: Calculate Swale Length

Using the design flow velocity and a minimum residence time of 10 minutes, the length of the swale is calculated as follows. The swale length must be a minimum of 100 ft.

Step 4: Calculate swale length	
4-1. Enter target residence time (10 minutes minimum), t_{HR}	$t_{HR} = 10 \text{ min}$
4-2. Calculate swale length, $L = 60 \cdot t_{HR} \cdot V_{wq}$	$L = 360 \text{ ft}$
4-3. If L is too long for the site, proceed to step 5 to adjust the swale layout	
4-4. If L is greater than 100 ft and will fit within the constraints of the site skip to Step 6	
4-5. If L is less than 100 ft, increase the length to a minimum of 100 ft leaving the bottom width unchanged, skip to Step 6	

Site constraints only allow a swale length of 250 feet. Therefore proceed to Step 5 to adjust the swale length.

Step 5: Adjust Swale Layout to Fit Within Site Constraints

To adjust swale length to 250 feet, the bottom width needs to be increased (up to a maximum of 16 ft if a divider is provided).

Step 5: Adjust swale layout to fit within site constraints	
5-1. Choose a reduced swale length, L_f	$L_f = 250 \text{ ft}$
5-2. Recalculate flow velocity, $V_{wq} = L_f / (60t_{HR})$	$V_{wq} = 0.42 \text{ ft/s}$
5-3. Recalculate cross-sectional area, $A_{wq} = Q_{wq} / V_{wq}$	$A_{wq} = 2.8 \text{ ft}^2$
5-4. Calculate an increased bottom width $b_f = Q_{wq} / (V_{wq} \cdot y)$	$b_f = 8.5 \text{ ft}$
5-5. Recalculate longitudinal slope, $s_f = [Q_{wq} n_{wq} / (1.49 A_{wq} y^{2/3})]^2$	$s_f = 1.4 \%$
5-6. If s_f is between 1.0% and 6%, the swale design is acceptable for water quality, proceed to Step 6	

Since longitudinal slopes are less than 1.5%, if the soils are poorly drained (e.g., silts and clays), then an underdrains should be provided. A soils report to verify soils properties should be provided for swales less than 1.5%.

Step 6: Provide Conveyance Capacity for Flows Higher than Q_{wq}

The swale will be offline such that all flows greater than Q_{wq} will be bypassed

Filter Strip Worksheet

Step 1: Calculate the design flow	
1-1. Enter drainage area, A	A = acres
1-2. Enter impervious fraction, Imp	Imp =
1-3. Calculate runoff coefficient, $C = (0.9 \cdot \text{Imp} + 0.05)$	C =
1-4. Enter design rainfall intensity, i (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for flow-based controls sizing Method 1)	i = in/hr
1-5. Calculate SUSMP flow, $Q_{wq} = CiA$	Q_{wq} = cfs
Step 2: Calculate the design flow depth	
2-1. Enter filter strip longitudinal slope, s	s =
2-2. Enter Manning roughness coefficient (0.25-.3), n_{wq}	n_{wq} =
2-3. Enter width of impervious surface contributing area, W	W = ft
2-4. Calculate average depth of water using Manning eq, $d_f = 12[Q_{wq}n_{wq}/1.49Ws^{0.5}]^{0.6}$	d_f = in
2-5. If $d_f > 1"$, go step 2-1 and decrease the slope	
2-6. If the slope cannot be changed due to construction constraints, go to step 2-3 and increase the width perpendicular to flow	
Step 3: Calculate the design velocity	
3-1. Calculate design flow velocity, $V_{wq} = Q_{wq}/d_f W$	V_{wq} = ft/s
3-2. If the $V_{wq} > 1$ ft/s go to step 2-1 and decrease the slope	
Step 4: Calculate the length of the filter strip	
4-1. Enter residence time (10 minutes, min.), t	t = min
4-2. Calculate length of the filter strip, $L = 60tV_{wq}$	L = ft
4-3. If $L < 4$ ft, go to step 2-1 and increase the slope	

Filter Strip Design Example

Step 1: Calculate the Design Flow

For this design example, a 10-acre residential development with a 60% total impervious area is considered. Flow-based sizing Method 1, as described in A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended), is assumed. Therefore, the design rainfall intensity is assumed to be 0.2 in.

Step 1: Calculate the design flow		
1-1. Enter drainage area, A	A =	10 acres
1-2. Enter impervious fraction, Imp	Imp =	0.60
1-3. Calculate runoff coefficient, $C = (0.9 \times \text{Imp} + 0.05)$	C =	0.59
1-4. Enter design rainfall intensity, i (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for flow-based controls sizing Method 1)	i =	0.2 in/hr
1-5. Calculate SUSMP flow, $Q_{wg} = CiA$	Q_{wg} =	1.18 cfs

Step 2: Calculate the Design Flow Depth

Based on the site constraints we choose the width of the filter strip 150 ft and the filter strip longitudinal slope as 3%. The design water depth should not exceed 1 inch.

Step 2: Calculate the design flow depth		
2-1. Enter filter strip longitudinal slope, s	s =	0.03
2-2. Enter Manning roughness coefficient (0.25-.3), n_{wg}	n_{wg} =	0.27
2-3. Enter width of impervious surface contributing area, W	W =	150 ft
2-4. Calculate average depth of water using Manning eq, $d_t = \frac{12[Q_{wg}n_{wg}/1.49Ws^{0.5}]^{0.6}}{1}$	d_f =	0.67 in
2-5. If $d_f > 1"$, go step 2-1 and decrease the slope		
2-6. If the slope cannot be changed due to construction constraints, go to step 2-3 and increase the width perpendicular to flow		

Step 3: Calculate the Design Velocity

The designed flow velocity should not exceed 1 foot/second across the filter strip.

Step 3: Calculate the design velocity		
3-1. Calculate design flow velocity, $V_{wg} = Q_{wg}/d_fW$	V_{wg} =	0.1401 ft/s
3-2. If the design flow velocity is higher than 1ft/s go to step 2-1 and decrease the slope		

Step 4: Calculate the Length of the Filter Strip

The filter strip should be at least 4 feet long (in the direction of flow) and accommodate a minimum residence time of 10 minutes to provide adequate water quality treatment.

Step 4: Calculate the length of the filter strip	
4-1. Enter residence time(10 minutes, min.), t	t = 10 min
4-2. Calculate length of the filter strip, $L = 60tV_{wg}$	L = 84.1 ft
4-3. If $L < 4$ ft, go to step 2-1 and increase the slope	

Bioretention Area Worksheet

Step 1: Determine SUSMP volume	
1-1. Enter drainage area, A	A = _____ acres
1-2. Enter impervious fraction, Imp	Imp = _____
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = _____
1-4. Enter design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for volume-based controls sizing methods), P_i	P_i = _____ in
1-5. Calculate rainfall depth, $P = P_i/12$	P = _____ ft
1-6. Calculate SUSMP volume, $V_{wq} = 43560 \cdot P \cdot A \cdot C$	V_{wq} = _____ ft ³
Step 2: Pretreatment	
2-1. If required please go to filter strips worksheet	
Step 3: Calculate bioretention area	
3-1. Enter thickness of planting mix (min. 24"), l	l = _____ in
3-2. Enter storage depth (max. 18") above the filter, d	d = _____ in
3-3. Enter design percolation rate (with an underdrain, assume 0.375"/hr min.; without an underdrain, use measured percolation rate x 0.25), P_{design}	P_{design} = _____ in/hr
3-4. Enter drawdown time (48 hrs, max.), t	t = _____ hr
3-5. Calculate bioretention area necessary, $A_{sf} = V_{wq}/t P_{\text{design}}$	A_{sf} = _____ ft ²
Step 4: Calculate underdrain system or size gravel layer	
4-1. Calculated filtered flow rate to be conveyed by the longitudinal drain pipe, $Q_f = P_{\text{design}} \cdot A_{sf}/43200$ (note: for this example, step 4-1 is equivalent to step 5-1 of the Sand Filter Worksheet).	Q_f = _____ cfs
4-2. Please follow steps 5-2 through 5-7 of the Sand Filter Worksheet to calculate the underdrain system capacity.	
4-3. If no underdrain, size a gravel layer. Calculate the maximum depth of runoff that can be infiltrated within the required drain time (max. 72 hr), $d_{\text{max}} = \frac{P_{\text{design}}}{12} * t$	d_{max} = _____ ft
4-4. Choose the gravel drainage layer porosity n (typically	n = _____
4-5. Choose the gravel drainage layer depth (l) such that $d_{\text{max}} \geq n * l$	l = _____ ft

Step 4: Calculate underdrain system or size gravel layer (cont)	
4-6. Choose the fill time T (time to fill bioretention area with water) (hrs) [use 2 hours for most designs]	T = hrs
4-6. Calculate the infiltrating surface area (filter bottom area) required: $A = \frac{V_{design}}{\frac{TP_{design}}{12} + nl} * t$	A = ft ²
Step 5: Provide Conveyance Capacity for Flows Higher than Q_{wg}	
5-1. An emergency overflow must still be provided in the event that the surface area becomes clogged or the bioretention area is placed online.	

Bioretention Area Design Example

Bioretention areas have several components that allow the pretreatment, spreading, filtration, collection and discharge of the incoming flows.

Step 1: Determine SUSMP Volume

For this design example, a 10-acre residential development with a 60% total impervious area is considered.

Step 1: Determine SUSMP volume	
1-1. Enter drainage area, A	A = 10 acres
1-2. Enter impervious fraction, Imp	Imp = 0.60
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = 0.59
1-4. Enter design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for volume-based controls sizing methods), P_i	$P_i = 1.2$ in
1-5. Calculate rainfall depth, $P = P_i/12$	P = 0.10 ft
1-6. Calculate SUSMP volume, $V_{\text{wq}} = 43560 \cdot P \cdot A \cdot C$	$V_{\text{wq}} = 25,700$ ft ³

Step 2: Pretreatment

The bioretention areas that collect runoff from residential roofs, sidewalks, driveways, or other "cleaner" surfaces do not require pretreatment. If the runoff originates from locations other than "clean" surfaces, then pretreatment is required. Please refer to Filter Strips Worksheet for detailed calculations.

Step 3: Determine bioretention area footprint area

A bioretention area is designed with two components: (1) temporary storage reservoir to store runoff, and (2) a plant mix filter bed (planting soil mixed with sand content = 70%) through which the stored runoff must percolate to obtain treatment.

The simple sizing method does not route flows through the filter which would allow a more accurate sizing of the facility. The size of the filter is determined based on the simple assumption that inflow is immediately discharged through the filter at a rate not less than 0.375 in/hr which is equivalent to drawing down the maximum 18" storage depth over 48 hours (0.375 in/hr = 18 in/48 hr).

Step 3: Calculate bioretention footprint area		
3-1. Enter thickness of planting mix (min. 24"), l	$l =$	24 in
3-2. Enter storage depth (18" max.) above the filter, d	$d =$	18 in
3-3. Enter percolation rate (0.375"/hr min.), P_{design}	$P_{\text{design}} =$	0.375 in/hr
3-4. Enter drawdown time (48 hrs max.), t	$t =$	48 hr
3-5. Calculate bioretention area, $A_{\text{sf}} = V_{\text{wq}}/t P_{\text{design}}$	$A_{\text{sf}} =$	17,134 ft ²

Step 4: Calculate Filter Longitudinal Underdrain Collection Pipe

If an underdrain is required, please see the sand filter underdrain calculation. All underdrain pipes must be 6 inches or greater to facilitate cleaning.

Step 4: Calculate filter underdrain system		
4-1. Calculated filtered flow rate to be conveyed by the longitudinal drain pipe, $Q_f = P_{\text{design}} \cdot A_{\text{sf}}/43200$ (note: for this example, step 4-1 is equivalent to step 5-1 of the Sand Filter Worksheet.	$Q_f =$	0.1 cfs
4-2. Please follow steps 5-2 through 5-7 of the Sand Filter Worksheet to calculate the underdrain system capacity.		

Step 5: Provide Conveyance Capacity for Flows Higher than Q_{wq}

Provide conveyance capacity for flows higher than Q_{wq} , SUSMP flow rate, to bypass the bioretention area. An emergency overflow must also be provided in the event that the surface area becomes clogged or the bioretention area is placed online.

Infiltration Facilities Worksheet

Step 1: Determine SUSMP volume	
1-1. Enter drainage area, A	A = _____ acres
1-2. Enter impervious fraction, Imp	Imp = _____
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = _____
1-4. Enter design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for volume-based controls sizing methods), P_i	P_i = _____ in
1-5. Calculate rainfall depth, $P = P_i/12$	P = _____ ft
1-6. Calculate SUSMP volume, $V_{\text{wg}} = 43560 \cdot P \cdot A \cdot C$	V_{wg} = _____ ft ³
Step 2: Calculate design infiltration rate	
2-1. Enter measured soil percolation rate (0.5 in/hr min.), P_{measured}	P_{measured} = _____ in/hr
2-2. Enter correction factor for testing (0.5), F_t	F_t = _____
2-3. Enter correction factor for plugging, (0.7 loams-sandy loams, 0.8 fine-loamy sands, 0.9 medium sands, 1.0 coarse sands-cobbles), F_p	F_p = _____
2-4. Calculate F_{geometry} (must be between 0.25 and 1.0), $F_{\text{geometry}} = 4 D/W + 0.05$, where D=depth from the bottom of the facility to the maximum wet-season water table elevation or nearest impervious layer, whichever is less (ft) and W = width of the facility (ft)	F_{geometry} = _____
2-5. Calculate the design percolation rate, $P_{\text{design}} = P_{\text{measured}} F_t F_p F_{\text{geometry}}$	P_{design} = _____ in/hr
Step 3: Determine facility size	
3-1. Enter drawdown time (72 hrs max.), t_d	t_d = _____ hrs
3-2. Calculate max.depth of runoff that can be infiltrated within the t_d , $d_{\text{max}} = P_{\text{design}} t_d/12$	d_{max} = _____ ft
3-3. For basins, select ponding depth d_p such that $d_p \leq d_{\text{max}}$	d_p = _____ ft
3-4. For trenches, enter trench fill aggregate porosity, n_t	n_t = _____
3-5. Enter depth of trench fill, d_t	d_t = _____ in
3-5. Select trench ponding depth d_p such that $d_p \leq d_{\text{max}} - n_t d_t$	d_p = _____ ft
Step 4: Determine infiltrating surface area (filter bottom area)	
4-1. Enter the time to fill infiltration basin or trench with water (Use 2 hours for most designs), T	T = _____ hrs
4-2. Calculate infiltrating surface area for infiltration basin: $A_b = V_{\text{wg}}/(T P_{\text{design}}/12 + d_p)$	A_b = _____ ft ²

4-3. Calculate infiltrating surface area for infiltration trenches: $A_t = \frac{V_{wq}}{(T P_{design} / 12 + n_t d_t + dp)}$	$A_t =$ ft^2
Step 5: Provide conveyance capacity for filter clogging	
5-1. The infiltration facility should be placed off-line, but an emergency overflow must still be provided in the event the filter becomes clogged.	

Infiltration Facility Design Example

Step 1: Determine SUSMP Volume

For this design example, an infiltration basin and trench are sized for a 10-acre residential development with a 60% total impervious area.

Step 1: Determine SUSMP volume	
1-1. Enter drainage area, A	A = 10 acres
1-2. Enter impervious fraction, Imp	Imp = 0.60
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = 0.59
1-4. Enter design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for volume-based controls sizing methods), P_i	P_i = 1.2 in
1-5. Calculate rainfall depth, $P = P_i/12$	P = 0.10 ft
1-6. Calculate SUSMP volume, $V_{wq} = 43560 \cdot P \cdot A \cdot C$	V_{wq} = 25,700 ft ³

Step 2: Calculate Design Infiltration Rate

Infiltration facilities require a minimum soil infiltration rate of 0.5 in/hr. If the rate exceeds 2.4 in/hr as in this example, then the runoff should be fully treated in an upstream BMP prior to infiltration to protect the groundwater quality.

Step 2: Calculate design infiltration rate	
2-1. Enter measured soil percolation rate (0.5 in/hr min.), P_{measured}	P_{measured} = 4 in/hr
2-2. Enter correction factor for testing (0.5), F_t	F_t = 0.5
2-3. Enter correction factor for plugging, (0.7 loams-sandy loams, 0.8 fine-loamy sands, 0.9 medium sands, 1.0 coarse sands-cobbles), F_p	F_p = 0.8
2-4. Calculate F_{geometry} (must be between 0.25 and 1.0), $F_{\text{geometry}} = 4 D/W + 0.05$, where D=depth from the bottom of the facility to the maximum wet-season water table elevation or nearest impervious layer, whichever is less (ft) and W = width of the facility (ft)	F_{geometry} = 0.25
2-5. Calculate the design percolation rate, $P_{\text{design}} = P_{\text{measured}} F_t F_p F_{\text{geometry}}$	P_{design} = 0.4 in/hr

Step 3: Determine Facility Size

The simple sizing method requires that the SUSMP volume must be completely infiltrated within 72 hours. The size of the infiltration trench is determined based on the simple assumption that inflow is immediately discharged through the trench.

Step 3: Determine facility size		
3-1. Enter drawdown time (72 hrs max.), t_d	$t_d =$	72 hrs
3-2. Calculate max. depth of runoff that can be infiltrated within the t_d , $d_{max} = P_{design} t_d / 12$	$d_{max} =$	2.4 ft
3-3. Enter trench fill aggregate porosity, n_t	$n_t =$	0.32
3-4. Enter depth of trench fill, d_t	$d_t =$	4 ft
3-5. Select trench ponding depth d_p such that $d_p \leq d_{max} - n_t d_t$	$d_p =$	1.1 ft

Step 4: Determine Infiltrating Surface Area

The size of the infiltrating surface is determined by assuming the SUSMP volume will fill the available ponding depth (plus the void spaces of the computed porosity (usually about 32%) of the gravel in the trench).

Step 4: Determine infiltrating surface area (filter bottom area)		
4-1. Enter the time to fill infiltration basin or trench with water (Use 2 hours for most designs), T	$T =$	2 hrs
4-2. Calculate infiltrating surface area for infiltration basin: $A_b = V_{wq} / [(T P_{design} / 12) + d_p]$	$A_b =$	10,420 ft ²
4-3. Calculate infiltrating surface area for infiltration trenches: $A_t = V_{wq} / (T P_{design} / 12 + n_t d_t + d_p)$	$A_t =$	10,500 ft ²

Step 5: Provide Conveyance Capacity for Flows Higher than Q_{wq}

5-1. The infiltration facility should be placed off-line, but an emergency overflow for flows greater than the SUSMP peak flow rate, Q_{wq} , must still be provided in the event the filter becomes clogged.

Stormwater Wetland Worksheet

Step 1: Determine SUSMP Volume	
1-1. Enter drainage area, A	A = acres
1-2. Enter impervious fraction, Imp	Imp =
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C =
1-4. Enter the design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for volume-based controls sizing methods), P_i	P_i = in
1-5. Calculate rainfall depth, $P = P_i/12$	P = ft
1-6. Calculate SUSMP volume, $V_{\text{wg}} = 43560 \cdot P \cdot A \cdot C$	V_{wg} = ft ³
Step 2: Determine Wetland Location, Wetland Type and Preliminary Geometry Based on Site Constraints	
2-1. Based on site constraints, determine the wetland geometry and the storage available by developing an elevation-storage relationship for the wetland. For this simple example, assume a trapezoidal geometry for cell 1 (forebay) and cell 2. The wetland does not have extended detention.	
2-2. Enter the total surface area of the wetland footprint based on site constraints, A_{tot}	A_{tot} = ft ²
2-3. Enter the length of the wetland footprint based on site constraints, L_{tot}	L_{tot} = ft
2-4. Calculate the width of the wetland footprint, $W_{\text{tot}} = A_{\text{tot}} / L_{\text{tot}}$	W_{tot} = ft
2-5. Enter interior side slope as length per unit height (min = 3), Z	Z =
2-6. Enter desired freeboard depth, d_{fb}	d_{fb} = ft
2-7. Calculate the length of the SUSMP surface area including the internal berm but excluding freeboard, $L_{\text{wg-tot}} = L_{\text{tot}} - 2Zd_{\text{fb}}$	$L_{\text{wg-tot}}$ = ft
2-8. Calculate the width of the SUSMP surface area including the internal berm but excluding freeboard, $W_{\text{wg-tot}} = W_{\text{tot}} - 2Zd_{\text{fb}}$	$W_{\text{wg-tot}}$ = ft
2-9. Calculate the total SUSMP surface area including the internal berm and excluding freeboard, $A_{\text{wg-tot}} = L_{\text{wg-tot}} \cdot W_{\text{wg-tot}}$	$A_{\text{wg-tot}}$ = ft ²
2-10. Enter the width of the internal berm (6 ft min), W_{berm}	W_{berm} = ft
2-11. Enter the length of the internal berm, $L_{\text{berm}} = W_{\text{wg-tot}}$	L_{berm} = ft
2-12. Calculate the area of the berm, $A_{\text{berm}} = W_{\text{berm}} \cdot L_{\text{berm}}$	A_{berm} = ft ²
2-13. Calculate the SUSMP volume surface area excluding the internal berm and freeboard, $A_{\text{wg}} = A_{\text{wg-tot}} - A_{\text{berm}}$	A_{wg} = ft ²

Step 3: Determine Dimensions of Cell 1 (forebay)		
3-1. Enter the percent of V_{wq} in Cell 1 (10-20% required), $\%V_1$	$\%V_1 =$	%
3-2. Calculate the active volume of Cell 1 (includes SUSMP + sediment storage volume), $V_1 = (V_{wq} \cdot \%V_1)/100$	$V_1 =$	ft ³
3-3. Enter desired average depth of Cell 1 (5-9 ft including sediment storage of 1 ft), d_1	$d_1 =$	ft
3-4. Calculate the surface area for the SUSMP volume of Cell 1, $A_1 = V_1 / d_1$	$A_1 =$	ft ²
3-5. Enter the width of Cell 1, $W_1 = W_{av-tot} = L_{berm}$	$W_1 =$	ft
3-6. Calculate the length of Cell 1 (<u>Note:</u> inlet and outlet should be configured to maximize the residence time), $L_1 = A_1 / W_1$	$L_1 =$	ft
Step 4: Determine Dimensions of Cell 2		
4-1. Calculate the active volume of Cell 2, $V_2 = V_{wq} - V_1$	$V_2 =$	ft ³
4-2. Calculate surface area of Cell 2, $A_2 = A_{wq} - A_1$	$A_2 =$	ft ²
4-3. Enter width of Cell 2, $W_2 = W_1 = W_{wq-tot} = L_{berm}$	$W_2 =$	ft
4-4. Calculate top length of Cell 2, $L_2 = A_2 / W_2$	$L_2 =$	ft
4-5. Verify that the length-to-width ratio of Cell 2 is at least 3:1 with $\geq 4:1$ preferred. If the length-to-width ratio is less than 3:1, modify input parameters until a ratio of at least 3:1 is achieved. If the input parameters cannot be modified as a result of site constraints, another site for the pond should be chosen, $LW_2 = L_2 / W_2$	$LW_2 =$	
4-6. Enter percent of surface area of very shallow zone, $\%A_{vs}$ (see recommended distribution of depths, pg. 7-3)	$\%A_{vs} =$	%
4-7. Calculate very shallow zone surface area, $A_{vs} = (A_2 \cdot \%A_{vs})/100$	$A_{vs} =$	ft ²
4-8. Enter average depth of very shallow zone (0.1 - 1 ft), d_{vs}	$d_{vs} =$	ft
4-9. Calculate volume of very shallow zone, $V_{vs} = A_{vs} \cdot d_{vs}$	$V_{vs} =$	ft ³
4-10. Enter width of very shallow zone, $W_{vs} = W_2$	$W_{vs} =$	ft
4-11. Calculate length of very shallow zone, $L_{vs} = A_{vs} / W_{vs}$	$L_{vs} =$	ft
4-12. Enter percent of surface area of shallow zone, $\%A_s$	$\%A_s =$	%
4-13. Calculate surface area of shallow zone, $A_s = (A_2 \cdot \%A_s)/100$	$A_s =$	ft ²
4-14. Enter average depth of shallow zone (1 - 3 ft), d_s	$d_s =$	ft
4-15. Calculate volume of shallow zone, $V_s = A_s \cdot d_s$	$V_s =$	ft ³
4-16. Enter width of shallow zone, $W_s = W_2$	$W_s =$	ft
4-17. Calculate length of shallow zone, $L_s = A_s / W_s$	$L_s =$	ft
4-18. Calculate surface area of deep zone, $A_{deep} = A_2 - A_{vs} - A_s$	$A_{deep} =$	ft ²
4-19. Calculate volume of deep zone, $V_{deep} = V_2 - V_{vs} - V_s$	$V_{deep} =$	ft ³

Step 4: Determine Dimensions of Cell 2	
4-20. Calculate average depth of deep zone (3 - 5 ft), $d_{\text{deep}} = V_{\text{deep}} / A_{\text{deep}}$	$d_{\text{deep}} =$ _____ ft
4-21. Enter width of deep zone, $W_{\text{deep}} = W_2$	$W_{\text{deep}} =$ _____ ft
4-22. Calculate length of deep zone, $L_{\text{deep}} = A_{\text{deep}} / W_{\text{deep}}$	$L_{\text{deep}} =$ _____ ft
Step 5: Ensure Design Requirements and Site Constraints are Achieved	
5-1. Check design requirements and site constraints. Modify design geometry until requirements are met. If the chosen site for the wetland is inadequate to meet the design requirements, choose a new location for the wetland or select an alternative treatment BMP.	
Step 6: Size Outlet Structure	
6-1. Please refer to Appendix C for wetland outlet structure sizing methodologies and examples. The wetland outlet pipe shall be sized, at a minimum, to pass flows greater than the SUSMP peak flow for off-line basins or flow from the capital storm for on-line basins.	
Step 7: Determine Emergency Spillway Requirements	
7-1. For online basins, an emergency overflow spillway should be sized to pass the capital design storm to prevent overtopping of the walls or berms in the event that a blockage of the riser occurs. For offline basins, an emergency spillway or riser should be sized to pass the SUSMP storm. For sites where the emergency spillway discharges to a steep slope, an emergency overflow riser, in addition to the spillway should be provided.	

Stormwater Wetland Design Example

Wetland siting requires the following considerations prior to construction: (1) availability of base flow – stormwater wetlands require a regular source of water to support wetland biota, (2) slope stability – stormwater wetlands are not permitted near steep slope hazard areas, (3) surface space availability – large footprint area is required, and (4) compatibility with flood control – basins must not interfere with flood control functions of existing conveyance and detention structures.

The wetland in this example does not have extended detention. An internal berm separates the forebay (Cell 1) and the main basin (Cell 2). The berm is at the elevation of the active volume (SUSMP plus sediment storage volume) design surface which is also the permanent wetpool elevation.

Step 1: Determine SUSMP Volume

For this design example, a 10-acre residential development with a 60% total impervious area is considered.

Step 1: Determine SUSMP Volume	
1-1. Enter drainage area, A	A = 10 acres
1-2. Enter impervious fraction, Imp	Imp = 0.60
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = 0.59
1-4. Enter the design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for volume-based controls sizing methods), P_i	$P_i = 1.20$ in
1-5. Calculate rainfall depth, $P = P_i/12$	P = 0.10 ft
1-6. Calculate SUSMP volume, $V_{\text{wq}} = 43560 \cdot P \cdot A \cdot C$	$V_{\text{wq}} = 25,700$ ft ³

Step 2: Determine Pond Location and Preliminary Geometry Based on Site Constraints

A total footprint area and total length available for the wetland is provided. This step calculates the total active volume surface area which is equivalent to the permanent wetpool surface area. This step also calculates the dimensions of the internal berm.

Step 2: Determine Wetland Location, Wetland Type and Preliminary Geometry Based on Site Constraints	
2-1. Based on site constraints, determine the wetland geometry and the storage available by developing an elevation-storage relationship for the wetland. For this simple example, assume a trapezoidal geometry for cell 1 (forebay) and cell 2. The wetland does not have extended detention.	

Step 2: Determine Wetland Location, Wetland Type and Preliminary Geometry Based on Site Constraints	
2-2. Enter the total surface area of the wetland footprint based on site constraints, A_{tot}	$A_{tot} = 11,000 \text{ ft}^2$
2-3. Enter the length of the wetland footprint based on site constraints, L_{tot}	$L_{tot} = 200 \text{ ft}$
2-4. Calculate the width of the wetland footprint, $W_{tot} = A_{tot} / L_{tot}$	$W_{tot} = 55 \text{ ft}$
2-5. Enter interior side slope as length per unit height (min = 3), Z	$Z = 3$
2-6. Enter desired freeboard depth, d_{fb}	$d_{fb} = 2 \text{ ft}$
2-7. Calculate the length of the SUSMP surface area including the internal berm but excluding freeboard, $L_{wq-tot} = L_{tot} - 2Zd_{fb}$	$L_{wq-tot} = 188 \text{ ft}$
2-8. Calculate the width of the SUSMP surface area including the internal berm but excluding freeboard, $W_{wq-tot} = W_{tot} - 2Zd_{fb}$	$W_{wq-tot} = 43 \text{ ft}$
2-9. Calculate the total SUSMP surface area including the internal berm and excluding freeboard, $A_{wq-tot} = L_{wq-tot} \cdot W_{wq-tot}$	$A_{wq-tot} = 8,084 \text{ ft}^2$
2-10. Enter the width of the internal berm (6 ft min), W_{berm}	$W_{berm} = 6 \text{ ft}$
2-11. Enter the length of the internal berm, $L_{berm} = W_{wq-tot}$	$L_{berm} = 43 \text{ ft}$
2-12. Calculate the area of the berm, $A_{berm} = W_{berm} \cdot L_{berm}$	$A_{berm} = 258 \text{ ft}^2$
2-13. Calculate the active volume surface area excluding the internal berm and freeboard, $A_{wq} = A_{wq-tot} - A_{berm}$	$A_{wq} = 7,826 \text{ ft}^2$

Step 3: Determine Dimensions of Cell 1

It should be assumed that cell 1 (the forebay) should be 15% of the SUSMP volume, V_{wq} .

Step 3: Determine Dimensions of Cell 1	
3-1. Enter the percent of V_{wq} in Cell 1 (10-20% required), $\%V_1$	$\%V_1 = 15 \%$
3-2. Calculate the active volume of Cell 1 (including sediment storage), $V_1 = (V_{wq} \cdot \%V_1)/100$	$V_1 = 3,855 \text{ ft}^3$
3-3. Enter desired average depth of Cell 1 (5-9 ft including sediment storage of 1 ft), d_1	$d_1 = 5 \text{ ft}$
3-4. Calculate the surface area for the SUSMP volume of Cell 1, $A_1 = V_1 / d_1$	$A_1 = 771 \text{ ft}^2$
3-5. Enter the width of Cell 1, $W_1 = W_{av-tot} = L_{berm}$	$W_1 = 43 \text{ ft}$
3-6. Calculate the length of Cell 1 (<u>Note</u> : inlet and outlet should be configured to maximize the residence time), $L_1 = A_1 / W_1$	$L_1 = 18 \text{ ft}$

Step 4: Determine Dimensions of Cell 2

Verify that the surface area and length-to-width ratio of Cell 2 meet the design criteria. Calculate volumes, depths and surface areas for the very shallow, shallow and deep zones.

Step 4: Determine Dimensions of Cell 2		
4-1. Calculate the active volume of Cell 2, $V_2 = V_{wq} - V_1$	$V_2 =$	21,845 ft ³
4-2. Calculate surface area of Cell 2, $A_2 = A_{wq} - A_1$	$A_2 =$	7,055 ft ²
4-3. Enter width of Cell 2, $W_2 = W_1 = W_{wq-tot} = L_{berm}$	$W_2 =$	43 ft
4-4. Calculate top length of Cell 2, $L_2 = A_2 / W_2$	$L_2 =$	164 ft
4-5. Verify that the length-to-width ratio of Cell 2 is at least 3:1 with $\geq 4:1$ preferred. If the length-to-width ratio is less than 3:1, modify input parameters until a ratio of at least 3:1 is achieved. If the input parameters cannot be modified as a result of site constraints, another site for the pond should be chosen, $LW_2 = L_2 / W_2$	$LW_2 =$	4
4-6. Enter percent of surface area of very shallow zone, $\%A_{vs}$	$\%A_{vs} =$	15 ft ²
4-7. Calculate very shallow zone surface area, $A_{vs} = (A_2 \cdot \%A_{vs})/100$	$A_{vs} =$	1,058 ft ²
4-8. Enter average depth of very shallow zone (0.1 - 1 ft), d_{vs}	$d_{vs} =$	1 ft
4-9. Calculate volume of very shallow zone, $V_{vs} = A_{vs} \cdot d_{vs}$	$V_{vs} =$	1,058 ft ³
4-10. Enter width of very shallow zone, $W_{vs} = W_2$	$W_{vs} =$	43 ft
4-11. Calculate length of very shallow zone, $L_{vs} = A_{vs} / W_{vs}$	$L_{vs} =$	25 ft
4-12. Enter percent of surface area of shallow zone, $\%A_s$	$\%A_s =$	55
4-13. Calculate surface area of shallow zone, $A_s = (A_2 \cdot \%A_s)/100$	$A_s =$	3,880 ft ²
4-14. Enter average depth of shallow zone (1 - 3 ft), d_s	$d_s =$	3 ft
4-15. Calculate volume of shallow zone, $V_s = A_s \cdot d_s$	$V_s =$	11,641 ft ³
4-16. Enter width of shallow zone, $W_s = W_2$	$W_s =$	43 ft
4-17. Calculate length of shallow zone, $L_s = A_s / W_s$	$L_s =$	90 ft
4-18. Calculate surface area of deep zone, $A_{deep} = A_2 - A_{vs} - A_s$	$A_{deep} =$	2,116 ft ²
4-19. Calculate volume of deep zone, $V_{deep} = V_2 - V_{vs} - V_s$	$V_{deep} =$	9,146 ft ³
4-20. Calculate average depth of deep zone (3 - 5 ft), $d_{deep} = V_{deep} / A_{deep}$	$d_{deep} =$	4 ft
4-21. Enter width of deep zone, $W_{deep} = W_2$	$W_{deep} =$	43 ft
4-22. Calculate length of deep zone, $L_{deep} = A_{deep} / W_{deep}$	$L_{deep} =$	49 ft

Step 5: Ensure Design Requirements and Site Conditions are Achieved

Check design requirements and site constraints. Modify design geometry until requirements are met. If the chosen site for the wetland is inadequate to meet the design requirements, choose a new location for the wetland or select an alternative treatment BMP.

Step 6: Size Outlet Structure

Please refer to Appendix C for wetland outlet structure sizing methodologies and examples. The wetland outlet pipe shall be sized, at a minimum, to pass flows greater than the SUSMP peak flow for off-line basins or flow from the capital storm for on-line basins.

Step 7: Determine Emergency Spillway Requirements

For online basins, an emergency overflow spillway should be sized to pass the capital design storm to prevent overtopping of the walls or berms in the event that a blockage of the riser occurs. For offline basins, an emergency spillway or riser should be sized to pass the SUSMP storm. For sites where the emergency spillway discharges to a steep slope, an emergency overflow riser, in addition to the spillway should be provided.

Sand Filters Worksheet

Step 1: Determine SUSMP volume	
1-1. Enter drainage area, A	A = _____ acres
1-2. Enter impervious fraction, Imp	Imp = _____
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C = _____
1-4. Enter design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for volume-based controls sizing methods), P_i	P_i = _____ in
1-5. Calculate rainfall depth, $P = P_i/12$	P = _____ ft
1-6. Calculate SUSMP volume, $V_{wg} = 43560 \cdot P \cdot A \cdot C$	V_{wg} = _____ ft ³
Step 2: Calculate sand filter area	
2-1. Enter thickness of sand filter (min. 2 ft, 3 ft preferred), L	L = _____ ft
2-2. Enter maximum storage depth (6 feet) above the filter, d	d = _____ ft
2-3. Enter routing adjustment factor, R	R = _____
2-4. Calculate average depth of water above the filter, $h = d/2$	h = _____ ft
2-5. Enter hydraulic conductivity (1"/hr), K_i	K_i = _____ in/hr
2-6. Calculate hydraulic conductivity (ft/day), $K_{day} = 2K_i$	K_{day} = _____ ft/day
2-7. Calculate hydraulic gradient, $i = (h+L)/L$	i = _____ ft/ft
2-8. Enter drawdown time, t	t = _____ day
2-9. Calculate sand filter area, $A_{sf} = (V_{wg}RL)/(K_{day}t(h+L))$	A_{sf} = _____ ft ²
Step 3: Determine filter dimensions	
3-1. Sand filter area, A_{sf}	A_{sf} = _____ ft ²
3-2. Enter geometric configuration, $L_R:W$ ratio (2:1), L_R	L_R = _____
3-3. Calculate the width of the sand filter, W	W = _____ ft
3-4. Calculate the length of the sand filter, L	L = _____ ft
3-5. Calculate rate of filtration, $r_{wg} = K_{day}i$	r_{wg} = _____ ft/d/ft ²
Step 4: Calculate storage volume	
4-1. Enter interior side slopes, 3H:1V(max), Z	Z = _____
4-2. Calculate top length, $L_t = L + 2Zd$	L_t = _____ ft
4-3. Calculate top width, $W_t = W + 2Zd$	W_t = _____ ft
4-4. Calculate filter storage volume, $V_s = 1/3 \cdot d(A_{sf} + A_t + (A_{sf}A_t)^{0.5})$ Where $A_t = L_t \cdot W_t$	V_s = _____ ft ³

Step 5: Calculate filter longitudinal underdrain collection pipe	
5-1. Calculated filtered flow rate, $Q_f = r_{wg} A_{sf}$	$Q_f =$ cfs
5-2. Enter minimum slope for energy gradient, S_e	$S_e =$
5-3. Enter Hazen-Williams coefficient for plastic, C	C =
5-4. Enter pipe diameter, D	D = in
5-5. Calculate pipe hydraulic radius, $R_h = D/48$	$R_h =$ ft
5-6. Calculate velocity at the outlet of the pipe, $V_p = 1.318 C R_h^{0.63} S_e^{0.54}$	$V_p =$ ft/s
5-7. Calculate pipe capacity, $Q_{cap} = 0.25 \pi (D/12)^2 V_p$	$Q_{cap} =$ cfs
Step 6: Provide conveyance capacity for filter clogging	
6-1. The sand filters should be placed off-line, but an emergency overflow must still be provided in the event the filter becomes clogged and verify that all parameters meet design requirements to complete sizing.	

Sand Filter Design Example

Step 1: Determine SUSMP Volume

For this design example, a 10-acre residential development with a 60% total impervious area is considered.

Step 1: Determine SUSMP volume		
1-1. Enter drainage area, A	A =	10 acres
1-2. Enter impervious fraction, Imp	Imp =	0.60
1-3. Calculate runoff coefficient, $C = 0.9 \cdot \text{Imp} + 0.05$	C =	0.59
1-4. Enter design rainfall depth of the storm, (see A Manual for the Standard Urban Storm Water Mitigation Plan, LACDPW, September 2002 (or as amended) for volume-based controls sizing methods), P_i	P_i =	1.2 in
1-5. Calculate rainfall depth, $P = P_i/12$	P =	0.10 ft
1-6. Calculate SUSMP volume, $V_{\text{wg}} = 43560 \cdot P \cdot A \cdot C$	V_{wg} =	25,700 ft ³

Step 2: Calculate Sand Filter Area

A sand filter is designed with two components: (1) temporary storage reservoir to store runoff, and (2) a sand filter bed through which the stored runoff must percolate getting treatment. The simple sizing method does not route flows through the filter. The size of the filter is determined based on the simple assumption that inflow is immediately discharged through the filter. The adjustment factor, R, is applied to compensate for the greater filter size resulting from this method.

Step 2: Calculate sand filter area		
2-1. Enter thickness of sand filter (min. 24" or 2'), l	l =	2 ft
2-2. Enter storage depth (6' max.) above the filter, d	d =	6 ft
2-3. Enter routing adjustment factor, R	R =	0.7
2-4. Calculate average depth of water above the filter, $h = d/2$	h =	3 ft
2-5. Enter hydraulic conductivity (1"/hr), K_i	K_i =	1 in/hr
2-6. Calculate hydraulic conductivity (ft/day), $K_{\text{day}} = 2K_i$	K_{day} =	2 ft/day
2-7. Calculate hydraulic gradient, $i = (h+l)/l$	i =	2.5 ft/ft
2-8. Enter drawdown time, t	t =	2 day
2-9. Calculate sand filter area, $A_{\text{sf}} = (V_{\text{wg}} R i) / (K_{\text{day}} t (h+l))$	A_{sf} =	1,799 ft ²

Step 3: Determine Filter Dimensions

Step 3: Determine filter dimensions		
3-1. Sand filter area, A_{sf}	A_{sf} =	1,799 ft ²

Step 3: Determine filter dimensions	
3-2. Enter geometric configuration, $L_R:W$ ratio (2:1 min.), L_R	$L_R = 2$
3-3. Calculate the width of the sand filter, W	$W = 30.0 \text{ ft}$
3-4. Calculate the length of the sand filter, L	$L = 60.0 \text{ ft}$
3-5. Calculate rate of filtration, $r_{wq} = K_{day}i$	$r_{wq} = 5.0 \text{ ft/d/ft}^2$

Step 4: Calculate Storage Volume

The side slopes are will be designed as 3H:1V, so $Z = 3$.

Step 4: Calculate storage volume	
4-1. Enter interior side slopes, 3H:1V(max), Z	$Z = 3$
4-2. Calculate top length, $L_t = L + 2Zd$	$L_t = 96.0 \text{ ft}$
4-3. Calculate top width, $W_t = W + 2Zd$	$W_t = 66.0 \text{ ft}$
4-4. Calculate filter storage volume, $V_s = 1/3 \cdot d(A_{sf} + A_t + (A_{sf}A_t)^{0.5})$, where $A_t = L_t \cdot W_t$	$V_s = 23,018 \text{ ft}^3$

Step 5: Calculate Filter Longitudinal Underdrain Collection Pipe

All underdrain pipes must be 6 inches or greater to facilitate cleaning.

Step 5: Calculate filter longitudinal underdrain collection pipe	
5-1. Calculated filtered flow rate, $Q_f = r_{wq}A_{sf}$	$Q_f = 0.10 \text{ cfs}$
5-2. Enter minimum slope for energy gradient, S_e	$S_e = 0.005$
5-3. Enter Hazen-Williams coefficient for plastic, C	$C = 140$
5-4. Enter pipe diameter, D	$D = 6 \text{ in}$
5-5. Calculate pipe hydraulic radius, $R_h = D/48$	$R_h = 0.13$
5-6. Calculate velocity at the outlet of the pipe, $V_p = 1.318CR_h^{0.63}S_e^{0.54}$	$V_p = 2.8 \text{ ft/s}$
5-7. Calculate pipe capacity, $Q_{cap} = 0.25\pi(D/12)^2V_p$	$Q_{cap} = 0.6 \text{ cfs}$

Step 6: Provide Conveyance Capacity for Filter Clogging

The sand filters should be placed off-line, but an emergency overflow must still be provided in the event the filter becomes clogged and **verify that all parameters meet design requirements** to complete sizing.

APPENDIX C POND OUTLET SIZING EXAMPLES

Perforated Risers Outlet Sizing Methodology (Figure 2-2)

The following factors are inputs to the perforated riser outlet sizing calculations:


- Shape of the pond (e.g. trapezoidal)
- Depth and volume of the pond
- Elevation / depth of first row of holes
- Elevation / depth of last row of holes
- Size of perforations
- Number of rows or perforations and number of perforations per row
- Desired draw down time (e.g. 16 hour and 32 hour draw down for top half and bottom half respectively, 48 hour total draw down time)

The governing the rate of discharge from a perforated riser structure can be calculated using Equation C-1 below:

$$Q = C_p \frac{2A_p}{3H_s} \sqrt{2g} H^{3/2} \quad (\text{Equation C-1})$$

Where:

- Q = riser flow discharge (cfs)
 C_p = discharge coefficient for perforations (use 0.61)
 A_p = cross-sectional area of all the holes (ft²)
 s = center to center vertical spacing between perforations (ft)
 H_s = distance from $s/2$ below the lowest row of holes to $s/2$ above the top row of holes (McEnroe 1988).
 H = distance from $s/2$ below the lowest row of holes to the water surface elevation under consideration.



For the iterative computations needed to size the perforations in the riser and determine the riser height a simplified version of Equation C-1 may be used, as shown below in Equation C-2:

$$Q = kH^{3/2} \quad (\text{Equation C-2})$$

Where:

$$k = C_p \frac{2A_p}{3H_s} \sqrt{2g} \quad (\text{Equation C-3})$$

Uniformly perforated riser designs are defined by the depth or elevation of the first row of perforations, the length of the perforated section of pipe, and the size or diameter of each perforation. The steps needed to size a perforated riser outlet are outlined below.

Step 1: Determine riser elevation or depth in the pond

Set the riser elevation at 6" above the pond bottom to provide for sediment storage. Select a riser height such that the last row of perforations is inline with the top of the SUSMP pool elevation.

Step 2: Determine pond and riser attributes and constants for computations

Parameters examined at this step include pond geometry such as pond shape, pond bottom length and width, and pond side slopes. Organize the attributes obtained in this step in a table such as Table C-1.

Step 3: Determine constant k

Determine the value of the constant k (Equations C-2 and C-3) that provides the desired draw down time.

- a. Set up a computation table such as Table C-3. Note that the table must have at least 19 height slices or the bottom 5% of the pond should be combined in the computations. The formulas for each column of the computation table are provided in Table C-2.
- b. Using the pond depth, partition the pond into equal height horizontal slices to be stored as entries in Table C-3. At each elevation E_n (or table entry), complete the following:
 - i. Determine the change in elevation H_n (ft) $[H_n = (E_o - E_{n+1})]$
 - ii. Calculate the average discharge Q_n (cfs) $[Q_n = k(H_n)^{3/2}]$ Eqn 3
 - iii. Calculate the pond surface area A_n (ft²) $[A_n = L \times W \text{ for rectangular ponds}]$
 - iv. Compute the available storage V_n (ft³) $[V_n = A_n \times H_n]$
 - v. Determine the average drain time T_n (hrs) $[T_n = (V_n / Q_n) \times 3600]$
- c. Sum up the drain times at each height slice to determine the total drain time for the pond. If the value obtained is smaller or greater than the desired value, increase or decrease the k value and repeat the computations in step b until the desired drain time is achieved.

Step 4: Determine the size and number of rows of perforations

Determine the size and number of rows of perforations that yield a k value equal to the k value used in the previous step. Follow the steps below to obtain riser attributes:

- Select an initial number of rows, number of holes per row and an initial hole diameter.
- Obtain flow area per row values from Table C-4 or compute flow area.
- Select a value for H_s and C_p and compute k .
- Repeat the above steps varying the number of rows, hole diameter, number of holes per row and H_s until the desired value of k is obtained or it is determined that k is too small to be matched by any realistic combination of inputs. Hole diameter should not be less than 1/4" to minimize the potential for clogging.

Step 5: Verify the design

The design is completed by verifying that the drain time for the both the top half and the bottom half are acceptable and the total drain time is equivalent to the desired value. Note that the drain time for the top half can be obtained by summing the drain times for the top half of the entries in the computation Table C-3. The drain time for the bottom half can similarly be obtained by summing values for the drain times for the bottom half of the entries in the computation Table C-3.

Table C-1: Constants Used in Example Computations

Constant	Values	Units
Orifice coefficient (C_p)	0.6	-
Perforation diameter (d)	0.0468	ft
Combined area of holes (A_p)	0.0399	ft ²
Acceleration due to gravity (g)	32.2	ft/s ²
Pond bottom length (L)	40	ft
Pond bottom width (W)	20	ft
Side slopes (z)	3	-
Pond bottom surface area (A)	800	ft ²
k	0.02791	ft ^{3/2} /s

Table C-2: Pond Draw Down Time Calculation

Line No.	Elev. (ft)	Change in Elevation (ft)	Average Discharge (cfs)	**Pond Surface Area (ft ²)	Storage Volume (ft ³)	Average Drain Time (hrs)
1	E_0	$H_0 = (E_0 - E_1)$	$Q_0 = k(H_0)^{3/2}$	$A_0 = L \times W$	$V_0 = A_0 \times H_0$	$T_0 = V_0 / Q_0$
2	E_1	$H_1 = (E_1 - E_2)$	$Q_1 = k(H_1)^{3/2}$	$A_1 = L \times W$	$V_1 = A_1 \times H_1$	$T_1 = V_1 / Q_1$
3	E_2	$H_2 = (E_2 - E_1)$	$Q_2 = k(H_2)^{3/2}$	$A_2 = L \times W$	$V_2 = A_2 \times H_2$	$T_2 = V_2 / Q_2$
...	...	...	...	...	...	...

* q_{add} is the additional flow from any additional orifices below the current elevation

** Pond surface area can be calculated or measured. Non rectangular cross sections must use the appropriate formulas for calculating cross-sectional areas.

Table C-3: Sample Spread Sheet for Perforated Riser Outlet Sizing Calculations

Line No.	Elevation	Change in height	Average Flow at Elev. (top orifice only)	Pond Surface Area	Storage Volume	Time to Drain Unit at Current Flow
	$[E_n]$	$[E_1 - E_2]$	[See Eqn 3]	A_n	$[A_n \times dH]$	$[V_{nv} / Q_n]$
	(ft)	H_n (ft)	Q_n (cfs)	(ft ²)	V_n (ft ³)	T (hrs)
1	6	0.3	0.4102	4256	1419	1.0
2	5.7	0.3	0.3765	3996	1332	1.0
3	5.3	0.3	0.3438	3744	1248	1.0
4	5.0	0.3	0.3120	3500	1167	1.0
5	4.7	0.3	0.2814	3264	1088	1.1
6	4.3	0.3	0.2518	3036	1012	1.1
7	4.0	0.3	0.2233	2816	939	1.2
8	3.7	0.3	0.1960	2604	868	1.2
9	3.3	0.3	0.1699	2400	800	1.3
10	3.0	0.3	0.1450	2204	735	1.4
11	2.7	0.3	0.1215	2016	672	1.5
12	2.3	0.3	0.0995	1836	612	1.7
13	2.0	0.3	0.0789	1664	555	2.0
14	1.7	0.3	0.0601	1500	500	2.3
15	1.3	0.3	0.0430	1344	448	2.9
16	1.0	0.3	0.0279	1196	399	4.0
17	0.7	0.3	0.0152	1056	352	6.4
18	0.3	0.3	0.0054	924	308	15.9
19	0.0	0.0	0.0000	800	0	0.0
Total Draw Down Time						48

Table C-4: Circular Perforation Sizing for Perforated Riser.

Hole Dia (in) *	Hole Dia (in)	Min. S _c (in)	Area per Row (sq in)		
			n=1	n=2	n=3
1/4	0.250	1	0.05	0.10	0.15
5/16	0.313	2	0.08	0.15	0.23
3/8	0.375	2	0.11	0.22	0.33
7/16	0.438	2	0.15	0.30	0.45
1/2	0.500	2	0.20	0.39	0.59
9/16	0.563	3	0.25	0.50	0.75
5/8	0.625	3	0.31	0.61	0.92
11/16	0.688	3	0.37	0.74	1.11
3/4	0.750	3	0.44	0.88	1.33
13/16	0.813	3	0.52	1.04	1.56
7/8	0.875	3	0.60	1.20	1.80
15/16	0.938	3	0.69	1.38	2.07
1	1.000	4	0.79	1.57	2.36
1 1/16	1.063	4	0.89	1.77	2.66
1 1/8	1.125	4	0.99	1.99	2.98
1 3/16	1.188	4	1.11	2.22	3.32
1 1/4	1.250	4	1.23	2.45	3.68
1 5/16	1.313	4	1.35	2.71	4.06
1 3/8	1.375	4	1.48	2.97	4.45
1 7/16	1.438	4	1.62	3.25	4.87
1 1/2	1.500	4	1.77	3.53	5.30
1 9/16	1.563	4	1.92	3.83	5.75
1 5/8	1.625	4	2.07	4.15	6.22
1 11/16	1.688	4	2.24	4.47	6.71
1 3/4	1.750	4	2.41	4.81	7.22
1 13/16	1.813	4	2.58	5.16	7.74
1 7/8	1.875	4	2.76	5.52	8.28
1 15/16	1.938	4	2.95	5.90	8.84
2	2.000	4	3.14	6.28	9.42
n = Number of columns of perforations					

Source: UDFCD, 1999

Multiple Orifice Outlet Sizing Methodology

The following attributes influence multiple orifice outlet sizing calculations:

- Shape of the pond (e.g. trapezoidal)
- Depth and volume of the pond
- Elevation of each orifice
- Desired draw-down time (e.g., 16 hour and 32 hour draw down times for top half and bottom half respectively, 48 hour draw down time for whole pond)

The rate of discharge from a single orifice can be calculated using Equation C-4 below:

$$Q = CA(2gH)^{0.5} \quad \text{(Equation C-4)}$$

Where:

- Q = orifice flow discharge
- C = discharge coefficient
- A = cross-sectional area of orifice or pipe (ft²)
- g = acceleration due to gravity (32.2 ft/s²)
- H = effective head on the orifice (measured from center of orifice to water surface)

Multiple orifice designs are defined by the depth (or elevation) and the size (or diameter) of each orifice (Figure 2-1). The steps needed to size a dual orifice outlet are outlined below; multiple orifices may be provided and sized using a similar approach.

Step 1: Determine orifice elevations

- a. For the bottom orifice, set the orifice elevation (H_b) at a maximum of 6" above the pond bottom. If the bottom orifice is below the invert of the outlet pipe, then use the outlet pipe invert elevation for orifice calculations.
- b. For the top orifice, set the orifice elevation (H_t) at half way to the top of the SUSMP pool.

Step 2: Determine pond and orifice attributes and constants for computations

Parameters examined at this step include pond geometry such as pond shape, pond bottom length and bottom width and pond side slopes. Organize the attributes obtained in this step in a table such as Table C-5.

Step 3: Determine the required size of the bottom orifice

- a. Set up a computation table such as Table C-6. The formulas for each column of the computation table are provided in Table C-7.
- b. Using the pond depth, partition the pond into equal height horizontal slices to be stored as entries in Table C-6. At each elevation E_n (or table entry), complete the following:

- | | |
|---|--|
| i. Determine the change in elevation H_n (ft) | $[H_n = (E_o - E_{n+1})]$ |
| ii. Calculate the average discharge Q_n (cfs) | $[Q_n = CA(2gH_n)^{0.5}]$ Eqn 1 |
| iii. Calculate the pond surface area A_n (ft ²) | $[A_n = L \times W \text{ for rectangular ponds}]$ |
| iv. Compute the available storage V_n (ft ³). | $[V_n = A_n \times H_n]$ |
| v. Determine the average drain time T_n (hrs) | $[T_n = (V_n / Q_n) \times 3600]$ |
- c. Sum up the drain times at each height slice to determine the total drain time for the bottom half of the pond. If the value obtained is smaller or greater than the desired value, increase or decrease the orifice diameter and repeat the computations in step b above until the desired drain time is achieved

Step 4: Determine the required size of the top orifice

- a. Set up a Table such as Table C-8. The formulas for each column of the computation tables are provided in Table C-7.
- b. At each elevation E_n complete the following:
- | | |
|--|--|
| i. Determine the change in elevation H_n (ft) | $[H_n = (E_n - E_{n+1})]$ |
| ii. Calculate the average discharge Q_n (cfs) | $[q_n = CA(2gH_n)^{0.5}]$ Eqn 1 |
| iii. Calculate the combine average discharge Q_0 | $[Q_n = q_n + q_{add}]$ |
| iv. Calculate the pond surface area A_n (ft ²) | $[A_n = L \times W \text{ for rectangular ponds}]$ |
| v. Compute the available storage V_n (ft ³) | $[V_n = A_n \times H_n]$ |
| vi. Determine the average drain time T_n (hrs) | $[T_n = V_n / Q_n]$ |
| vii. Note that q_{add} is the maximum discharge from the bottom orifice. | |
- c. Sum up the drain times at each height slice to determine the total drain time for the top half of the pond. If the value obtained is smaller than the desired value, increase or decrease the orifice diameter and repeat the computations in step 4b until the desired drain time is achieved.

Step 5: Verify the design

The design is completed by verifying that the sum of the detention times for the top half of the pond and the bottom half of the pond add up to the total desired detention time (36 to 48 hours).

Table C-5: Constants Used in Example Computations

Constant	Lower Orifice Values	Upper Orifice Values	Units
Orifice coefficient (C_p)	0.6	0.6	-
Orifice diameter (d)	0.0633	0.0675	ft
Orifice cross-sectional area (a)	0.003	0.004	ft ²
Acceleration due to gravity (g)	32.2	32.2	ft/s ²
Pond bottom length (L)	40	40	ft
Pond bottom width (W)	20	20	ft
Side slopes (z)	3	3	-
Pond bottom surface area (A)	800	800	ft ²

Table C-6: Sample Spreadsheet for Dual Orifice Pond Outlet Sizing Calculations: Bottom Half of Pond

Line Number	Elevation [E]	Change in height	Average Flow at Elev. (top orifice only)	Pond Surface Area	Storage Volume	Time to Drain Unit at Current Flow Rate
		$[E_1 - E_2]$	[See Eqn 1]	A_{elev}	$[A_{elev} \times dH]$	$[V_{elev} / Q_{elev}]$
	(ft)	H (ft)	q_{top} (cfs)	(ft ²)	V_{elev} (ft ³)	T (hrs)
1	3.0	3.0	0.0567	2204	735	3.6
2	2.7	2.7	0.0534	2016	672	3.5
3	2.3	2.3	0.0500	1836	612	3.4
4	2.0	2.0	0.0463	1664	555	3.3
5	1.7	1.7	0.0422	1500	500	3.3
6	1.3	1.3	0.0378	1344	448	3.3
7	1.0	1.0	0.0327	1196	399	3.4
8	0.7	0.7	0.0267	1056	352	3.7
9	0.3	0.3	0.0189	924	308	4.5
10	0.0	0.0	0.0000	800	0	0.0
Subtotal Draw Down Time					32.0	

Table C-7: Pond Draw Down Time Calculation

Line No.	Elev. (ft)	Change in Elevation (ft)	Average Discharge (cfs)	*Combined Average Discharge (cfs)	**Pond Surface Area (ft ²)	Storage Volume (ft ³)	Average Drain Time (hrs)
1	E_0	$H_0 = (E_0 - E_1)$	$q_0 = CA(2gH_0)^{0.5}$	$Q_1 = q_1 + q_{add}$	$A_0 = L \times W$	$V_0 = A_0 \times H_0$	$T_0 = V_0 / Q_0$
2	E_1	$H_1 = (E_1 - E_2)$	$q_1 = CA(2gH_1)^{0.5}$	$Q_2 = q_2 + q_{add}$	$A_1 = L \times W$	$V_1 = A_1 \times H_1$	$T_1 = V_1 / Q_1$
3	E_2	$H_2 = (E_2 - E_1)$	$q_2 = CA(2gH_2)^{0.5}$	$Q_3 = q_3 + q_{add}$	$A_2 = L \times W$	$V_2 = A_2 \times H_2$	$T_2 = V_2 / Q_2$
...	...	...	...	...	...	...	...

* q_{add} is the additional flow from any additional orifices below the current elevation

** Pond surface area can be calculated or measured. Non-rectangular cross sections must use the appropriate formulas for calculating cross-sectional areas.

Table C-8: Sample Spreadsheet for Dual Orifice Pond Outlet Sizing Calculations: Top Half of Pond

Line Number	Elevation	Change in height	Average Flow at Elev. (top orifice only)	Combined Average Discharge	Pond Surface Area	Storage Volume	Time to Drain Unit at Current Flow
	[E]	[E ₁ - E ₂]	[See Eqn 1]	[q _{top} + q _{bot}]	A _{elev}	[A _{elev} × dH]	[V _{elev} / Q _{elev}]
	(ft)	H (ft)	q _{top} (cfs)	Q _{elev} (cfs)	(ft ²)	V _{elev} (ft ³)	T (hrs)
1	6.0	3.0	0.1615	0.2181	4256	1419	1.8
2	5.7	2.7	0.1522	0.2089	3996	1332	1.8
3	5.3	2.3	0.1424	0.1990	3744	1248	1.7
4	5.0	2.0	0.1318	0.1885	3500	1167	1.7
5	4.7	1.7	0.1203	0.1770	3264	1088	1.7
6	4.3	1.3	0.1076	0.1643	3036	1012	1.7
7	4.0	1.0	0.0932	0.1499	2816	939	1.7
8	3.7	0.7	0.0761	0.1328	2604	868	1.8
9	3.3	0.3	0.0538	0.1105	2400	800	2.0
10	3.0	0.0	0.0000	0.0567	2204	0	0.0
Subtotal Draw Down Time							16.0
Total Draw Down Time							48.0

APPENDIX D FLOW SPLITTER DESIGN SPECIFICATION

Flow splitters must be provided for off-line facilities to divert the SUSMP flow to the BMP and bypass higher flows. In most cases, it is a designer's choice whether stormwater treatment BMPs described in this manual are designed as on-line or off-line; an exception are filter strips and planter boxes which are always designed on-line.

A crucial factor in designing flow splitters is to ensure that low flows are delivered to the treatment facility up to the SUSMP flow rate. Above this rate, additional flows remain in the storm drain or are diverted to a bypass drain with minimal increase in head at the flow splitter structure to avoid surcharging the SUSMP facility under high flow conditions.

Flow splitters are typically manholes or vaults with weirs. In place of weirs, the splitter mechanism may be a half tee section with a solid top and an orifice in the bottom of the tee section. A full tee option may also be used (see "Design Criteria" below). Two possible design options for flow splitters are shown in Figures D1 and D2. Other equivalent designs that achieve the result of splitting low flows, up to the SUSMP design flow, into the treatment facility and divert higher flows around the facility are also acceptable.

Flow splitters may be modeled using standard level pool routing techniques, as described in the Handbook of Applied Hydrology (Chow, Ven Te, 1964) and elsewhere. The stage/discharge relationship of the outflow pipes should be determined using backwater analysis techniques. Orifices, if used, may be designed using the approach outlined in "Outlet Structure and Drawdown Time" in Chapter 2, Extended Detention Basins. Weirs should be analyzed as sharp-crested weirs.


Design Criteria

1. A flow splitter shall be designed to deliver the required SUSMP flow rate to the stormwater treatment facility.
2. The top of the weir shall be located at the water surface corresponding to the design flow. Higher flows enter the bypass line.
3. Capital storm flows to the treatment facility shall not increase the design SUSMP flow by more than 10%.
4. Example designs are shown in Figure D1 and Figure D2. Equivalent designs are also acceptable.
5. Special applications, such as roads, may require the use of a modified flow splitter. The weir wall may be fitted with a notch and adjustable weir plate to proportion runoff volumes other than high flows.
6. For ponding facilities, backwater effects must be included in designing the height of the standpipe in the manhole/vault (Option B).

7. Ladder or step and handhold access shall be provided. If the weir wall is higher than 36 inches, two ladders, on the either side of the wall, are required.

Material Requirements


1. The splitter baffle shall be installed in a standard manhole or vault. The baffle wall shall be made of material resistant to corrosion (minimum 4-inch thick reinforced concrete, Type 302 or Type 316 stainless steel plate, or equivalent).
2. The minimum clearance between the top of the weir wall and the bottom of the manhole or vault cover shall be 4 feet; otherwise, dual access points shall be provided.
3. All metal parts shall be corrosion resistant. Examples of preferred materials include aluminum, stainless steel, and plastic. Copper, zinc and galvanized materials are not permitted because of aquatic toxicity. Painting metal parts shall not be allowed because of poor longevity.



NOTES:

- ① INLET PIPE
- ② ADJUSTABLE WEIR PLATE
- ③ HIGH FLOW BYPASS PIPE;
SIZED FOR FLOOD CONTROL FLOWS
- ④ WEIR PLATE FRAME;
ANCHORED TO MANHOLE
- ⑤ PIPE TO WATER QUALITY FACILITY;
SIZED FOR WATER QUALITY FLOWS
- ⑥ ACCESS STEPS
- ⑦ 24" ROUND FRAME AND SOLID LID
- ⑧ 4' MIN DISTANCE OR PROVIDE SEPARATE
ACCESS ON BOTH SIDES OF WEIR

Figure D-1
FLOW SPLITTER- OPTION A



NOTES:

- ① INLET PIPE
- ② BYPASS STANDPIPE
- ③ BAFFLE TO CONTROL FLOATABLES
- ④ HIGH FLOW BYPASS PIPE;
SIZED FOR FLOOD CONTROL FLOWS
- ⑤ ACCESS STEPS
- ⑥ PIPE TO WATER QUALITY FACILITY
- ⑦ RISER PIPE; TOP OF PIPE AT DESIGN
ELEVATION FOR WATER QUALITY FLOWS
- ⑧ 24" ROUND FRAME AND SOLID LID
- ⑨ REMOVABLE "TEE" SECTION FOR CLEANOUT
- ⑩ RISER PIPE ORIFICE SIZED FOR WATER QUALITY FLOWS

Figure D-2
FLOW SPLITTER—OPTION B

APPENDIX E FACILITY INSPECTION

Introduction

To ensure high-quality, long-term performance, BMPs need to be inspected on a regular basis. These inspections help the stormwater manager monitor the safety, longevity, and effectiveness of these practices over time. BMP maintenance inspections are intended to do the following:

- Ensure the facilities are generally safe
- Maintain the proper stormwater management capacity and cost-effectiveness
- Comply with reporting to regulatory agencies
- Provide BMP tracking data
- Follow standard engineering practices

Inspection Types and Frequency

Inspection types range in detail from a low level (e.g., drive by) to a high level (e.g., rigorous professional inspection). Inspection frequency depends on many factors including the type of facility, accessibility to the public, likelihood of vandalism, and major storm events. Regular inspections include observations on general appearance, damage by water or vandalism, erosion, plant loss, trash and debris accumulation, standing water (where there shouldn't be), obvious (visual) loss of functionality, and vegetation condition. Such inspections should occur at:

- regular intervals for aesthetics, vegetation maintenance and checking for vandal damage,
- after large storms and at the end of the rainfall season for possible flow damage, and
- before winter storms to ensure the facility is properly prepared to handle the coming runoff events.

Annual or semi-annual inspections would include these and other more rigorous evaluations.

The instructions for operations and maintenance in this Manual include suggested inspection frequencies for each BMP type.

Procedures

Pre-Inspection Preparation

Prior to BMP inspection, the inspector(s) will have to gather a number of materials and equipment that fall under three categories:

Public Communications Materials

General educational materials as well as jurisdiction program and contact information may be used to help address questions or comments raised by inquisitive residential or commercial property owners encountered during the inspection.

BMP Background Information

Historical information on each BMP to be inspected will ease the inspection process and help to ensure that past maintenance or structural problems have been addressed. As-builts drawings are particularly helpful if available.

Inspection Checklists

Standard inspection checklists are used to record the condition of all facilities, and particularly those that need frequent maintenance. It will also be easier to track maintenance electronically, using either a database or spreadsheet, rather than relying on paper files.

Well-designed checklists can be integrated with these systems to prioritize maintenance, track performance over time, and relate design characteristics to particular problems. To effectively achieve these goals, the checklist should:

- Be quantitative, so that maintenance can be easily prioritized.
- Be very specific about possible problems to reduce subjectivity.
- Limit the use of text, particularly if integrated with a database.
- Link problems to specific actions.
- Where possible, track the function of the facility over time for future research and design.

Inspection checklists should also be grouped in the order the inspector would inspect the practice. For example, ponds should typically be inspected from downstream to upstream, so the investigation begins with the outfall channel. Checklists are presented in Appendix F.

Inspection Equipment

A range of equipment is necessary to perform a comprehensive, safe inspection of a facility. A list of the materials and equipment that could potentially accompany any inspector is presented in Table E-1 below. Actual equipment needed for inspection is determined by the type of facility being inspected and the level of detail of the inspection.

Table E-1: Inspection Equipment

BMP Inspection Equipment / Materials	Quantity	Required for
Public communications materials		
Jurisdiction permission letter (for 3rd party inspectors)	multiple	All BMPs
Jurisdiction contact list multiple	All	BMPs
BMP-Specific Information		
Blank inspection checklists	multiple	All BMPs
Site plans/as-built drawings	per facility	All BMPs
Facility type and outfall pipe size	per facility	All BMPs
Facility location	per facility	All BMPs
Previous inspection results (reports, redlines and photos)	per facility	All BMPs
Confined space entry permit (as needed)	per facility	Underground Confined Space Entry (CSE)

Inspection Equipment		
Clipboard w/forms, pencil and compass	1	All BMPs
Area map	1	All BMPs
Mobile telephone	1	All BMPs
Two-way radio w/charged batteries	2	All BMPs
100' measuring tape	1	All BMPs
25' retractable scale	1	All BMPs
Bolt cutters	1	All BMPs
Cans of orange spray paint	2	All BMPs
Crow bar	1	All BMPs
Digital camera	1	All BMPs
First aid kit	1	All BMPs
Flashlight w/charged batteries	1	All BMPs
Goggles or safety glasses	2	All BMPs
Hardhats	2	All BMPs
Leather gloves	2	All BMPs
Manhole cover tool / puller	1	All BMPs
Pair of hard sole boots (wear)	2	All BMPs
Pair of rubber boots (as-needed)	2	All BMPs
Roll of orange tie-off tape	1	All BMPs
Std. size bolt locks and keys (for gates)	2	All BMPs
Waterproof carrying bag	1	All BMPs
Machete or pruning sheers	1	Above ground
Monkey wrench	1	Above ground
Standard shovel	1	Above ground
Observation well cap wrenches	1/Size	Infiltration facilities only
Small size bolt lock and key (for well caps)	1	Infiltration facilities only
100' rope	1	Underground CSE
Air monitor/meter w/charged batteries	1	Underground CSE
Orange pylons/traffic cones	4	Underground CSE
Spot light	1	Underground CSE
5 minute air supply	1	Underground CSE
Full face respirator	1	Underground CSE
Recalibration kit	1	Underground CSE
Ventilation/forced air blower	1	Underground CSE

Pre-Inspection Notification

Inspection and maintenance of BMPs is often the responsibility of two separate entities. Since the local government is accountable for ensuring the region's stormwater management system is operating within State and Federal regulations, inspections are typically conducted by either government personnel or a private contractor under government authority. However, the duty of maintaining the site frequently falls to the hands of a private homeowner, homeowner association or commercial property owner. Communication between the local government and the BMP manager/owner is key to ensuring long-term and effective BMP operation.

All correspondence should provide detailed information about what the BMP manager/owner can expect. This will allow the BMP manager/owner to better understand and be prepared for the role he/she or the community plays during the entire process. Effective communication can eliminate unnecessary concerns and confusion on the part of the BMP owner and provide a

base for legal action for the enforcing agency. The greater the clarity, the smoother the process will be for all involved.

Prior to inspection, a Notification of Inspection Letter should be sent to the BMP manager/owner. An example of this letter is included in Appendix G. This letter serves several purposes:

1. Informs the manager that he/she should expect someone to be on their property.
2. Encourages routine maintenance to be performed.
3. Notifies the manager of any special pre-inspection actions that must be completed.
4. Secures the name of the person who oversees the maintenance of the BMP.

A Notification of Inspection Letter should include the basic information listed above, along with all of the following information:

Date of Future Inspection

This could either be a specific day or a period, such as a week, that the BMP manager/owner would expect a local government inspector to be on the property.

Request for current maintenance manager contact information

Finding this information ahead of time will save time later when trying to ensure the repairs are completed.

Special Instructions

For example, the BMP manager/owner may be responsible for pumping out and pressure washing underground facilities prior to inspection.

Outline of Inspection Process

Provide as much detail as possible, such as, "The inspection will be sometime in the morning during the second week in August by Inspector. Within 14 days of inspection, you will be notified of any repairs that are required. You will then have 30 days to fix any deficiencies..."

In summary, all correspondence should include the following basic information:

1. Facility address and BMP owner's address are both essential because it possible that the owner is in charge of multiple sites.
2. Facility identification number provides an internal reference for the inspecting unit and for BMP owners that may have more than one BMP at the same address.
3. BMP owner name and title. Since homeowners, homeowner associations, and property managers can change without notice it is critical to include both the name and title, such as "John Doe or Current Property Manager/Owner," to ensure the letter reaches the appropriate person.
4. Description of Authority tells the manager by which regulation/code the local government gains authority to inspect the site and require repairs.

5. Deadline by which a response or repair should be made.
6. Consequences if response or repairs are not made.
7. Contact information for the person to whom the manager/owner can speak for assistance.

Health and Safety

Safety is a critical element of any operations and maintenance plan. Potential hazards associated with operating and maintaining BMP facilities include physical hazards that may develop as a result of automobile traffic, inclement weather conditions, high flow conditions, and steep or difficult terrain; electrical/mechanical hazards from motorized-valves and controls, atmospheric hazards resulting from poor ventilation in confined spaces, and chemical hazards from materials that may be present in urban runoff or in products used to clean/maintain various equipment.

A Health and Safety Plan approved by the County's Health and Safety Coordinator should be reviewed by the all field personnel before inspections begin. All persons involved in inspections should be made aware of the hazards associated with inspection and should freely voice any concerns if potential hazards become apparent. The Occupational Safety and Health Administration (OSHA) provides regulations and guidance on occupational safety, many of which are directly applicable to the types of activities involved in inspection. It is the direct responsibility of each person involved in the inspection program to read the Health and Safety Plan and adhere to its requirements.

Operation and maintenance personnel are responsible for assessing the individual site conditions to identify possible hazards, selecting safety equipment, and implementing appropriate safety precautions. Under no circumstances should inspection and/or maintenance activities be conducted if there is a significant safety concern that cannot be adequately addressed.

The following list provides a few basic health and safety procedures that can help to create a safer sampling environment:

- Do not enter a confined space (e.g., StormFilter™ vault) without proper training, equipment, and surface support.
- Never remove or replace manhole covers with your bare hands or feet.
- Never leave an open manhole unattended.
- Do not start staging or sampling until traffic control has been established.
- Follow manufacturer's instructions when operating mechanical equipment.
- Standard precautions should be taken when operating electrical equipment due to the moist conditions that will prevail at many of the installations (e.g., outdoor equipment panels).

Maintenance operations will normally be conducted under dry conditions when the facility is more accessible and the potential for many physical hazards is low. However, inspection activities may be conducted during storm events to evaluate how the system is operating. When working near open water it is important to be aware of and avoid drowning hazards. High stormwater flows often carry branches and other debris that can entangle a person or pin them beneath submerged obstacles. Creek banks can be unstable or slippery during wet weather and caution should be observed when walking on wet unstable surfaces.

Problem Identification

Inspectors should clearly identify the extent and location of problems identified during inspection. In addition to clearly describing problem areas on the checklists, inspectors should help repair crews locate repairs both at the site and on design plans.

Immediate Concerns

While all maintenance and inspection items are important, some maintenance concerns actually pose an immediate safety concern. Many of these are caused by missing or damaged elements that would prevent access by the public. Examples include missing manhole covers or trash racks, missing or damaged fencing when that fence prevents access to a pond with steep side slopes, or a missing or damaged grate at a large inflow or outfall pipe. Another set of immediate pond and wetland repairs involve dam safety or flooding hazards. If a practice shows signs of embankment failure, or if an inspector is unsure, an appropriately qualified person or engineer should be called in to investigate the situation immediately. Similarly, cracks in a concrete riser that drains a large area may pose a dam safety threat.

As-built Drawings

The inspector should bring a copy of the as-built plan of the facility to mark potential corrections and problem areas on this plan. The marked up as-built plan should be stored either digitally or in a paper file system so that it can be brought out to confirm that maintenance was performed correctly on the follow-up inspection.

Photographs

Inspectors should take a core set of documentation photographs of practices being inspected. In addition, specific problem areas should be photo documented. A recommended set of core photographs include:

- Vehicle access points.
- Overview of the facility.
- Overview of principal intake structure.
- Inlet to facility and downstream outfall from facility.
- Emergency spillway (if applicable).

In addition, because of the large number of photographs that will likely be generated, a digital camera should be used to allow photographs to be stored electronically. (In advanced database programs, these photographs can be retrieved digitally). Finally, photographs should be named using a standard convention. The photograph name should indicate the practice identification number, feature (or problem) being photographed, and date of photograph.

Field Marking

Inspectors can highlight key areas of concern with spray paint or other marker. This is particularly useful for problems that may otherwise be difficult to find by others. Marking should be used as discretely as possible. For example, only dots sprayed at the base of trees should be used to mark limits of clearing for vegetation removal.

Post Inspection Follow Up and Maintenance Request Procedure

Once the BMP has been inspected, the BMP manager/owner should be informed of the BMP status and any repairs that need to be made through a Maintenance Notification Letter if privately owned, or through a Maintenance Request Order if the facility is maintained by the County. An example of the Maintenance Notification Letter is included in Appendix G. This letter should include the basic inspection information with the additional information below.

List of Repairs

This list should be detailed enough so it cannot be misinterpreted. For example, avoid ambiguous phrases such as "clear the bank." Instead, the list should specify "clear the bank of dead vegetation."

Outline of the Repair Process

This can expedite the repairs, particularly if the BMP manager/owner does not have previous experience with BMPs. In most cases it is worthwhile to suggest the use of a contractor to dissuade unqualified persons from performing the repairs. For example, "You will have 30 days to complete the repairs. The first step is to get bids from contractors. Next, your contractor should contact our inspector to discuss repairs. . ."

A facility inspection report should be attached for the BMP manager's/owner's records.

Educational material

Educational materials should also be attached to reinforce why properly maintaining BMPs is important not only for environmental reasons but also how good stormwater management serves their best interests.

Notification of Violation

In situations when a BMP manager/owner fails to comply with a Maintenance Notification Letter and/or other requests for compliance, a letter using strong language should be sent. These

notices are typically more formal than Maintenance Notification Letters and have a strong emphasis on the consequences if the manager/owner does not remedy the situation. Notices of Violation should include the basic information, plus:

1. Reference(s) to previous correspondence, which can provide a paper trail in cases when disagreement of roles arises.
2. List of repairs that should be detailed enough so it cannot be misinterpreted
3. List of violations the BMP manager/owner has accrued, including actions such as failing to comply with previous notices.

Copies of this letter may be sent to other agencies affected, e.g., such as those responsible for dam safety, etc. An example of this letter is included in Appendix G.

APPENDIX F FACILITY INSPECTION AND MAINTENANCE CHECKLIST

Included in this appendix are a series of checklists that can be used by both inspectors and maintenance personnel to ensure that observed deficiencies in BMPs are maintained appropriately. The checklists are ordered as follows:

1. Detention Basin Inspection/Maintenance Checklist
2. Vegetated Swale Inspection/Maintenance Checklist
3. Filter Strip Inspection/Maintenance Checklist
4. Bioretention Inspection/Maintenance Checklist
5. Planter Box Inspection/Maintenance Checklist
6. Infiltration Trench Inspection/Maintenance Checklist
7. Hydrodynamic Separation Device Inspection/Maintenance Checklist
8. Catch Basin Insert Inspection/Maintenance Checklist
9. Cartridge Media Filter Inspection/Maintenance Checklist

Extended Detention Basin Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0, 1 or 2)†	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
General				
Appearance	Untidy, un-mown (if applicable)			
Vegetation	Access problems or hazards; dead or dying trees			
	Poisonous or nuisance vegetation or noxious weeds			
Insects	Insects such as wasps and hornets interfere with maintenance activities.			
Rodent Holes	Any evidence of rodent holes if facility is acting as a dam or berm, or any evidence of water piping through dam or berm via rodent holes			
Trash and Debris	Trash and debris > 5 cf/1,000 sf (one standard size garbage can).			
Pollutants	Any evidence of oil, gasoline, contaminants or other pollutants			
Inlet/Outlet Pipe	Inlet/Outlet pipe clogged with sediment and/or debris. Basin not draining.			
Erosion	Erosion of the basin's side slopes and/or scouring of the basin bottom that exceeds 2-inches, or where continued erosion is prevalent.			
Piping	Evidence of or visible water flow through basin berm.			
Settlement of Basin Dike/Berm	Any part of these components that has settled 4-inches or lower than the design elevation, or inspector determines dike/berm is unsound.			
Overflow Spillway	Rock is missing and/or soil is exposed at top of spillway or outside slope.			
Sediment Accumulation in Basin Bottom	Sediment accumulations in basin bottom that exceeds the depth of sediment zone plus 6-inches.			
Tree or shrub growth	Trees > 4 ft in height with potential blockage of inlet, outlet or spillway; or potential future bank stability problems			
Debris Barriers (e.g., Trash Racks)				
Trash and Debris	Trash or debris that is plugging more than 20% of the openings in the barrier.			

†Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Defect	Conditions When Maintenance Is Needed	Inspection Result (0, 1 or 2)†	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
Damaged/ Missing Bars	Bars are bent out of shape more than 3 inches.			
	Bars are missing or entire barrier missing.			
	Bars are loose and rust is causing 50% deterioration to any part of barrier.			
Inlet/Outlet Pipe	Debris barrier missing or not attached to pipe.			
Fencing				
Missing or broken parts	Any defect in the fence that permits easy entry to a facility.			
Erosion	Erosion more than 4 inches high and 12-18 inches wide, creating an opening under the fence.			
Damaged Parts	Damage to gate/fence, posts out of plumb, or rails bent more than 6 inches.			
Deteriorating Paint or Protective Coating	Part or parts that have a rusting or scaling condition that has affected structural adequacy.			
Gates				
Damaged or missing member	Missing gate or locking devices, broken or missing hinges, out of plum more than 6 inches and more than 1 foot out of design alignment, or missing stretcher bar, stretcher bands, and ties.			

†Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Vegetated Swale Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0, 1, or 2)†	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
Appearance	Untidy			
Trash and Debris Accumulation	Trash and debris accumulated in the swale.			
Vegetation	When the grass becomes excessively tall (greater than 10-inches); when nuisance weeds and other vegetation start to take over.			
Excessive Shading	Vegetation growth is poor because sunlight does not reach swale. Evaluate vegetation suitability.			
Poor Vegetation Coverage	When vegetation is sparse or bare or eroded patches occur in more than 10% of the swale bottom. Evaluate vegetation suitability.			
Sediment Accumulation	Sediment depth exceeds 2 inches or covers more than 10% of design area.			
Standing Water	When water stands in the swale between storms and does not drain freely.			
Flow spreader or Check Dams	Flow spreader or check dams uneven or clogged so that flows are not uniformly distributed through entire swale width.			
Constant Baseflow	When small quantities of water continually flow through the swale, even when it has been dry for weeks and an eroded, muddy channel has formed in the swale bottom.			
Inlet/Outlet	Inlet/outlet areas clogged with sediment and/or debris.			
Erosion/ Scouring	Eroded or scoured swale bottom due to flow channelization, or higher flows. Eroded or rilled side slopes.			
	Eroded or undercut inlet/outlet structures			

†Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Filter Strip Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0, 1 or 2) [†]	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
Appearance	Untidy			
Trash and Debris Accumulation	Trash and debris accumulated on the filter strip.			
Vegetation	When the grass becomes excessively tall (greater than 10-inches); when nuisance weeds and other vegetation starts to take over.			
Excessive Shading	Grass growth is poor because sunlight does not reach swale. Evaluate grass species suitability.			
Poor Vegetation Coverage	When grass is sparse or bare or eroded patches occur in more than 10% of the swale bottom. Evaluate grass species suitability.			
Erosion/Scouring	Eroded or scoured areas due to flow channelization, or higher flows.			
Sediment Accumulation on Grass	Sediment depth exceeds 2 inches.			
Flow spreader	Flow spreader uneven or clogged so that flows are not uniformly distributed through entire filter width.			

[†]Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Bioretention Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0, 1, or 2) [†]	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
Appearance	Untidy			
Trash and Debris Accumulation	Trash, plant litter and dead leaves accumulated on surface.			
Vegetation	Unhealthy plants and appearance.			
Irrigation	Functioning incorrectly (if applicable).			
Inlet	Inlet pipe blocked or impeded.			
Splash Blocks	Blocks or pads correctly positioned to prevent erosion.			
Overflow	Overflow pipe blocked or broken.			
Filter media	Infiltration design rate is met (e.g., drains 36-48 hours after moderate - large storm event).			

[†]Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Planter Box Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0, 1, or 2) [†]	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
Appearance	Untidy			
Trash and Debris Accumulation	Trash, plant litter and dead leaves accumulated on surface.			
Vegetation	Unhealthy plants and appearance.			
	Vegetation interfering with planter operations.			
Irrigation	Functioning incorrectly (if applicable).			
Plant box	Structural defects, holes and gaps.			
Inlet	Inlet pipe blocked or impeded.			
Splash Blocks	Blocks or pads correctly positioned to prevent erosion.			
Overflow	Overflow pipe blocked or broken.			
Filter media	Infiltration design rate is met (e.g., drains 3-4 hours after moderate - large storm event).			

[†]Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Infiltration Trench Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0,1, or 2) [†]	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
Appearance, vegetative health	Mowing and trimming vegetation is needed to prevent establishment of woody vegetation, and for aesthetic and vector reasons.			
Vegetation	Poisonous or nuisance vegetation or noxious weeds.			
	Excessive loss of turf or ground cover (if applicable).			
Trash & Debris	Trash and debris > 5 cf/1,000 sf (one standard size garbage can).			
Contaminants and Pollution	Any evidence of oil, gasoline, contaminants or other pollutants.			
Erosion	Undercut or eroded areas at inlet or outlet structures.			
Sediment and Debris	Accumulation of sediment, debris, and oil/grease on surface, inflow, outlet or overflow structures.			
Sediment and Debris	Accumulation of sediment and debris, in sediment forebay and pretreatment devices.			
Water drainage rate	Standing water, or by visual inspection of wells (if available), indicates design drain times are not being achieved (i.e., within 72 hours).			
Media clogging surface layer	Lift surface layer (and filter fabric if installed) and check for media clogging with sediment (function may be able to be restored by replacing surface aggregate/filter cloth).			
Media clogging	Lift surface layer (and filter fabric if installed) and check for media clogging with sediment (partial or complete clogging which may require full replacement).			

[†]Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Hydrodynamic Device Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0, 1 or 2) [†]	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
Refer to the manufacturer's instructions for maintenance/inspection requirements, below are generic guidelines to supplement manufacturer's recommendations.				
General				
Trash and Debris Accumulation	Trash or debris is blocking inletting capacity of the facility by more than 10%.			
Trash and Debris Sediment Accumulation	Trash, debris and sediment have reached the unit's capacity			
Unit Cover				
Cover Not in Place	Cover is missing or only partially in place.			
Locking Mechanism Not Working	Mechanism cannot be opened by one maintenance person with proper tools. Bolts into frame have less than 1/2 inch of thread.			
Cover Difficult to Remove	One maintenance person cannot remove lid after applying normal lifting pressure. (Intent is to keep cover from sealing off access to maintenance.)			

[†]Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Catchbasin Insert Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Date: _____ Work Order # _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0,1, or 2) [†]	Date Maintenance Performed	Comments or Action(s) Taken to Resolve Issue
Refer to the manufacturer's instructions for maintenance/inspection requirements, below are generic guidelines to supplement manufacturer's recommendations.				
Sediment Accumulation	When sediment forms a cap over the insert media of the insert and/or unit.			
Trash and Debris Accumulation	Trash and debris accumulates on insert unit creating a blockage or restriction.			
Media Insert Use Beyond Normal Product Life	Media has been used beyond the typical average life of media insert product.			
Hydrocarbon removal type				
Media Insert Not Removing Oil	Effluent water from media insert has a visible sheen.			
Media Insert Water Saturated	Catch basin insert is saturated with water and no longer has the capacity to absorb.			
Media Insert-Oil Saturated	Media oil saturated due to petroleum spill that drains into catch basin.			

[†]Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Filter Cartridge Inspection and Maintenance Checklist

Date: _____ Work Order # _____

Type of Inspection: ☐ post-storm ☐ annual ☐ routine ☐ post-wet season ☐ pre-wet season

Facility: _____ Inspector(s): _____

Defect	Conditions When Maintenance Is Needed	Inspection Result (0,1, or 2) [†]	Date Maintenance Performed	Comments or Action(s) taken to resolve issue
Refer to the manufacturer's instructions for maintenance/inspection requirements, below are generic guidelines to supplement manufacturer's recommendations.				
Underground Vault				
Sediment Accumulation on Media	Sediment depth exceeds 0.25-inches.			
Sediment Accumulation in Vault	Sediment depth exceeds 6-inches in first chamber.			
Trash/Debris Accumulation	Trash and debris accumulated on compost filter bed.			
Sediment in Drain Pipes or Cleanouts	When drain pipes, clean-outs, become full with sediment and/or debris.			
Damaged Pipes	Any part of the pipes that are crushed or damaged due to corrosion and/or settlement.			
Access Cover Damaged/Not Working	Cover cannot be opened; one person cannot open the cover using normal lifting pressure, corrosion/deformation of cover.			

[†]Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

Defect	Conditions When Maintenance Is Needed	Inspection Result (0,1, or 2) [†]	Date Maintenance Performed	Comments or Action(s) taken to resolve issue
Vault Structure Includes Cracks in Wall, Bottom, Damage to Frame and/or Top Slab	Cracks wider than 1/2-inch or evidence of soil particles entering the structure through the cracks, or maintenance/inspection personnel determine that the vault is not structurally sound.			
	Cracks wider than 1/2-inch at the joint of any inlet/outlet pipe or evidence of soil particles entering through the cracks.			
Baffles	Baffles corroding, cracking warping, and/or showing signs of failure as determined by maintenance/inspection person.			
Access Ladder Damaged	Ladder is corroded or deteriorated, not functioning properly, not securely attached to structure wall, missing rungs, cracks, or misaligned.			
Below Ground Cartridge Type				
Filter Media	Drawdown of water through the media takes longer than 1 hour and/or overflow occurs frequently.			
Short Circuiting	Flows do not properly enter filter cartridges.			

[†]Maintenance: Enter 0 if satisfactory, 1 if maintenance is needed and include WO#. Enter 2 if maintenance was performed same day.

APPENDIX G POLICY FOR NEW PERCOLATION BASIN TESTING, DESIGN, AND MAINTENANCE

Approved Donald L. Wolfe
DDE Donald L. Wolfe

October 10, 2007

TO: Tom Hoagland
Deputy Director

FROM: Dennis Hunter *DH*
Land Development Division *TWH*

**MAPP GOAL NO. 4—FISCAL YEAR 2006-07
POLICY FOR NEW PERCOLATION BASIN TESTING, DESIGN, AND MAINTENANCE**

Recommendation

Approve the testing, design, and maintenance procedures as outlined in the following attachments for percolation basins that are constructed as part of private development projects.

Background

On October 28, 1980, the Board of Supervisors adopted the Interim Drainage Policy for Quartz Hill, which included mitigation for increased runoff from proposed developments (portions included in Appendix). One mitigation measure mentioned in this policy is percolation basins that would detain the increased runoff caused by a development that may adversely affect downstream areas. Due to increased development in Acton, Antelope Valley, and other areas that lack adequate drainage conveyances and outlets, developers are utilizing percolation basins as their method of mitigation. The Interim Drainage Policy for Quartz Hill also required these basins to be designed to the County Engineer's requirements. However, Public Works' lack of minimum requirements resulted in nonstandardized testing methodologies and design procedures that provided less than satisfactory results (Photos 1 and 2).

This policy will identify minimum requirements and, therefore, allow development to occur that is free of flood hazard while not significantly exacerbating flooding conditions to adjacent properties. If the site soils are such that an onsite basin cannot be designed to ensure that it is empty within seven (7) days, Public Works will require an offsite storm drain to convey flows to a more suitable offsite basin location. The applicant will be required to obtain all easements prior to Tentative Map approval.

Discussion

A panel consisting of representatives from Land Development, Geotechnical and Materials Engineering, Flood Maintenance, and Road Maintenance Divisions was assembled to develop standardized testing, design, and maintenance procedures. The current procedures were revisited and it was determined that traditional percolation

Tom Hoagland
October 10, 2007
Page 2

testing fails to account for the long-term saturation of the basins. It was also determined that the maintenance procedures recommended by the various private consultants resulted in the need for various filter fabrics and mechanical devices to remove accumulated sediments. In addition to establishing testing, design, and maintenance standards the panel also formalized the roles and areas of responsibility for the various divisions involved.

A presentation and draft version of the policy was distributed at the August 14, 2007, Land Development Advisory Committee meeting. A few questions were asked and answered, but no comments were received that warranted any revision to the policy.

RGD:la

P:\ldpub\ADMIN\DENNIS\GOALS\2006-07\MAPP GOAL NO 4 (BASIN TESTING, DESIGN, & MAINT.).doc

Attach.

cc: Geotechnical and Materials Engineering (Kelley, Montgomery)
Flood Maintenance (Lee, Hildebrand)
Road Maintenance (Lehman, Caddick)

ATTACHMENT 1

PERCOLATION BASIN TESTING PROCEDURE

Pretesting Preparation:

- Drill at least one boring to a minimum depth of 30 feet below the planned bottom of each proposed percolation basin. Additional borings must be performed in the area to establish continuity of subsurface materials. Each exploratory boring must be logged by a certified Engineering Geologist or Soils Engineer by either downhole logging or via samples obtained through the use of a continuous sampler.
- Create an excavation bottoming at the invert of the proposed basin. The consultant shall test a limited area through the use of an open-ended standpipe. The standpipe must be a minimum of 5 feet in diameter. The outer edge of the standpipe must be sealed in order to eliminate water loss from around the base.
- Presaturate the excavation, via the standpipe, for at least one week prior to performing testing. Maintain a constant head of at least 18 inches of water in the standpipe at all times during the presoak period.

Testing:

- Perform percolation testing using sediment-laden water. A minimum sediment load of 1000 Nephelometric Turbidity Units (NTU) is required. Sediment loading must be carried out by directly adding sediment to the standpipe based upon water usage and the amount of load required to produce the required NTU. This must be accomplished on a daily basis. The sediment shall be collected from a nearby source area and shall be screened to reflect the anticipated sediment load grain size distribution. Maintain a constant 18 inches of head in the standpipe and record usage utilizing a continuous data logger.
- Once the usage stabilizes, continue testing for a minimum of two weeks. Stabilization is defined as when the slope of the mean trend line of the readings is less than 2 percent, when graphing the time (days) vs. percolation rate (in/hr).

Retesting:

- Allow sediment water to percolate completely and perform the recommended annual maintenance procedures recommended by the Soils Engineer and in accordance with Attachment 3 on the test area.
- Perform a retest utilizing the same methodology as described in the testing above, once maintenance has been performed.

Post-Testing:

- Based on the results of testing, the consultant must recommend a long-term percolation rate (in inches per day) to be utilized in the design of the percolation basin. The recommendation shall not exceed the result of the retest utilizing maintenance.
- Prepare and submit a report, which discusses the testing procedures, includes conclusions, and provides recommendations for maintenance.

Additional Notes:

- Land Development Division must be notified at least three (3) working days prior to initiation of testing.
- Basins will not be approved in areas that will receive fill during grading operations.
- Land Development Division will be responsible for requesting testing of proposed percolation basins and acceptance of the recommended percolation rate.
- Geotechnical and Materials Engineering Division will be responsible for the review of the testing procedures and design parameters.
- Flood Maintenance Division will be responsible for the operation and maintenance of the basin upon transfer to the Flood Control District.
- Percolation basins must percolate completely within seven days.

ATTACHMENT 2

PERCOLATION BASIN DESIGN PARAMETERS

- The basin will be required to be completely in native material. The basin may not be constructed in compacted fill.
- The sides of the basin must be at 3:1 gradient or flatter.
- The basin shall not be planted.
- The basin shall be designed to have pretreatment facilities, such as a filter strip or grass swale, to aid in the removal of suspended particulate pollutants
- Concrete access road to the bottom of the basin is required. The section of this access road is 12-foot-wide, 6-inch Portland Cement Concrete on 4-inch Crushed Miscellaneous Base, and not steeper than 12 percent grade.
- Monumentation for cleanouts will be required. This can be pipe-markers at all four corners of the basin.
- Discharge of nuisance flow from the development into the basin must be minimized. This should be done by designing the project so that nuisance flows minimally occur (i.e., smart irrigation, etc).
- The basin must be designed in a manner that will not accept any natural drainage, only the differential runoff from the proposed development.
- The basin must be designed with a drain valve to release the water in emergency situations.
- The location of the basin will be per the Soils Engineer's recommendation.
- A Drainage Benefit Assessment Area (DBAA), or similar, will be required to be setup by the developer to finance the maintenance of these basins.
- The Geotechnical Engineer shall address the potential for hydroconsolidation and slope instability associated with the impoundment of water within the basin.

ATTACHMENT 3

PERCOLATION BASIN MAINTENANCE PROCEDURE

- Maintenance should consist of either periodic physical removal of accumulated silt or periodic spading of the soil on an annual basis before each storm season or sooner if recommended by the Geotechnical Engineer. Spading of soil should be done annually, in order to limit growth of vegetation in the basin.
- With either method, care should be taken to avoid smearing of the absorption layer.
- If physical removal is utilized, the absorption layer should be scarified after removal of silt.
- If spading is utilized, a device such as the Tortella Spader should be utilized in lieu of conventional rototilling or disking, which tend to smear at the blade-soil interface.
- Organic material should be spaded into the soil to improve soil structure.
- The maintenance interval will be determined by the consultant's recommendation utilizing both volume of flow as well as water quality in the basin (spading should be done annually, prior to the start of the rainy season).

PHOTOGRAPHS



PHOTO 1 – Existing Percolation Basin in Antelope Valley



PHOTO 2–Existing Percolation Basin in Antelope Valley



PHOTO 3–Test Basin Excavation



PHOTO 4–Five Foot Diameter Stand Pipe

APPENDIX

DEPARTMENT OF PUBLIC WORKS

M E M O R A N D U M

TO: Carl L. Blum
Assistant Deputy Director

October 24, 1986

FROM: Rod Kubomoto
Drainage & Grading Section

ANTELOPE VALLEY INTERIM DRAINAGE POLICY

Recommendation

Approve the attached interim drainage policies and design criteria and standards for implementation in the Antelope Valley.

Discussion

Interim drainage policies for the Antelope Valley are a practical approach to flood hazard mitigation until regional drainage improvements are installed. In lieu of a moratorium on new construction, the Board of Supervisors adopted an interim drainage policy on October 28, 1980 for the Quartz Hill area (see attached copy). This was necessary due to an increase in development proposals in this area which lacks drainage conveyances and adequate outlets. The desert topography, coupled with the lack of well defined drainage courses and existing improvements affecting flow patterns, compounded the problem. Regional drainage improvements will ultimately alleviate the unmet drainage needs. However, in the interim, the main concern was and is today to allow development to occur that is free of flood hazard while not significantly worsening flooding conditions to adjacent properties. The Quartz Hill policy essentially provided this goal by collecting and percolating the increased run-off due to development and requiring elevated building pads above the anticipated flood level. Development continues to increase throughout the Antelope Valley and similar drainage problems are now being experienced. The Quartz Hill drainage policy is a reasonable compromise for the entire valley floor until regional facilities are installed. Attached are guidelines relative to reviewing and imposing requirements at tentative map processing and design criteria and standards for proposed County maintained drainage facilities. Approval of the recommendation will assist staff in regulating reasonable flood plain management for this area and improve section plan review consistency.

ANTELOPE VALLEY MASTER DRAINAGE PLAN FEES

In order to provide a source of funding for regional drainage improvements, the Department has adopted drainage fee requirements for all new land divisions.

The requirements are as follows:

\$ 2,000 per lot for single family residential

\$10,000 per acre for commercial, manufacturing, or industrial

\$1,000 per multi-dwelling unit (condo and apartments)

\$10,000 per acre for mobile home parks (conditioned at time of CUP review)

These fees are currently waived for conditional certificates of compliance and building permits. Lots within a proposed land division with existing dwellings or other permitted main use are also exempt from the fees.

The developers must enter into an agreement with the County and provide adequate surety for the fees when (a) they apply for occupancy, or (b) the County has identified projects for construction which will use this money. Based on current construction scheduling of regional facilities, the fees shall be collected prior to land division recordation. The submission of appropriate security shall be in accordance with Government Code Section 66499 and approved by the County. Two signed originals of the agreement are required and the surety shall be in the form of cashiers check, letter of credit, or letter of assignment. Due to the lengthy process to exonerate bonds, the Division does not prefer this form of surety for fees. It is intended that the Antelope Valley Master Plan of Drainage Facilities be built as soon as funds become available. However, if the funds are not used for construction within 7 years, the funds, if collected, will be returned to the applicant.

DRAINAGE BENEFIT ASSESSMENT AREAS (DBAA)

Proposed County-maintained facilities outside of the Flood Control District boundaries require maintenance provisions in the form of drainage benefit assessment area administered by the County and funded by lot owner assessments. The formation of the assessment area is coordinated through the Planning Division. Due to the relatively long process to legally form the assessment area, the developer may elect to enter into an agreement with the County. This would allow him to record the land division prior to assessment formation provided that no lots change ownership (see attached copy).

The following data must be submitted to the County to begin processing the assessment:

1. \$3,000 processing fee
2. Land division map
3. Copy of the private drain plans
4. Benefited are indentified
5. Anticipated annual maintenance cost
6. O & M manual for multi-use flood recreational type facilities
7. Agreement

DETAILED PROCEDURES ARE OUTLINED PER SEPARATE MEMORANDUM (SEE ATTACHED DRAFT COPY).

TENTATIVE MAP REQUIREMENTS

Tentative map reviews are to be evaluated per current guidelines and procedures consistent with the Subdivision Ordinance. However, the added conditions are:

Assessment of required master drainage plan fees.

2. Formation of a benefit assessment district to fund the maintenance of drainage improvements (P.D.) if the site is located north of Avenue "S", Township 5 North (Outside Flood Control District boundaries).
3. Execution of the necessary agreements for master plan fees and DBAA formation and deposits prior to land division recordation.
4. Dedication of right of ways indentified on the Antelope Valley master drainage plan. Market value of the right of way can be used to offset the drainage fees. Construction in "planned flow paths" will be restricted but right of way will not be dedicated to County.

DRAINAGE CONCEPTS

Review of drainage concepts are to be consistent with current requirements and guidelines. However, four key issues should be acknowledged by the consulting engineer to avoid future complications and possible significant expenditures.

1. A maximum of seven day soil percolation rate for delta-volume and/or full retention basins. A soils report should be submitted for soil section review.
2. Drainage solutions that not only mitigate the flood hazard to lots but are compatible with street safety drainage requirements (refer to Road Sewer and Water Section).
3. Location and approximate sizing of the percolation basin.
4. Need for drainage acceptance letters from affected adjacent property owners.

DESIGN CRITERIA

The interim drainage provisions for the valley floor require subdivisions to limit drainage outflow to the before developed condition quantities. This would include not only the change in peak Q but also the volume due to the incremental decrease in permeability associated with development. Facilities therefore must detain the change in peak Q and percolate the change in volume to satisfy the interim policy. Percolation basins are the preferred design concept. However, due to site topography, public opposition, and field design parameters, several design options may be considered acceptable.

1. Allow contributory drainage to flow essentially through the development and detain the peak Delta Q and percolate the Delta volume. Return discharge of flows to the predevelopment condition or obtain drainage release letters from all affected properties.
2. Allow contributory drainage to be collected into the basin with the developmental increase and regulate outflow to the before-development Q while still percolating the Delta volume. Return discharge of flows to the before-developed condition or obtain drainage release letters.
3. Allow only detention of the peak Delta Q provided there is a reasonable adequate outlet and drainage release letters obtained from all affected properties.
4. Provide full retention and percolation of flows.

Each site must be evaluated on a case-by-case basis and drainage release letters may be mandatory due to the particular circumstances. Existing public roads maintained by the County may be considered as acceptable drainage outlets provided Departmental approval is obtained.

Interior street patterns should be designed to accommodate existing drainage patterns and street sump conditions should be avoided. Local streets can be utilized to convey storm flows provided it complies with street safety drainage requirements (refer to Road Sewer & Water Section).

PERCOLATION BASINS

A. HYDROLOGIC CRITERIA

Basins are to be sized on a 25-year rainfall frequency, 4th day only, storm event plus one foot of freeboard. The volume analysis is deemed acceptable due to physical conditions that indicate that the area experiences high-intensity, short-duration (thundershower) storm events. Updated methodology and hydrologic criteria are being evaluated by Hydraulic and Water Conservation Division. Analysis procedures and updated data will be incorporated upon Department policy and implementation approval.

B. GENERAL DESIGN STANDARDS

Provide adequate energy dissipation for inflows to prevent scour and erosion of the basin invert and side slopes.

Provide standard protection barriers and trash racks for inlets and outlets.

Provide a secondary overflow path (i.e., access road) to a paved public street as an auxiliary spillway.

Outflow lines (except true detention type basins) are to be elevated a minimum of one foot above the basin invert.

The basin floor is to be graded to drain away from the outflow line (1% typical). This is to be minimize basin maintenance by isolating and concentrating summer low flows.

No seepage pits in the basin floor to mitigate nuisance flows will be allowed due to their high maintenance and lack of reliability.

C. STRUCTURAL CRITERIA

Soils report should be submitted that addresses slope stability, effects of rapid drawdown, infiltration, potential seepage, and possible effects such as land settlement or increased lateral infiltration and groundwater recharges.

Provide maximum 3:1 side slopes unless the soils report can verify stability at steeper slopes.

Basins utilizing walls as a means of retaining water must be reinforced concrete and structurally designed for hydrostatic pressures.

D. ACCESS AND FENCING

Provide security fencing and a double drive gate per Standard Drawing No. 2-D 178 or provide Department approved blockwalls (Min. height of 5 feet).

Provide a 12-foot wide minimum concrete access ramp to the bottom of the basin. Maximum grade into the basin shall be 12 percent.

Provide a 5-foot setback from the fence line or wall to the top of the basin slope along the basin perimeter adjacent public streets.

Provide an 8-foot setback from the fence line or wall to the top of the basin slope along the basin perimeter adjacent private lots. Lesser setbacks must be approved by the Department's Soil Unit and Operation and Maintenance Division.

RIGHTS OF WAY

The rights of way shall be shown and properly labeled on the plans. Basin facilities located outside the Flood Control District boundaries shall have easements dedicated to the County of Los Angeles for Flood Control purposes. Basins within the District boundaries are to be dedicated to Los Angeles County Flood Control District for flood control purposes. Rights of way in fee simple is required for facilities within future right of way needs per the Antelope Valley Master Drainage Plan. Planned flow paths are to be considered flood hazard areas.

INTERIM STANDARDS FOR PERCOLATION BASINS

1. The basin capacity shall be the difference in volume of runoff between the undeveloped subdivision and the developed conditions for the fourth storm day using the modified rational method.
2. The basin's side slopes shall not exceed one foot vertical to four feet horizontal with a depth of ponding no greater than 2.5 feet. *FOR MULTI-USE RECREATIONAL PROPOSALS*
3. The development shall be designed to direct nuisance water to the basin.
4. Basins must be designed to totally percolate drainage within a seven day time interval after storms. Percolation tests will have to be provided and approved by County Engineer. A controlled discharge outlet will have to be designed if soil conditions do not allow adequate percolation.
5. The basin design should be such that it does not adversely affect the aesthetics of the area and all efforts should be made to preserve significant natural plants and trees.
6. The subdivider shall establish a homeowners association for the maintenance for all drainage facilities other than those accepted for maintenance by the County. *DBAA*

COUNTY ENGINEER-FACILITIES

ATTN: Pete Spancer

*File
Quartz Hill
Drainage*

MOTION BY SUPERVISOR BAXTER WARD

October 28, 1980

Recommendation of Supervisor Ward for Interim Drainage
Policy for Quartz Hill, as suggested by North County Citizens
Planning Council.

ADOPTED
BOARD OF SUPERVISORS
COUNTY OF LOS ANGELES

4

OCT 28 1980

James S. Mize

JAMES S. MIZE
EXECUTIVE OFFICER

MOTION BY SUPERVISOR BAXTER WARD

October 28, 1980

The Quartz Hill area of Antelope Valley is located on a relatively flat gently sloping plain which can be identified with the large alluvial plains found at the bases of most mountain ranges. Typically, storm runoff over these areas take the form of sheet flow with few defined drainage courses. In recent years, however, the area has begun to develop into a residential community at an increasing pace with a corresponding increase in the total runoff. This runoff has been confined to unimproved shallow drainage paths or concentrated and channelized in the streets. These streets, particularly in the northsouth direction, have insufficient capacity to contain this runoff and adjacent properties have been subject to flooding. The area also has many unimproved dirt streets that not only erode in storm flow, but could become a problem with a constant flow of nuisance water crossing from new developments upstream.

The area has limited topographic data and the extent of the flood hazard area is difficult to determine as the terrain gradually flattens toward the valley. The area needs a comprehensive study outlining the problem areas and suggesting solutions. An interim policy must be established to allow development to continue until a detailed master plan for drainage is completed.

The proposed interim policy incorporates many of the recommendations by the North County Citizens Planning Council as presented in its letter dated September 18, 1980, to our Honorable Board.

THEREFORE, I MOVE THAT THIS BOARD:

1. Establish the attached interim policy for drainage of new development in the Quartz Hill area.
2. Instruct the County Engineer to determine the extent of the flood hazard and prepare permanent policy and master plan for drainage in the Quartz Hill area.

INTERIM DRAINAGE POLICY FOR
QUARTZ HILL AREA

Development will be permitted outside the flood plain.

Developments within the flood plain may be allowed if the street design and development layout do not alter the natural drainage patterns or adversely affect adjacent property. Floodways or flood protection areas must be provided for the passage of storm waters.

Fully improved roads may be used for routing storm water runoff. When the design storm exceeds the carrying capacity of the street, in new developments, floodways, or flood protection district shall be established.

When it is determined by the County Engineer that the development will have a significant increase in runoff and that this increase will adversely affect downstream developed areas, percolation basins may be required to detain the increased runoff caused by the development. Requirements for these basins shall be established by the County Engineer.

PROCEDURES FOR DBAA MAINTENANCE AND TRANSFER

During the past few years, the Land Development Division has been requiring measures be taken to provide for drainage in the Antelope Valley by on-site detention or retention of increased storm water developed by the new subdivisions. The method used has been minimal storm drain systems which outlet into a basin. These basins are designated to accept that portion of runoff attributed to increased development. This policy was adopted by the Board of Supervisors on October 28, 1980, as an interim policy for the Quartz Hill area of the North County. Since all of the Antelope Valley has similar drainage concerns in areas other than Quartz Hill, the policy has been expanded to include subdivisions throughout most of the Valley.

There have been several subdivisions with requirements to install percolation basins to provide for drainage. The developers have also been required to form a drainage district to maintain these systems since those formed are not within the Los Angeles County Flood Control District boundary. These districts are composed of the properties within a subdivision and are formed under a benefit assessment area with money to be collected with the individual tax bills. Maintenance is the developer's obligation until these facilities have been accepted by the County. Additionally, DBAAs are being formed for subsurface drainage systems to collect water in geological problem areas. These systems, called hydraugers, are located near Valencia.

Procedures are as follows:

The Land Development Division, as part of the subdivision requirements, shall process the plans, collect bonds, help establish the BAA and determine when the work is complete. When the work is complete, the Land Development Division shall recommend acceptance of the work and provide Planning Division with the information necessary to set up a procedure so that maintenance may commence.

Among necessary procedures are the following:

1. Set up fiscal collections from the Auditor-Controller.
2. Recommend yearly adjustments of collections to the Board of Supervisors.
3. Develop standards and specifications of maintenance or modify those submitted.
4. Monitor facilities.
5. Develop maintenance schedule.
6. Develop a disbursal program in conjunction with Business and Finance Division.
7. Development of work contracting.

Business and Finance Division

1. Establish recordkeeping procedure for collections and disbursal of funds.

Flood Maintenance Division

1. Receive work assignment from Planning Division including:
 - a. Copy of BAA Ordinance
 - b. DBAA document
 - c. Subdivision map
 - d. Construction plans
 - e. Operation and maintenance manual or specifications (as required)
2. Create work order.
3. Recordkeeping, function, time and cost.
4. Service contract development.
5. August budget estimate to Planning Division (each year).

Construction Division

1. Provide ongoing inspection during construction.
2. Provide final inspection prior to acceptance of construction.

The Drainage Benefit Assessment Area listing is attached.

KCM:acm
(8.1/3)

Land Development Division

1. Identify drainage needs on tentative map conditions.
2. Review construction plans.
3. Send construction plans to Flood Maintenance Division for review and maintenance estimate.
4. Collect deposit for DBAA formation.
5. Send material for DBAA formation to Planning Division.
6. Approve construction plans.
7. Construction inspection by Construction Division.
8. Notify Planning Division of completion of construction when Board of Supervisors' letter is prepared.
9. Recommend acceptance of completed construction by letter to Board of Supervisors after maintenance tax is collected.
10. Transfer maintenance "package" to Planning Division.

Planning Division

1. Accept DBAA formation material
 - a. Job number access (\$3,000.00+)
 - b. Subdivision map
 - c. Copy of private drain plans
 - d. Benefited area boundary
 - e. Maintenance cost estimate
 - f. Operation and maintenance manual (as required)
2. Prepare report, EIR, Resolution Instituting Proceedings, and Notice of Hearing and Filing.
3. File necessary documents with Board of Supervisors.
4. Post Notice of Hearing and Filing.
5. Submit notification affidavits.
6. Prepare resolution determining assessments and submittal to voters.
7. File resolution determining assessment with Board.
8. Notify Land Development Division when DBAA is formed.
9. Accept transfer package from Land Development Division including:
 - a. Copy of BAA Ordinance
 - b. DBAA document
 - c. Subdivision map and assessment roll
 - d. Construction plans
 - e. Operation and maintenance manuals or specifications (as required)
10. Records for each area.
11. Notices to Business and Finance Division.
12. Assign work and disbursements to Flood Maintenance Division.
13. Budgets each August for Board of Supervisors' approval.

DEPARTMENT OF PUBLIC WORKS

M E M O R A N D U M

TO: Mike Nagao
Planning Division

September 5, 1986

FROM: Carl L. Blum
Land Development Division

File No. 2-15.40
Transfer of Storm Drain Systems
Drainage Benefit Assessment Area No. _____
Private Drain No. _____

For your information, the above-referenced Retention/Detention Basin and Storm Drain System has been transferred to the District for operation and maintenance.

Date of Board of Supervisors' approval:

Date of Board Letter: _____ (copy attached)

Supervisory District: 5

Designed by:

Basin Capacity: _____ acre feet.

Main Line Storm Drain Length: _____ feet more or less

Area:

Thomas Guide: _____ page

Quad Sheet:

Operation and Maintenance Area: Hansen Yard

Rod H. Kubomoto
Head, Drainage and Grading Section

RHK:amc

Attachment

bc: Contract Administration Division, Operation and Maintenance (2), (Hansen Yard), Property Management (Permits), Land Development (D&G), Secretary of Nomenclature Committee, General Files.

DRAINAGE BENEFIT ASSESSMENT AREA

<u>No.</u>	<u>Name</u>	<u>Location</u>	<u>Type of Maintenance</u>	<u>Constructed</u>
1	Tract 38994 P.D. 1706	Avenue L-8 Street West	Sump/Landscape	20% Constructed Formed
2	Big Rock Mesa	Malibu	Hydraugers	No Construction Not Formed
3	Tract 36496	Canyon Country	Hydraugers	Construction completed-Formed
4	Tract 30114 P.D. 1248	Elizabeth Lake	Storm Drain	No Construction Formed
5	Tract 36395 P.D. 1853	Avenue M-8 and 60th Street West	Sump	Construction completed-Formed
6	Tract 43528	Canyon Country (Sierra Highway)	Hydraugers	Formed
7	P.M. 13213 P.D. 1809	Avenue M and 10th Street West	Dry S.D.	85% Constructed Voted
8	Tract 43545 P.D. 1937	Avenue K and 45th Street (W.)	Sump	No Construction Not Formed
9	Tract 44330	Quartz Hill	Sump	Formed
10	Tracts 36875 & 43087/P.D. 1990	Avenue R-12 and 47 Street E.	Sump	Abandoned
11	Tract 44370 P.D. 1980	Division Street and Avenue R-8	Detention Basin	Not Formed
12	Calle Del Barco	Malibu	Hydraugers	Voted
13	Tracts 43708, 44440, 44441, and 44442	40th Street W. and Avenue L-8	Sump	Not Formed



THOMAS A. TIDEMANSON, Director
CECIL E. BUGH, Chief Deputy Director
MAS NAGAMI, Assistant Director

COUNTY OF LOS ANGELES

DEPARTMENT OF PUBLIC WORKS

900 SOUTH FREMONT AVENUE
ALHAMBRA, CALIFORNIA 91803-1331
Telephone: (818) 458-5100

ADDRESS ALL CORRESPONDENCE TO:
P.O. BOX 1460
ALHAMBRA, CALIFORNIA 91802-1460

IN REPLY PLEASE
REFER TO FILE:

October 25, 1989

TO: Land Development Advisory
Committee Members

FROM: Donald L. Wolfe 
Assistant Deputy Director
Land Development Division

INTERIM DRAINAGE POLICY

Attached is a draft interim drainage policy and guidelines for land development projects in the Acton area. Your comments are requested by December 1, 1989.

JEE:mg(M-2)IDP
L-0

DRAFT

ACTON INTERIM DRAINAGE POLICY AND GUIDELINES

The Interim Policy

Containment of the incremental increase of runoff and nuisance flows from land development proposals within the watershed for downtown Acton.

Tentative Map Requirements

Tentative map reviews are to be evaluated per current guidelines and procedures consistent with the Subdivision Ordinance. Drainage concepts will continue to be required and tentative subdivision maps held until the concepts are approved. The concept review will include an intensive evaluation of the lot layout and street patterns, as it affects drainage patterns and public safety. The reduction of proposed lots and/or redesign of street patterns may be necessary to mitigate the drainage concerns (and thereby avoid certain structural improvements).

Drainage Concepts

A drainage concept will be required for any division of land in Acton involving areas of known flood hazard and/or five acres or greater in total area. Delta Q basins shall be utilized to contain and percolate the incremental increase in runoff due to the development, similar to that used in the Antelope Valley.

Review of drainage concepts are to be consistent with current requirements and guidelines. However, several key issues should be acknowledged by the developer's engineer to avoid future complications and possible significant expenditures.

1. A maximum of seven-day soil percolation rate for delta-volume and/or full retention basins. A soils report should be submitted for soil section review.
2. Drainage solutions that not only mitigate the flood hazard to lots but are compatible with street safety drainage requirements.
3. Location and approximate sizing of the Delta Q basin.
4. Need for drainage acceptance letters from affected adjacent property owners.
5. The existence of multiple watercourses in the developed area necessitating multiple Delta Q basins.
6. Preliminary hydrology studies to evaluate before and after runoff conditions for the on-site areas as well the contributory off-site areas.

Drainage Concepts (Cont'd)

The drainage concepts will be coordinated and concurrently approved by both the Drainage and Grading and Road/Sewer and Water Sections.

Design Criteria

The interim drainage provisions require subdivisions to limit drainage outflow to the before developed condition quantities. This would include not only the change in peak Q but also the volume due to the incremental decrease in permeability associated with development. Facilities, therefore, must detain the change in peak Q and percolate the change in volume to satisfy this policy. No credit shall be permitted (in determining basin volume) for percolation during inflow.

Percolation basins are the preferred design concept. However, due to site topography, public input, and field design parameters, several design options may be considered acceptable including:

1. Allow contributory drainage (with debris) to flow essentially through the development and detain the peak Delta Q from the developed area and percolate the Delta volume. Return discharge of flows to the predevelopment condition or obtain drainage release letters from all affected properties.
2. Allow contributory, desilted drainage to be collected into the basin along with the developmental increase and regulate outflow to the before-development Q while still percolating the Delta volume. Return discharge of flows to the before-developed condition or obtain drainage release letters.
3. Allow only detention of the peak Delta Q provided there is a reasonable adequate outlet and drainage release letters obtained from all affected properties. Percolation of nuisance flows is still required.
4. Provide full retention and percolation of flows.
5. For subdivisions of five acres or less, provide drainage release letters in lieu of a Delta Q basin.

Each site must be evaluated on a case-by-case basis and drainage release letters may be mandatory due to the particular circumstances. Existing public roads maintained by the County may be considered as acceptable drainage outlets provided Departmental approval is obtained.

Interior street patterns should be designed to accommodate existing drainage patterns and street sump conditions should be avoided. Local streets can be utilized to convey storm flows provided it complies with street safety drainage requirements.

Basins are to be located at the downstream end of the developed area to maximize interception of nuisance flows and peak flow reduction.

DRAFT

Road Drainage Criteria

The attached charts depict the criteria for maintaining road drainage in the interim policy for Acton when storm drain solutions are not feasible. This policy permits flooding under certain conditions of all roadways up to a 25-year design frequency rainstorm.

Rights-Of-Way

The rights-of-way shall be shown and properly labeled on the plans. Retention and Delta Q basin easements are to be dedicated as flood control purposes to Los Angeles County Flood Control District.

Design Standards for Delta Q Basins

A. Hydrologic Criteria:

Basins are to be sized on a 25-year rainfall frequency, 4th day only, storm event plus one foot of freeboard. The volume shall be calculated based on hydrology before and after on the developed area without consideration for debris.

B. General Design Standards:

Provide adequate energy dissipation for inflows to prevent scour and erosion of the basin invert and side slopes.

Provide standard protection barriers and trash racks for inlets and outlets.

Provide a secondary overflow path (i.e., access road) to a paved public street as an auxiliary spillway.

Outflow lines (except true detention type basins) are to be elevated a minimum of one foot above the basin invert.

The basin floor is to be graded to drain away from the outflow line (3% typical). This is to be minimize basin maintenance by isolating and concentrating summer low flows.

C. Structural Criteria:

Soils report should be submitted that addresses slope stability, effects of rapid drawdown, infiltration, potential seepage, and possible effects such as land settlement or increased lateral infiltration and groundwater recharges.

Provide maximum 3:1 side slopes unless the soils report can verify stability at steeper slopes.

Basins utilizing walls as a means of retaining water must be reinforced concrete and structurally designed for hydrostatic pressures.

DRAFT

-4-

D. Access and Fencing:

Provide security fencing and a double drive gate per APWA Standard Drawing No. 600-0 or provide Department approved blockwalls (Min. height of 5 feet).

Provide a 12-foot wide minimum concrete access ramp to the bottom of the basin. Maximum grade into the basin shall be 12 percent.

Provide a 5-foot setback from the fence line or wall to the top of the basin slope along the basin perimeter adjacent public streets.

Provide an 8-foot setback from the fence line or wall to the top of the basin slope along basin perimeter adjacent private lots. Lesser setbacks must be approved by the Department in advance.

Drywell Alternatives

In smaller residential subdivisions (particularly with large rural lots) the use of a Delta Q basin and associated interceptor systems may be impractical. The Department will consider the use of a Maxwell Type IV drywell (or approved equal) on a case by case basis under the following conditions:



1. The subdivision is ten acres or less with minimum lot size of two acres and cannot be resubdivided into smaller lots.
2. Runoff and summer nuisance flows are properly intercepted and drywells are designed to handle potential debris laden flows.
3. Soils analysis supports the viability of operation, including in areas of proposed fill.
4. The drywells are located within public easements with paved vehicular access provided for maintenance and repair functions.
5. The use of these facilities have been adequately addressed in the environmental document for the tentative subdivision.
6. The approved hydrology study indicates a minimal increase in runoff due to development.

In certain situations, it may also be impractical to desilt all tributary flows and still pick up clear, developmental runoff for a Delta Q basin. The Department will consider, on site specific basis, the use of drywells to achieve percolation while allowing dilluted debris flows from the developed area to enter a Delta Q basin. It is the responsibility of the engineering consultant to develop a basin facility that can operate in the dual capacity function.



Drywells will be considered in controlling summer nuisance flows wherein topographic features and other Department policies and standards do not allow the practicality of draining the flows into the Delta Q basin.

DRAFT

PRESENT CRITERIA	FULL ROAD IMPROVEMENT ALTERNATIVES	DESIGN CRITERIA		ROAD FLOODING CONDITION		COMMENTS
		Q25	Q10	Within Gutter Area D X V	Highway	
	1. Without storm drain	X		Less than 6	1/2 free lane must be open in each direction	R/W to R/W or below either side of R/W
			X	*	One free lane must be open in each direction	*
	2. With storm drain	X		Less than 6	1/2 free lane must be open in each direction	There are generally no existing acceptable outlets for concentrated flow.
			X	*	One free lane must be open in each direction	





* Q25 Criteria governs



PROPOSED. TON
INTERIM ROAD DRAINAGE SAFETY POLICY

PROPOSED CRITERIA	FULL ROAD IMPROVEMENT ALTERNATIVES	DESIGN CRITERIA			ROAD FLOODING CONDITION		COMMENTS		
		Q25	Q10	Within Gutter Area D X V	Highway	Street	PROS	CONS	Additional Requirements
	3. Storm drain is not feasible. Allow flooding R/W to R/W.	X		A. New road improvements must be less than 6. D X V B. Widening existing improvements must be less than existing conditions to a maximum of 9. D X V	Allow highway flooding R/W to R/W but don't divert flow or increase the depth or the amount of flooding.	R/W to R/W	Roads are fully improved	1. Flooding R/W to R/W making road impassable during design storms. 2. Increase cost for road maintenance. 3. Conditions will not be improved until regional drainage facilities are available 4. Possible additional liabilities.	1. Drainage facilities to eliminate nuisance flows from highways.


DRAFT



PROPOSED TION
INTERIM ROAD DRAINAGE SAFETY POLICY

PROPOSED CRITERIA	FULL ROAD IMPROVEMENT ALTERNATIVES	DESIGN CRITERIA			ROAD FLOODING CONDITION		COMMENTS		
		Q25	Q10	Within Gutter Area D X V	Highway	Street	PROS	CONS	Additional Requirements
	4. Storm drain is not feasible. Exceed flooding R/W to R/W.	X		A. New road improvements must be less than 6.	Allow highway flooding R/W to R/W but don't divert flow or increase the depth or amount of flooding.	Not apply	Roads are fully improved	1. Flooding R/W to R/W making road impassable during design storms.	1. Drainage facilities to eliminate nuisance flows from highways.
				B. Widening existing road improvements must be less than existing condition to a maximum of 9.	Provide ditch or drainage facilities outside R/W to carry flows exceeding sur-face capacity.			2. Increase cost for road maintenance.	2. Pipe or box culvert or Arizona type crossing with low flow pipes for road crossing.
								3. Conditions will not be improved until regional drainage facilities are available.	3. Dedication of open space lots for drainage facilities outside R/W (private maintenance arrangement)
								4. Possible additional liabilities.	

* Only if all other normal drainage solutions are not feasible, the Arizona type crossing with low flow pipes may be permissible on highways in flat natural drainage courses.



DRAFT