

Beech Avenue Watermain Replacement

This project involves replacing about 3200 linear feet of existing 10-inch diameter asbestos-cement waterline with a 12-inch diameter ductile iron pipeline. The replacement line will span the length of Beech Avenue between Avenue J and Lancaster Boulevard in downtown Lancaster and will require about 85 existing service connections and nine fire hydrant connections to be transferred to the new line.

This project was completed in October 2012.

