
PLACEMENT DATA

- 1 PL. 18 TR FT. # 6 GROUND WIRE INSTALL 3 COPPER GROUND RODS 5/8" DIAMETER, 8' MINIMUM LENGTH NO PM - PROTECTION PRECAUTION
- 2 PL. 32' # 6 GROUND WIRE AT POLE 4428161E R/C 22C
- (3) PL. 54' 1-4" C-PC PTS 77 OR EQUIV. PM 1 DU 54' D & E CAP AT P/L FOR SUB'S TO PICK UP







- CONSTRUCTION REQUIREMENTS

 1. MAINTAIN MINIMUM COVER OF 36' BELOW FLOW LINE
 2. VERIFY EXISTING SUBSTRUCTURES PRIOR TO EXCAVATION.
 3. ALL 4" TO CONFORM TO PTS.-77 OR EQUIVALENT.
 4. ALL 2" TO CONFORM TO PTS.-66 OR EQUIVALENT.
 5. ALL BACKFILL TO BE SAND 12' BELOW AND 5" ABOVE.
 6. DO NOT BACKFILL OVER ANY TELEPHONE BURIED SPLICE LOCATIONS UNTIL. AUTHORIZED BY TELEPHONE COMPANY INSPECTOR.
 7. PLACE #6 TINNED GROUND WIRE AT BONDING POINTS. (SEE BONDING DETAIL)
 8. PLACE PULL ROPE IN NEW CONDUIT.
 9. DO NOT CUT CURB & GUTTER.
 10. ALL SURFACES AND LANDSCAPES WHICH HAVE BEEN REMOVED OR DAMAGED IN THE COURSE OF CONSTRUCTION SHALL BE RECONSTRUCTED OR REPLACED TO AT LEAST EQUAL OR BETTER THAN THE PREVIOUS OR ADJACENT SURFACE.
 11. ALL TRAFFIC CONTROL TO BE IN ACCORDANCE WITH THE CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) LATEST EDITION.
 12. PER ATAT GUIDELINES, ALL HANDHOLES, SPLICE BOXES, AND MANHOLES TO BE PURCHASED FROM EITHER NEWBASE OR UTILITY VAULT.

THIS PROJECT REQUIRES EXCAVATION. CONSTRUCTION WILL UTILIZE AND IMPLEMENT ALL BEST MANAGEMENT PRACTICES (BMPs) AS REQUIRED TO ENSURE COMPLIANCE WITH A TAT POLICY LETTER ISSUE FEBRUARY 21, 2003 AND REVISED IN OCTOBER 2005 BY ENVIRONMENTAL MANAGEMENT CONCERNING STORM WATER PERMITTING AND STORM WATER POLLUTION PREVENTION PLANS (SWPPPS) AND IN ACCORDANCE WITH THE CLEAN WATER ACT (1972) AND EPA REQUIATIONS PUBLISHED IN 1990 AS MODIFIED BY THE PHASE II RULE IN 1999.

LOCATION: 119TH ST N/S OF STREET, 94' W/O C/L OF BERENDON AVE.

DESCRIPTION: PL. GROUND BED & 32' OF BARE #6 GROUND WIRE AT POLE 4428161E. PL. 54' OF 1.4" DU FROM POLE 4428161E TO P/L. D & E CAP AT P/L FOR SUB'S TO PICK UP.

BACKFILL SHALL BE PER CITY OF LOS ANGELES COUNTY

STREET TYPE	SOIL CLASS	PROPOSED BACKFILL
MAJOR	N/A	N/A
SECONDARY	N/A	N/A
LOCAL	N/A	N/A
ALLEY	N/A	N/A

CONDUIT RECORD: N/A

SUB MAP #: N/A TREET NAME N/A MATERIAL N/A INEAR FEET N/A

EXCAVATION DATA						
OF:	LOS ANGELES COUNTY					
CING:	CONDUIT ,GROUND BED & 32' OF BARE#6 GROUND WIRE					

EXCAVATION IN CONCRETE SIDEWALK 40' X 1' = 40 SQ FT EXCAVATION IN DIRT (GRND. BED) EXCAVATION IN DIRT

	TOTAL E	EXCAVATION:		69 SQ FT
	NUMBER	R OF CUTS:		2
		DATE	ATTID	DAWN HOLTZMAN
	DRAWN	4/21/14	CHC/GO5373	TELEPHONE NUMBER 818-778-2404
	CHECKE	D		DH7852@ATT.COM
	APPROVI	ED 5/2/14	DH7852	PHILLIP MUNOZ
	DATE REVISIONS		IS	310-515-4246
				A312
				PLYMOUTH
Consulting, LLC	SCALE			UNDERGROUND CONSTRUCTION PROJECT NUMBER
1700 E. Garry Ave. , Suite 210	1" = 20' 704-A7		THOMAS GUIDE 704-A7	9210055
Santa Ana, CA 92705 (949) 250-0004 / FAX (949) 250-0006	FILENAME: A312 9210055.dwg			DRAWING: 1/1