PERMIT NEEDED

Pole located @ 204 S. 8th Ave

CITY OF INDUSTRY / LACO

ASPLUNDH CONSTRUCTION CORP.

SOUTHERN CALIFORNIA EDISON
An EDISON INTERNATIONAL Company

E/S

DETERIORATED POLE REPLACEMENT

CIRCUIT (S):
ISIS 12KV o/o PROCTOR SUB

STA'S
11-12

ADDRESS:
LOCATION: 8TH AV E/S 585' N/O PROCTOR ST
CITY: INDUSTRY
*** NOTES:**

(11) RM 810760E
45' Class C4
RM: 1– POLE 45' CLASS 4 WOOD FULL TREAT
RM: 1– SA POLY W/GND PRI–N 12KV 1P
RM: 1– XA SNGL FB 10' STEEL PINS
RM: 3– INS GLASS & PIN 12KV
RM: 2– INS POLY DE 12KV HOT SHOE #4 & 1/0
RM: 2– SEC ROLLER (166–CLEVIS & SPOOL)

SET SAME HOLE

POLE 810760E (12)
50' Class C1
IN: 1– POLE 50' CLASS 1 WOOD FULL TREAT
IN: 1– SA POLY W/GND PRI–N 12KV 1P
IN: 1– XA SNGL FB 10' STEEL PINS
IN: 2– INS POLY W/PIN 12KV CLMP #6–4/0 CU
IN: 1– INS POLY W/PIN 12KV CLMP #4–653 ACSR
IN: 2– INS POLY DE 12KV HOT SHOE #4 & 1/0
IN: 2– SEC ROLLER (166–CLEVIS & SPOOL)

(P) 7/7 KB

TRANSFER (S):
2/C 6B-12KV
1-4A-12KV
2-4AT-120V (SVC'S)
1-4"/3" RISER
1-3"/2" RISER
1-2" RISER
PETHEADS

EXISTING RISER DETAIL



4"/3" PRI RIS
3"/2" COMM
2" OPEN

concrete

NOT TO SCALE

PERMIT REQ'D.

CALTRANS:	
ENCROACHMENT:	
RAILROAD:	
HELICOPTER:	
OTHER:	

SPEED LIMIT 25

PEDESTRIAN TRAFFIC CONTROL REQUIRED
[X] YES [ ] NO

GPS: LAT: N 34° 1' 50.98"
LONG: W 117° 58' 22.1"

TLM DATA:

	SIZE	KVA	CUST.	% LOAD
EXIST				
PROP.				

VOLTAGE DROP ____ %
PRI. CIRC. _____

NOTES

JOINT POLE:	X
RENTER:	
MITC FUME:	
JOINT MEET:	X
TRUCK ACCESS:	X
HAND SET:	
CONTACT CATV:	X
ENVIRONMENTAL:	
REAL PROP. REVIEW:	
PAVEMENT REPAIR:	X
[X] CONCRETE / [ ] ASPHALT	4' X 4'

DISTRICT 26 – COVINA	PROJ. MGR. RODRIGUEZ, JOHN T PHONE 909–469–0219		PLANNER MANIS, BRETT PHONE 714–893–2405		
FOREMAN	TRUCK NO.	P/E	INVENTORY MAP NO. 122–4296–1	THOMAS GUIDE LA–638–B6	GRID NO.
DESIGN NO. 564934_0.01					
CSD 140 Y ___ N ___	BY–PASS CODE	EXISTING ___ CHANGE TO ___	TLM CHECKED ___ %LOAD	J.P.A. NO. 4100601708	ASSOCIATED DESIGN NO.
PRODUCT/SAP NO. 808568-INFRA REP - DET POLE RELACE		PRODUCT/SAP NO.		PRODUCT/SAP NO.	

TYPE	APPROVED BY	DATE	CHECKED BY	DRAWN BY	PAX #

PROPOSED CONSTRUCTION (LOCATION)
DETERIORATED POLE REPLACEMENT
COVINA

SHEET ___ OF ___
JOB NO. 564934_0.01

Southern California Edison Company

PAGE NO. 4 J.P. AUTH. NO. E6026-406061708

POLE NO.	Pole Length / Anchor Size	Year Set	Pole Trt. / Class / Anchor Direct.	Record 12KV E	Record VZ	Record NG	Record	Proposed 12KV E	Proposed VZ	Proposed NG	Proposed	Proposed	Item No.	LOCATION AND NATURE OF WORK If not in accordance with Joint Pole agreement and routine-state reasons.	
														E TO REPLACE PER SECTION 7.11, 7.4, 19.6, 10.8	1
810760E	45	50	FT		24'			PTD						8TH AV E/S 585' N/O PROCTOR ST	2
								2					83	1-CATV / 1-COMM	3
								1/2 (1)					19B		4
								1/2(1)					10A	5' X 5'	5
															6
810760E	50	14	FT CL-2						24-6					8TH AV E/S 586' N/O PROCTOR ST	7
														SET SAME HOLE	8
															9
															10
															11
															12
															13
															14
															15
															16
															17
															18
															19

POLE LEGEND:
P = PULL
PB = PULL BUTT
T = TRANSPORT
S = SALVAGE
D = DISPOSE
TN = TENANT

L = LOWER CUT
C(XX)= FOOTAGE CUT
SCZ = SAFETY CLEARANCE ZONE

ANCHOR LEGEND:
AR = ANCHOR REMOVED
AT = ANCHOR TRANSFERRED

Show Quantity of Items to be billed in the Column of Party to be Paid.

GEOGRAPHICAL LOCATION

INDUSTRY

COMMUNITY