

**EROSION AND SEDIMENT CONTROL PLAN (ESCP) GENERAL NOTES:**

1. In case of emergency, call \_\_\_\_\_ (Responsible Person) \_\_\_\_\_ at \_\_\_\_\_ (24-Hour telephone).  
i. Please fill in name and number
2. Total Disturbed Area \_\_\_\_\_ WDID # \_\_\_\_\_  
i. Risk Level 1 2 3 (circle one as determined by State General Permit for sites greater than 1 acre)
3. A stand-by crew for emergency work shall be available at all times during the rainy season (November 1 to April 15). Necessary materials shall be available on-site and stockpiled at convenient locations to facilitate rapid construction of emergency devices when rain is imminent.
4. Erosion control devices shown on this plan may be removed when approved by the Building Official if the grading operation has progressed to the point where they are no longer required.
5. Graded areas adjacent to fill slopes located at the site perimeter must drain away from the top of slope at the conclusion of each working day. All loose soils and debris that may create a potential hazard to off-site property shall be stabilized or removed from the site on a daily basis.
6. All silt and debris shall be removed from all devices within 24 hours after each rainstorm and be disposed of properly.
7. A guard shall be posted on the site whenever the depth of water in any device exceeds two feet. The device shall be drained or pumped dry within 24 hours after each rainstorm. Pumping and draining of all basins and drainage devices must comply with the appropriate BMP for dewatering operations.
8. The placement of additional devices to reduce erosion damage and contain pollutants within the site is left to the discretion of the Field Engineer. Additional devices as needed shall be installed to retain sediments and other pollutants on site.
9. Desilting basins may not be removed or made inoperable between November 1 and April 15 of the following year without the approval of the Building Official.
10. Storm Water Pollution and Erosion Control devices are to be modified, as needed, as the project progresses, the design and placement of these devices is the responsibility of the field engineer. Plans representing changes must be submitted for approval if requested by the Building Official.
11. Every effort should be made to eliminate the discharge of non-storm water from the project sites at all times.
12. Eroded sediments and other pollutants must be retained on-site and may not be transported from the site via sheet flow, swales, area drains, natural drainage courses, or wind.
13. Stockpiles of earth and other construction-related materials must be protected from being transported from the site by the forces of wind or water.
14. Fuels, oils, solvents, and other toxic materials must be stored in accordance with their listing and are not to contaminate the soils and surface waters. All approved storage containers are to be protected from the weather. Spills must be cleaned up immediately and disposed of in a proper manner. Spills may not be washed into the drainage system.
15. Excess or waste concrete may not be washed into the public way or any other drainage system. Provisions shall be made to retain concrete wastes on-site until they can be disposed of as solid waste.
16. Developers/contractors are responsible to inspect all Erosion Control Devices and BMPs are installed and functioning properly if there is a 50% or greater probability of predicted precipitation, and after actual precipitation. A construction site inspection checklist and inspection log shall be maintained at the project site at all times and available for review by the Building Official (copies of the self-inspection check list and inspection logs are available upon request).

- 17. Trash and construction-related solid wastes must be deposited into a covered receptacle to prevent contamination of rainwater and dispersal by wind.
- 18. Sediments and other materials may not be tracked from the site by vehicle traffic. The construction entrance roadways must be stabilized so as to inhibit sediments from being deposited into the public way. Accidental depositions must be swept up immediately and may not be washed down by rain or other means.
- 19. Any slopes with disturbed soils or denuded of vegetation must be stabilized so as to inhibit erosion by wind and water.
- 20. As the engineer/QSD of record, I have selected appropriate BMPs to effectively minimize the negative impacts of this project's construction activities on storm water quality. The project owner and contractor are aware that the selected BMPs must be installed, monitored, and maintained to ensure their effectiveness.

_____	_____
Civil Engineer/QSD Signature	Date

21. The following notes must be on the plan:

As the project owner or authorized agent of the owner, "I certify that this document and all attachments were prepared under my direction or supervision in accordance with the system designed to ensure that a qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, to the best of my knowledge and belief, the information submitted is true, accurate, and complete. I am aware that submitting false and/ or inaccurate information, failing to update the ESCP to reflect current conditions, or failing to properly and/or adequately implement the ESCP may result in revocation of grading and/or other permits or other sanctions provided by law."

_____	_____
Owner or Authorized Representative (Permittee)	Date

22. Developers/contractors are responsible to inspect all Erosion Control Devices and BMPs are installed and functioning properly as required by the State Construction General Permit. A construction site inspection checklist and inspection log shall be maintained at the project site at all times and available for review by the Building Official.

23. The following BMPs from the "2009 Construction BMP Handbook/Portal" must be implemented for all construction activities as applicable. As an alternative, details from "Caltrans Stormwater Quality Handbooks, Construction Site Best Management Practices (BMP) Manual" may be used. Additional measures may be required if deemed appropriate by the Building Official.

EROSION CONTROL

EC1 – SCHEDULING  
EC2 – PRESERVATION OF EXISTING VEGETATION  
EC3 – HYDRAULIC MULCH  
EC4 – HYDROSEEDING  
EC5 – SOIL BINDERS  
EC6 – STRAW MULCH  
EC7 – GEOTEXTILES & MATS  
EC8 – WOOD MULCHING  
EC9 – EARTH DIKES AND DRAINAGE SWALES  
EC10 – VELOCITY DISSIPATION DEVICES  
EC11 – SLOPE DRAINS  
EC12 – STREAMBANK STABILIZATION  
EC13 – *RESERVED*  
EC14 – COMPOST BLANKETS  
EC15 – SOIL PREPARATION/ROUGHENING  
EC16 – NON-VEGETATED STABILIZATION

TEMPORARY SEDIMENT CONTROL

SE1 – SILT FENCE  
SE2 – SEDIMENT BASIN  
SE3 – SEDIMENT TRAP  
SE4 – CHECK DAM  
SE5 – FIBER ROLLS  
SE6 – GRAVEL BAG BERM  
SE7 – STREET SWEEPING AND VACUUMING  
SE8 – SANDBAG BARRIER  
SE9 – STRAW BALE BARRIER  
SE10 – STORM DRAIN INLET PROTECTION  
SE11 – ACTIVE TREATMENT SYSTEMS  
SE12 – TEMPORARY SILT DIKE  
SE13 – COMPOST SOCKS & BERMS  
SE14 – BIOFILTER BAGS

WIND EROSION CONTROL

WE1 – WIND EROSION CONTROL

TEMPORARY TRACKING CONTROL

TC1 – STABILIZED CONSTRUCTION ENTRANCE EXIT  
TC2 – STABILIZED CONSTRUCTION ROADWAY  
TC3 – ENTRANCE/OUTLET TIRE WASH

NON-STORMWATER MANAGEMENT

NS1 – WATER CONSERVATION PRACTICES  
NS2 – DEWATERING OPERATIONS  
NS3 – PAVING AND GRINDING OPERATIONS  
NS4 – TEMPORARY STREAM CROSSING  
NS5 – CLEAR WATER DIVERSION  
NS6 – ILLICIT CONNECTION/DISCHARGE  
NS7 – POTABLE WATER/IRRIGATION  
NS8 – VEHICLE AND EQUIPMENT CLEANING  
NS9 – VEHICLE AND EQUIPMENT FUELING  
NS10 – VEHICLE AND EQUIPMENT MAINTENANCE  
NS11 – PILE DRIVING OPERATIONS  
NS12 – CONCRETE CURING  
NS13 – CONCRETE FINISHING  
NS14 – MATERIAL AND EQUIPMENT USE  
NS15 – DEMOLITION ADJACENT TO WATER  
NS16 – TEMPORARY BATCH PLANTS

WASTE MANAGEMENT & MATERIAL POLLUTION CONTROL

WM1 – MATERIAL DELIVERY AND STORAGE  
WM2 – MATERIAL USE  
WM3 – STOCKPILE MANAGEMENT  
WM4 – SPILL PREVENTION AND CONTROL  
WM5 – SOLID WASTE MANAGEMENT  
WM6 – HAZARDOUS WASTE MANAGEMENT  
WM7 – CONTAMINATION SOIL MANAGEMENT  
WM8 – CONCRETE WASTE MANAGEMENT  
WM9 – SANITARY/SEPTIC WASTE MANAGEMENT  
WM10 – LIQUID WASTE MANAGEMENT