


GENERAL NOTES

1. CONTRACTOR SHALL BE HELD RESPONSIBLE FOR HAVING VISITED THE SITE AND HAVING FAMILIARIZED HIMSELF WITH THE EXISTING CONDITIONS PRIOR TO SUBMITTING HIS BID.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO ANY DEMOLITION OR CONSTRUCTION AT THE JOB SITE. ANY DISCREPANCY TO NOTIFY LA COUNTY ARCHITECT IMMEDIATELY.
3. ALL WORK SHALL BE PERFORMED AS PER CALIFORNIA BUILDING CODE, 2022 EDITION AND ALL INSPECTIONS SHALL BE PERFORMED AS REQUIRED BY THE COUNTY OF LOS ANGELES BUILDING DEPARTMENT AND THEIR RELATED AGENCIES.
4. CONTRACTOR SHALL MAINTAIN A SET OF PLANS, APPROVED BY THE LOCAL BUILDING DEPARTMENT, ON THE JOB SITE AT ALL TIMES DURING CONSTRUCTION.
5. ALL WORK AND MATERIALS SHALL CONFORM TO THE REQUIREMENTS OF THE LATEST EDITIONS OF THE COUNTY OF LOS ANGELES BUILDING CODE AND UNIFORM BUILDING CODE STANDARDS, CALIFORNIA CODE OF REGULATIONS HANDICAPPED ACCESSIBILITY REQUIREMENTS (TITLE 24), AMERICANS WITH DISABILITIES ACT (ADA), THE PLANS AND THE PROJECT MANUAL.
6. THIS PROJECT REQUIRES THE PRIME CONTRACTOR TO POSSESS A LICENSE PER GENERAL CONDITIONS AT THE TIME OF BID AWARD. CONTRACTORS SHALL VERIFY THAT ALL CORRECT LICENSES ARE POSSESSED FOR THIS PROJECT.
7. CONTRACTOR SHALL BE RESPONSIBLE TO IDENTIFY & PROTECT AND REPAIR ALL ABOVE AND UNDERGROUND UTILITIES, INCLUDING ELECTRICAL, PLUMBING, SPRINKLERS, GAS SEWERS, AND STORM DRAINS WITHIN THE CONSTRUCTION SITE OR AREAS THAT THEY WORK IN. CONTRACTOR SHALL BE RESPONSIBLE TO SOLICIT THE SERVICES OF USA/DIG ALERT PRIOR TO AN EXCAVATION WORK.
8. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS, DIMENSIONS, AND ELEVATIONS. ANY DISCREPANCIES SHALL BE CALLED TO THE ATTENTION OF THE DEPARTMENT OF PUBLIC WORKS AND BE RESOLVED PRIOR TO STARTING WORK. DO NOT SCALE DRAWINGS.
9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE WORK OF ALL TRADES. CONTRACTOR TO COORDINATE CIVIL, ARCHITECTURAL, ELECTRICAL, MECHANICAL AND PLUMBING REQUIREMENTS BEFORE CONSTRUCTION. ALL CONDITIONED SPACES SHALL COMPLY WITH "TITLE 24" STATE ENERGY CONSERVATION REQUIREMENTS. THE CONTRACTOR SHALL MAINTAIN FIRE ACCESS DURING CONSTRUCTION.
10. CONTRACTOR SHALL BE RESPONSIBLE FOR THE PUBLIC SAFETY AND FOR THE SAFETY OF THE BUILDING DURING CONSTRUCTION. THIS INCLUDES ALL NECESSARY SHORING, BRACING AND GUY WIRES WHICH SHALL CONFORM TO ALL APPLICABLE SAFETY ORDINANCES. CONSULTANTS ARE AVAILABLE AT OSHA.
11. CONTRACTOR SHALL MAINTAIN THE SITE CLEAN OF RUBBISH SO AS NOT TO IMPEDE THE ACCESS AND WORK OF OTHER TRADES. THE CONTRACTOR SHALL PROVIDED BARRICADE/TEMPORARY FENCING/WARNING SIGNS TO PROTECT THE PUBLIC OR WORKMEN DURING CONSTRUCTION. BARRICADES/TEMPORARY FENCING SHALL BE LEFT IN PLACE UNTIL AUTHORIZED BY THE DEPARTMENT TO BE REMOVED BY THE CONTRACTOR, AND AFTER THE BARRICADES/TEMPORARY FENCING IS NOT LONGER REQUIRED FOR PROTECTION.
12. ALL ADJACENT FACILITIES SHALL CONTINUE IN NORMAL OPERATION DURING THE PERIOD OF THE CONTRACT. THE CONTRACTOR SHALL CONDUCT HIS WORK IN SUCH A MANNER NOT TO RESTRICT OR OBSTRUCT ENTRANCES, EXITS OR DISRUPT UTILITY SERVICES. THE CONTRACTOR SHALL PROVIDE TEMPORARY CONNECTIONS, LINES AND SERVICES TO THE LOS ANGELES COUNTY DEPARTMENTS.
13. ALL AREAS AFFECTED OR DAMAGED BY ALTERATION, REMOVAL OF EXISTING CONSTRUCTION AND NEW WORK SHALL BE PATCHED AND REPAIRED TO MATCH EXISTING OR IN A SATISFACTORY MANNER APPROVED BY LOS ANGELES COUNTY PUBLIC WORKS. MATCH ADJACENT SIMILAR MATERIALS IN TEXTURE AND COLOR.
14. SEPARATE BUILDING PERMITS SHALL BE TAKEN OUT FOR ELECTRICAL AND MECHANICAL PORTIONS. REQUIRED PERMITS SHALL BE OBTAINED FROM THE "STATE DIVISION OF INDUSTRIAL SAFETY" FOR ANY TRENCHES OR EXCAVATIONS 5 FEET OR MORE IN DEPTH INTO WHICH A PERSON IS REQUIRED TO DESCEND. SEPARATE PLANS SHALL BE PLAN CHECKED AND SEPARATE PERMITS SHALL BE OBTAINED FOR AUTOMATIC FIRE EXTINGUISHING SYSTEM AS APPLICABLE.
15. ALL WORK AND MATERIALS ARE NEW UNLESS OTHERWISE INDICATED. THE CONTRACT DOCUMENTS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE UNLESS OTHERWISE SHOWN. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND HE SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES, INCLUDING BUT NOT LIMITED TO INSTALLATION OF ADEQUATE SHORING, BRACING, ETC., TO SAFELY EXECUTE ALL WORK.
16. DRAWINGS ARE DIVIDED INTO SEPARATE SHEETS FOR GENERAL CONVENIENCE ONLY. SHEET DESIGNATIONS OR NUMBERS SHALL NOT BE CONSIDERED TO LIMIT AREAS OF WORK, RESPONSIBILITY, OR TRADES. CONTRACTOR MUST COORDINATE THE DRAWINGS WITH EACH OTHER AND WITH PROJECT MANUAL IN ORDER TO COMPLETE THE PROJECT AS DESIGNED.
17. DIMENSIONS OF STUD WALLS ARE TO CENTERLINE OF STUDS UNLESS OTHERWISE NOTED. ALL DIMENSIONS ARE TO CENTER LINE OF COLUMNS UNLESS NOTED OTHERWISE. CONCRETE IS DIMENSIONED TO FACE OF WALL. CMU DIMENSIONS ARE TO CENTERLINE OF MORTAR JOINTS UNLESS OTHERWISE NOTED. FOR EXACT OVERALL WALL DIMENSIONS SUBTRACT ONE MORTAR JOINT. FOR EXACT WALL OPENING DIMENSION ADD ONE MORTAR JOINT TO BOTH WIDTH AND HEIGHT. VERTICAL DIMENSIONS FROM FINISH FLOOR LINE ARE TO TO TOP OF UNIT UNLESS OTHERWISE NOTED.
18. TYPICAL DETAILS AND GENERAL NOTES APPLY TO ALL PARTS OF THE JOB, EXCEPT WHERE THEY CONTRADICT WITH DETAILS NOTES SPECIFIED ON OTHER SHEETS. ALL INFORMATION SHOWN ON THE DRAWINGS RELATIVE TO EXISTING CONDITIONS IS GIVEN AS BEST AS POSSIBLE, BUT WITHOUT GUARANTEE OF ACCURACY. WHERE ACTUAL CONDITIONS CONFLICT WITH THE DRAWINGS, THEY SHALL BE REPORTED TO LOS ANGELES COUNTY PUBLIC WORKS ARCHITECTS SO THAT THE PROPER REVISIONS MAY BE MADE. MODIFICATIONS OF DETAILS OF CONSTRUCTION SHALL NOT BE MADE WITHOUT WRITTEN APPROVAL OF LOS ANGELES COUNTY PUBLIC WORKS ARCHITECTS. WHERE NO SPECIFIC DETAIL IS SHOWN, THE FRAMING OR CONSTRUCTION SHALL BE IDENTICAL OR SIMILAR TO THAT FOR LIKE CASES OF CONSTRUCTION ON THIS PROJECT, AND BE SUBJECT TO REVIEW AND APPROVAL BY LA COUNTY DPW ARCHITECTS.

BA
SECURE Y
SECURITY A
163
S

BUILDING SUMMARY	
ZONING:	PF-1VL
BUILDING OCCUPANCY:	I-3, B
CONSTRUCTION TYPE:	TYPE I-A (FIRE RESISTIVE CONSTRUCTION) 
BUILDING CODE:	CALIFORNIA BUILDING CODE, 2022 EDITION CALIFORNIA MECHANICAL CODE, 2022 EDITION CALIFORNIA ELECTRICAL CODE, 2022 EDITION

APPLICABLE CODES

BUILDING CODES:

- LA COUNTY BUILDING CODE, 2023 EDITION
- LA COUNTY MECHANICAL CODE, 2023 EDITION
- LA COUNTY ELECTRICAL CODE, 2023 EDITION
- LA COUNTY PLUMBING CODE, 2023 EDITION
- LA COUNTY ENERGY CODE, 2023 EDITION
- LA COUNTY GREEN BLDG. STANDARDS CODE, 2023 EDITION

DIRECTORY

OWNER'S REPRESENTATIVE

LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
PROJECT MANAGEMENT DIVISION II
900 S. FREMONT AVENUE
ALHAMBRA, CA 91803
ATTN.: COURTNEY TOSSOUNIAN
TEL: 626-300-3277

ARCHITECT

JTC ARCHITECTS, INC.
65 N. FIRST AVE., STE. 201
DOWNTOWN

ARCADIA, CA 91706
ATTN.: JUNE QUEK
TEL : 626-254-8884

CIVIL
CALVADA SURVEYING, INC.
411 JENKS CIRCLE, SUITE 205
CORONA, CA 92878
ATTN.: ARMANDO DUPONT
TEL: 951-280-9960

STRUCTURAL
MHP STRUCTURAL ENGINEERS
3900 COVER STREET
LONG BEACH, CA 90808
ATTN.: RICK BEALL
TEL: 562-985-3200

MECHANICAL & ELECTRICAL
dHA+CALPEC
150 S. ARROYO PARKWAY, STE. 100
PASADENA, CA 91105
ATTN.: KEVIN CHEN (MECH.)
DEREK WEI (ELEC.)
TEL.: 626-445-8580

LEGAL DESCRIPTION

ASSESSOR'S PARCEL NO. 2603-010-906

LOS ANGELES OLIVE GROWERS ASSOCIATION LANDS LOT COM AT NW
COR OF LOT 3 BLK 218 TH E TO NE COR OF SD LOT TH N
112°27'33" E 117.65 FT TH S 32°36'07" E TO W LINE OF YARNELL
ST TH S THEREON TO N LINE OF S P R R /W TH W ON SD N
LINE TO E LINE OF FILBERT ST TH N THEREON TO BEG PART OF
LOTS 2, 4 AND 6 AND ALL OF LOTS 3, 5, 7 AND LOT 8 BLK 218

PROJECT DESCRIPTION

TWO PORTIONS OF THE OVERALL PROJECT UNDER THIS PERMIT APPLICATION INVOLVE SECURITY UPGRADES TO THE EXTERIOR PERIMETER WALLS AND PROVISIONS FOR A NEW HVAC FOR ONE OF THE BUILDINGS AT CAMP BARRY J. NIDORF JUVENILE HALL IN SYLMAR, CA. DESCRIPTIONS ARE LISTED BELOW:

- INSTALL SECURITY FENCE NETTING SYSTEM AT THE NORTH INTERIOR CONCRETE MASONRY BLOCK WALLS, ALONG THE WEST, NORTHEAST AND EAST BLOCK WALLS PROPERTY LINES.
- INSTALL NEW HVAC SYSTEM FOR THE DRY FOOD STORAGE ROOM AT BUILDING 16 KITCHEN CAFETERIA.

SCOPE OF WORK

A. SECURITY FENCE NETTING (PERIMETER BLOCK WALLS):


- INSTALL 26'--4" MINIMUM HIGH SECURITY NETTING ON STEEL FRAMES AND POSTS ALONG EXISTING MASONRY BLOCK WALLS (DRIVEWAY AISLES)
- DRILL PILE FOUNDATION FOR THE MAIN STRUCTURAL POSTS SUPPORTS

B. HVAC SYSTEM (AT BUILDING #5):

- INSTALL TWO DIRECT EXPANSION FAN COILS UNITS IN THE DRY FOOD STORAGE ROOM
- PROVIDE DUCTLESS OUTDOOR CONDENSER UNIT ON THE MAIN

3. NOTE TO PLANNING (PLAN CHECK COMMENT)
GRADING OF SITE AREAS IS NOT PART OF
SCOPE OF WORK. THERE IS NO GRADING
WORK INVOLVED UNDER THIS PERMIT.


VICINITY MAP

A vicinity map showing a street grid. A red line indicates the project location, running diagonally from the bottom left towards the top right. The map is oriented with North at the top. The streets are labeled with numbers and letters, but they are mostly illegible due to the low resolution and angle. The map shows a typical urban grid pattern with a main thoroughfare running diagonally.

A map showing the location of the Project Site. The map includes a road labeled 'Filbert St' running vertically. To the left of the road is a black square marker labeled 'Los Angeles County Juvenile Hall'. To the right of the road is a black circle marker labeled 'Barry J. Nidore Juvenile Hall'. A line connects the 'PROJECT SITE' label to the circle marker.

DRAWING INDEX		ISSUE DATE																				
DRAWING NUMBER AND TITLE																						
		04/28/23	SCHMATIC DESIGN	PROGRESS SET	07/07/23	SCHMATIC DESIGN SET	09/15/23	50% CONSTRUCTION DOCUMENTS	03/27/24	REVISED 50% CONSTRUCTION DOCUMENTS	04/24/24	90% CONSTRUCTION DOCUMENTS	05/10/24	PLAN CHECK SUBMITTAL-BLDG & PLAN'G	06/17/24	PLAN CHECK RESUBMITTAL-BLDG	11/11/24	PLAN CHECK RESUBMITTAL-PLANNING	11/30/24	PLAN CHECK RESUBMITTAL-SOILS REPORT	02/04/25	ISSUED FOR BIDDING
	TITLE																					
T-001	TITLE, VICINITY MAP, DIRECTORY, AND DRAWING INDEX	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
	CIVIL																					
C-1.01	TOPOGRAPHIC SURVEY – SHEET 1 OF 5						●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
C-1.02	PARTIAL ENLARGED TOPOGRAPHIC SURVEY – SHEET 2 OF 5						●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
C-1.03	PARTIAL ENLARGED TOPOGRAPHIC SURVEY – SHEET 3 OF 5						●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
C-1.04	PARTIAL ENLARGED TOPOGRAPHIC SURVEY – SHEET 4 OF 5						●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
C-1.05	PARTIAL ENLARGED TOPOGRAPHIC SURVEY – SHEET 5 OF 5												●	●	●	●	●	●	●	●	●	●
	ARCHITECTURAL																					
A-1.01	SITE PLAN		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
A-1.01A	SITE PLAN – AREAS OF WORK																●	●	●	●	●	●
A-1.02	PARTIAL ENLARGED SITE PLANS – EXISTING FOR REFERENCE						●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
A-1.03	PARTIAL ENLARGED SITE PLANS – EXISTING FOR REFERENCE						●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
AD-2.01	BUILDING #5 – KITCHEN/ DINNING/ CHAPEL FLOOR PLAN–DEMO		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
A-2.01	BUILDING #5 – KITCHEN/ DINNING/ CHAPEL FLOOR PLAN–NEW		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
A-3.01	ENLARGED SECURITY WALL PLANS – NEW WORK						●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
A-3.01A	ENLARGED SECURITY WALL PLANS – NEW WORK											●	●	●	●	●	●	●	●	●	●	●
A-3.02	ENLARGED SECURITY WALL ELEVATIONS – NEW WORK						●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
A-3.02A	ENLARGED SECURITY WALL ELEVATIONS – NEW WORK											●	●	●	●	●	●	●	●	●	●	●
A-3.03	PARTIAL ENLARGED SECURITY WALL PLAN, ELEVATIONS, SECTIONS AND DETAILS – NEW WORK		●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●	●
	STRUCTURAL																					
S-0.01	STRUCTURAL NOTES AND ABBREVIATIONS							●	●	●	●	●	●	●	●	●			●	●	●	●
S-0.02	STRUCTURAL NOTES							●	●	●	●	●	●	●	●	●			●	●	●	●
S-1.01	SITE PLAN								●	●	●	●	●	●	●	●			●	●	●	●
S-2.00	PARTIAL SECURITY WALL FOUNDATION PLAN								●	●	●	●	●	●	●	●			●	●	●	●
S-2.01	PARTIAL SECURITY WALL FOUNDATION PLAN								●	●	●	●	●	●	●	●			●	●	●	●
S-2.02	PARTIAL ROOF FRAMING PLAN								●	●	●	●	●	●	●	●			●	●	●	●
S-3.01	SECTIONS AND DETAILS							●	●	●	●	●	●	●	●	●			●	●	●	●
	MECHANICAL																					
M-0.01	MECHANICAL LEGEND, NOTES AND ABBREVIATIONS		●	●	●	●	●	●	●	●	●	●	●	●	●	●			●	●	●	●
M-0.02	MECHANICAL EQUIPMENT SCHEDULE		●	●	●	●	●	●	●	●	●	●	●	●	●	●			●	●	●	●
M-0.03	MECHANICAL TITLE 24														●	●			●	●	●	●
M-0.04	MECHANICAL TITLE 24														●	●			●	●	●	●
M-101	MECHANICAL FLOOR AND ROOF PLAN		●	●	●	●	●	●	●	●	●	●	●	●	●	●			●	●	●	●
M-5.01	DETAILS											●	●	●	●	●			●	●	●	●
	ELECTRICAL																					
E-0.01	ELECTRICAL LEGENDS AND NOTES		●	●	●	●	●	●	●	●	●	●	●	●	●	●			●	●	●	●
E-0.02	PARTIAL SINGLE LINE DIAGRAM AND PANEL SCHEDULE		●	●	●	●	●	●	●	●	●	●	●	●	●	●			●	●	●	●
E-0.03	ELECTRICAL DETAILS																		●	●	●	●
E-2.01	FLOOR PLAN – NEW WORK		●	●	●	●	●	●	●	●	●	●	●	●	●	●			●	●	●	●


DATE	NO.	FORMS:	BY:	DATE	NO.	FORMS:	BY:	DATE	NO.	FORMS:	BY:	DATE	NO.	FORMS:
02-04-25	△	PLAN CHECK SUBMITTAL-BUDG & PLANNING	JTC	11-11-24	△	PLAN CHECK RESUBMITTAL-PLANNING	JTC	02-04-25	△	BID SET	JTC		△	
6-14-24	△	PLAN CHECK RESUBMITTAL-BUDG	JTC	11-30-24	△	PLAN CHECK RESUBMITTAL-SOILS REPORT	JTC		△				△	



TOPOGRAPHIC SURVEY

16350 FILBERT STREET, SYLMAR, CA 91342

VICINITY MAP



LEGEND

- ASPHALT PAVEMENT
- CONCRETE PAVEMENT
- DOOR
- FIRE HYDRANT
- FOUND MONUMENT AS NOTED
- GATE
- GUARD POST
- HANDICAP
- POWER POLE
- SEWER MANHOLE
- STORM DRAIN MANHOLE
- SIGN
- TREE (TYPICAL)
- TREE STUMP
- TRUNCATED DOME
- WATER METER
- WATER VALVE
- ASSESSOR'S PARCEL NUMBER
- CENTERLINE
- FINISH FLOOR
- FINISH SURFACE
- FLOW LINE
- HANDICAP RAMP
- IRRIGATION CONTROL VALVE
- NATURAL GROUND
- PROPERTY LINE
- RIGHT-OF-WAY
- TOP OF CURB
- TOP OF STRUCTURE
- TOP OF WALL
- BLOCK WALL
- BRICK WALL
- CENTERLINE
- CHAIN LINK FENCE
- EDGE OF PAVEMENT
- INTERIOR LOT LINE
- OVERHANG
- PROPERTY LINE
- RIGHT-OF-WAY
- WROUGHT IRON FENCE

CONTROL POINTS

CP#	NORTHING	EASTING	ELEVATION	DESCRIPTION
CP26	1938224.06'	6415287.35'	1318.13'	SET MAGNETIC NAIL & SHINER
CP28	1937846.29'	6415221.36'	1296.02'	SET SCRIBED X
CP29	1938147.02'	6415664.53'	1285.24'	SET MAGNETIC NAIL & SHINER
CP30	1937416.04'	6415139.40'	1278.28'	SET SCRIBED X
CP32	1937422.94'	6415018.81'	1279.04'	SET MAGNETIC NAIL/TIN
CP33	1937963.20'	6415172.03'	1299.69'	SET 1X2 MAGNETIC NAIL
CP2000	1938085.56'	6415400.32'	1317.22'	SET SCRIBED X
CP2001	1937898.70'	6415364.64'	1304.92'	SET SCRIBED X
CP5100	1937301.26'	6415176.00'	1277.05'	SET MAGNETIC NAIL/SHINER
CP5101	1937352.64'	6415228.38'	1277.87'	SET 2"x2" HUB W/MAGNETIC NAIL
CP10058	1937093.60'	6416371.10'	1269.33'	SET MAGNETIC NAIL
CP10059	1937236.07'	6416470.47'	1275.49'	SET MAGNETIC NAIL & SHINER

NOTE: THIS SURVEY WAS PREPARED WITHOUT THE BENEFIT OF A TITLE REPORT.

REVISIONS			
NO.	DATE	REVISIONS	BY
0	05/09/23	SUBMITTAL	LN/DM
1	04/17/24	ADDITIONAL TOPOGRAPHY	RM/AC

UTILITY STATEMENT

BURIED UTILITIES AND/OR PIPELINES SHOWN HEREON ARE PER VISIBLE AND APPARENT SURFACE EVIDENCE, RECORD DRAWINGS OF THE CONSTRUCTED UTILITY LINES OBTAINED FROM RELIABLE AND RESPONSIBLE SOURCES NOT PROVIDED BY AN INDEPENDENT LOCATING CONTRACTOR. NO GUARANTEE OR WARRANTY, EITHER EXPRESSED OR IMPLIED, IS MADE AS TO THE ACCURACY OR THOROUGHNESS OF SUCH INFORMATION. IF MORE ACCURATE LOCATIONS OF UNDERGROUND UTILITIES OR PIPE LINES ARE REQUIRED, THE UTILITY OR PIPELINE WILL HAVE TO BE VERIFIED BY FIELD POT-HOLING. CALVADA SURVEYING, INC. AND THE SURVEYOR OF RECORD SHALL NOT BE HELD LIABLE FOR THE LOCATION OF OR THE FAILURE TO NOTE THE LOCATION OF NON-VISIBLE UTILITIES OR PIPELINES.

Underground Service Alert

Call: TOLL FREE 1-800-227-2600

TWO WORKING DAYS BEFORE YOU DIG

PREPARED FOR

JTC ARCHITECTS

65 N. 1ST AVENUE, SUITE 201
ARCADIA, CA 91006
PHONE: 626.254.8884

BASIS OF BEARINGS

THE BEARINGS SHOWN HEREON ARE BASED UPON THE CALIFORNIA COORDINATE SYSTEM OF 1983, CCS83, ZONE 5, (2022.75) IN ACCORDANCE TO THE CALIFORNIA PUBLIC RESOURCES CODE SECTIONS 8801-8819; SAID BEARINGS ARE DETERMINED LOCALLY UPON FIELD-OBSERVED TIES TO THE FOLLOWING LEICA SMARTNET NORTH AMERICA (S.N.N.A.) CONTINUOUSLY OPERATING REFERENCE STATIONS (C.O.R.S.):

S.N.N.A. CALS:
NORTHING = 2058541.17' EASTING = 6517447.00'

S.N.N.A. CASC:
NORTHING = 1973008.05' EASTING = 6394682.99'

THE COMBINATION FACTOR FOR THIS PROJECT WAS APPLIED AT THE FOLLOWING POINT:
NORTHING = 1938081.07' EASTING = 6415574.85'

MAPPING ANGLE = -00°16'33" SCALE FACTOR = 1.00010637

BENCHMARK

THE ELEVATIONS SHOWN HEREON ARE BASED UPON THE SMARTNET NORTH AMERICA C.O.R.S. CALS, ELEVATION 2531.43 FEET (NAVD 88).

SITE INFORMATION

SITE NAME: Barry J. Nidorf Secure Youth Track Facility Security and Kitchen Upgrades

ADDRESS: 16350 Filbert St, Sylmar, CA 91342

ASSESSORS PARCEL NO: 2603-010-906

SURVEYOR OF RECORD

FIELD COMPLETION DATE: APRIL 02, 2024.

CAL VADA SURVEYING, INC.


411 Jenks Circle, Suite 205, Corona, CA 92878
Phone: 951-280-9900 Fax: 951-280-9746
Toll Free: 800-CALVADA www.calvada.com

EST. 1989 JOB NO. 23150

C-1.01 SHEET 1 OF 5


TOPOGRAPHIC SURVEY

16350 FILBERT STREET, SYLMAR, CA 91342



TOPOGRAPHIC SURVEY

16350 FILBERT STREET, SYLMAR, CA 91342





LEGEND	
	ASPHALT PAVEMENT
	CONCRETE PAVEMENT
	DOOR
	FIRE HYDRANT
	FOUND MONUMENT AS NOTED
	GATE
	GUARD POST
	HANDICAP
	POWER POLE
	SEWER MANHOLE
	STORM DRAIN MANHOLE
	SIGN
	TREE (TYPICAL)
	TREE STUMP
	TRUNCATED DOME
	WATER METER
	WATER VALVE
	ASSESSOR'S PARCEL NUMBER
	CENTERLINE
	FINISH FLOOR
	FINISH SURFACE
	FLOW LINE
	HANDICAP RAMP
	IRRIGATION CONTROL VALVE
	NATURAL GROUND
	PROPERTY LINE
	RIGHT OF WAY
	TOP OF CURB
	TOP OF STRUCTURE
	TOP OF WALL
	BLOCK WALL
	BRICK WALL
	CENTERLINE
	CHAIN LINK FENCE
	EDGE OF PAVEMENT
	INTERIOR LOT LINE
	OVERHANG
	PROPERTY LINE
	RIGHT-OF-WAY
	WROUGHT IRON FENCE

CONTROL POINTS				
CP#	NORTHING	EASTING	ELEVATION	DESCRIPTION
CP26	1938224.06'	6415287.35'	1318.13'	SET MAGNETIC NAIL & SHINER
CP28	1937846.29'	6415221.36'	1296.02'	SET SCRIBED X
CP29	1938147.02'	6415664.53'	1285.24'	SET MAGNETIC NAIL & SHINER
CP30	1937416.04'	6415139.40'	1278.28'	SET SCRIBED X
CP32	1937422.94'	6415018.81'	1279.04'	SET MAGNETIC NAIL/TIN
CP33	1937963.20'	6415172.03'	1299.69'	SET 1X2 MAGNETIC NAIL
CP2000	1938085.56'	6415400.32'	1317.22'	SET SCRIBED X
CP2001	1937898.70'	6415364.64'	1304.92'	SET SCRIBED X
CP5100	1937301.26'	6415176.00'	1277.05'	SET MAGNETIC NAIL/SHINER
CP5101	1937352.64'	6415228.38'	1277.87'	SET 2"X2" HUB W/MAGNETIC NAIL
CP10058	1937093.60'	6416371.10'	1269.33'	SET MAGNETIC NAIL
CP10059	1937236.07'	6416470.47'	1275.49'	SET MAGNETIC NAIL & SHINER



TOPOGRAPHIC SURVEY

16350 FILBERT STREET, SYLMAR, CA 91342



TOPOGRAPHIC SURVEY


16350 FILBERT STREET, SYLMAR, CA 91342




LEGEND

- ASPHALT PAVEMENT
- CONCRETE PAVEMENT
- DOOR
- FIRE HYDRANT
- FOUND MONUMENT AS NOTED
- GATE
- GUARD POST
- HANDICAP
- POWER POLE
- SEWER MANHOLE
- STORM DRAIN MANHOLE
- SIGN
- TREE (TYPICAL)
- TREE STUMP
- TRUNCATED DOME
- WATER METER
- WATER VALVE
- ASSESSOR'S PARCEL NUMBER
- CENTERLINE
- FINISH FLOOR
- FINISH SURFACE
- FLOW LINE
- HANDICAP RAMP
- ICV
- IRRIGATION CONTROL VALVE
- NATURAL GROUND
- PROPERTY LINE
- RIGHT OF WAY
- TOP OF CURB
- TOP OF STRUCTURE
- TOP OF WALL
- BLOCK WALL
- BRICK WALL
- CENTERLINE
- CHAIN LINK FENCE
- EDGE OF PAVEMENT
- INTERIOR LOT LINE
- OVERHANG
- PROPERTY LINE
- RIGHT-OF-WAY
- WROUGHT IRON FENCE

GRAPHIC SCALE



CONTROL POINTS				
CP#	NORTHING	EASTING	ELEVATION	DESCRIPTION
CP26	1938224.06'	6415287.35'	1318.13'	SET MAGNETIC NAIL & SHINER
CP28	1937846.29'	6415221.36'	1296.02'	SET SCRIBED X
CP29	1938147.02'	6415664.53'	1285.24'	SET MAGNETIC NAIL & SHINER
CP30	1937416.04'	6415139.40'	1278.28'	SET SCRIBED X
CP32	1937422.94'	6415018.81'	1279.04'	SET MAGNETIC NAIL/TIN
CP33	1937963.20'	6415172.03'	1299.69'	SET 1X2 MAGNETIC NAIL
CP2000	1938085.56'	6415400.32'	1317.22'	SET SCRIBED X
CP2001	1937898.70'	6415364.64'	1304.92'	SET SCRIBED X
CP5100	1937301.26'	6415176.00'	1277.05'	SET MAGNETIC NAIL/SHINER
CP5101	1937352.64'	6415228.38'	1277.87'	SET 2"x2" HUB W/MAGNETIC NAIL
CP10058	1937093.60'	6416371.10'	1269.33'	SET MAGNETIC NAIL
CP10059	1937236.07'	6416470.47'	1275.49'	SET MAGNETIC NAIL & SHINER



LEGEND

- (E) FIRE HYDRANT W/ BOLLARDS
- (E) ELECTRICAL PULL BOX
- (E) WALL MOUNTED LIGHT FIXTURE
- (E) SECURITY CAMERA
- (E) GRATED CATCH BASIN COVER

1 SITE PLAN
SCALE: 1"=50'-0"

REFERENCE NOTES

- (1) (E) FIRE HYDRANT WITH TWO BOLLARDS TO REMAIN.
- (2) (E) ELECTRICAL PULL BOX OR PANEL TO REMAIN.
- (3) (E) UNDERGROUND ELECTRICAL CABLE AREA TO REMAIN.
- (4) (E) WALL MOUNTED LIGHT FIXTURE TO REMAIN.
- (5) (E) CONDUIT EXPANSION LOCATION.
- (6) (E) COMBINATION AIR RELEASE VALVE WITH TWO BOLLARDS TO REMAIN.
- (7) (E) SECURITY CAMERAS TO REMAIN.
- (8) (E) MAN HOLE COVER TO REMAIN.
- (9) (E) GRATED CATCH BASIN COVER TO REMAIN.

NO.	DATE	BY	REMARKS
1	11-11-24	JTC	PLAN CHECK SUBMITTAL-BLDG & PLANNING
2	02-04-25	JTC	PLAN CHECK RESUBMITTAL-BLDG

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.




LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :
**BARRY J. NIRDOF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN UPGRADES
PW15739, PCA: P9700230,
PCS ID:2241**

LOCATION :
**16350 FILBERT STREET,
SYLMAR, CA 91342**

ARCHITECT :
**JTC
architects, inc.**
65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net




CONSULTANT :

BID SET

TITLE:
SITE PLAN

SCALE: AS SHOWN
DATE: 02-04-25
DRAWN BY: JT, EP
CHECKED BY: JQ
SHEET NUMBER:

A-1.01



AREAS OF WORK


- 1 SECURITY FENCE NETTING (PERIMETER BLOCK WALLS):
- INSTALL 26'-4" MINIMUM HIGH SECURITY NETTING ON STEEL FRAMES AND POSTS ALONG EXISTING MASONRY BLOCK WALLS (DRIVEWAY AISLES)
 - DRILL PILE FOUNDATION FOR THE MAIN STRUCTURAL POSTS SUPPORTS
- 2 HVAC SYSTEM (AT BUILDING #5):
- INSTALL TWO DIRECT EXPANSION FAN COILS UNITS IN THE DRY FOOD STORAGE ROOM
 - PROVIDE DUCTLESS OUTDOOR CONDENSER UNIT ON THE MAIN ROOF OF KITCHEN

- (E) FIRE HYDRANT W/ BOLLARDS
- (E) ELECTRICAL PULL BOX
- (E) WALL MOUNTED LIGHT FIXTURE
- (E) SECURITY CAMERA
- (E) GRATED CATCH BASIN COVER

- 1 (E) FIRE HYDRANT WITH TWO BOLLARDS TO REMAIN.
- 2 (E) ELECTRICAL PULL BOX OR PANEL TO REMAIN.
- 3 (E) UNDERGROUND ELECTRICAL CABLE AREA TO REMAIN.
- 4 (E) WALL MOUNTED LIGHT FIXTURE TO REMAIN.
- 5 (E) CONDUIT EXPANSION LOCATION.

- 6 (E) COMBINATION AIR RELEASE VALVE WITH TWO BOLLARDS TO REMAIN.
- 7 (E) SECURITY CAMERAS TO REMAIN.
- 8 (E) MAN HOLE COVER TO REMAIN.
- 9 (E) GRATED CATCH BASIN COVER TO REMAIN.

1 SITE PLAN - AREAS OF WORK
SCALE: 1"=50'-0"



THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.



PROJECT :

BARRY J. NIRD OF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN UPGRADES
PW15739, PCA: P9700230,
PCS ID:2241


LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT :

JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-674-7775
E-MAIL : jtcarch@pacbell.net



CONSULTANT :

BID SET

TITLE:

SITE PLAN -
AREAS OF NEW WORK

SCALE: AS SHOWN

DATE: 02-04-25

DRAWN BY: JT, EP

CHECKED BY: JQ

SHEET NUMBER:

A-1.01A



GENERAL NOTES:

1. CONTRACTOR SHALL PERFORM GROUND PENETRATING RADAR TEST BEFORE COMMENCING WORK. DOCUMENT ALL UTILITY LINES THROUGH AS-BUILT PROCESS. INFORM THE ARCHITECT OF FINDINGS.
2. PROTECT AT ALL COST EXISTING STRUCTURES, SURFACES, ON-SITE EQUIPMENTS, ETC DURING CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES INCURRED DUE TO NEGLIGENCE AND OR AS RESULT OF NOT FURTHER INVESTIGATING OR FAMILIARIZING HIMSELF WITH ALL AREAS INVOLVED (NOT ONLY LIMITED TO WORK AREAS)
3. DO NOT BLOCK ANY INGRESS OR EGRESS PATHWAY OF STRUCTURE. PROVIDE A CLEAR AND UNOBSTRUCTED PATH OF TRAVEL DEEMED SAFE AS AN ALTERNATIVE WAY TO AND FROM BUILDING ENTRANCES, IF NECESSARY
4. SUBMIT CONSTRUCTION SAFETY PLAN TO OWNER FOR REVIEW AND APPROVAL
5. VERIFY LOCATION FOR APPROVAL WITH OWNER FOR STAGING AREA AS REQUIRED FOR TEMPORARY STORAGE OF DEBRIS REMOVED AND STORAGE FOR SUPPLY OF MATERIALS. CONTRACTOR TO PATCH & REPAIR ANY DAMAGED PORTION OF AFFECTED AREA AS A RESULT OF TEMPORARY STAGING AREA
6. ALL CONCRETE CURB AND GUTTER FLOWLINES WITH LESS THAN ONE PERCENT SHALL BE WATER TESTED PRIOR TO FINAL FINISHING TO ENSURE PROPER DRAINAGE W/O UNACCEPTABLE HIGH OR LOW SPOTS.

8. ALL UTILITY TRENCH BACKFILL AND COMPACTION INSPECTION BE PERFORMED IN ACCORDANCE WITH STATE AND FEDERAL REGULATIONS.

10. CONTRACTOR SHALL MAINTAIN ADJACENT STREETS IN A NEAT, CLEAN, DUST-FREE, AND SANITARY CONDITION AT ALL TIMES AND TO THE SATISFACTION OF THE OWNER. THE ADJACENT AREAS SHALL BE KEPT CLEAN OF DEBRIS, WITH DUST AND OTHER NUISANCE BEING CONTROLLED AT ALL TIMES. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY CLEAN-UP ON ADJACENT STREETS AFFECTED CONSTRUCTION. METHOD OF STREET CLEANING SHALL BE BY DRY SWEEPING OF ALL PAVED AREAS. NO STOCKPILING OF BLDG MATERIALS WILL BE ALLOWED WITHIN THE STREET RIGHT-OF-WAY WITHOUT THE PERMISSION OF THE OWNER.

11. TRAFFIC FLOWS SHALL BE MAINTAINED AT ALL TIMES AND PROTECTED WITH ADEQUATE BARRICADES, LIGHTS, SIGNS, AND WARNING DEVICES IN ACCORDANCE WITH THE CURRENT STATE OF CALIFORNIA, DEPARTMENT OF TRANSPORTATION, TRAFFIC MANUAL AND TO OWNER.



12. IRRIGATION LINES SHALL BE REMOVED, RELOCATED OR RECONSTITUTED AS NECESSARY, INSRTALL PER LATEST STANDARDS

1. CONTRACTOR SHALL NOTIFY ALL OF HIS SUBCONTRACTORS THAT DUMPING OF CHEMICALS INTO THE STORM DRAIN SYSTEM OR THE WATERSHED IS PROHIBITED.


2. CONTRACTOR SHALL MAINTAIN CONSTRUCTION SITE IN SUCH CONDITION THAT AN ANTICIPATED STORM DOES NOT CARRY WASTES OR POLLUTANTS OFF THE SITE. POTENTIAL POLLUTANTS INCLUDE BUT ARE NOT LIMITED TO: SOLID OR LIQUID CHEMICAL SPILLS; WASTES FROM PAINTS, STAINS, SEALANT, GLUES, LIMES, PESTICIDES, HERBICIDES, WOOD PRESERVATIVES AND SOLVENTS; ASBESTOS FIBERS, PAINTS FLAKES OR STUCCO FRAGMENTS; FUELS, OILS, LUBRICANTS, AND HYDRAULIC FLUIDS; RADIATOR FLUIDS; FERTILIZERS, VEHICLE/EQUIPMENT WASH WATER AND CONCRETE WASH WATER; CONCRETE, DETERGENT OR FLOATABLE WASTES; WASTES FROM ANY ENGINE/EQUIPMENT STEAM CLEANING OR CHEMICAL DEGREASING; AND SUPERCHLORINATED POTABLE WATER LINE FLUSHINGS.

3. DURING CONSTRUCTION, CONTRACTOR SHALL DISPOSE OF SUCH MATERIALS IN A SPECIFIED AND CONTROLLED TEMPORARY AREA ON-SITE, PHYSICALLY SEPARATED FROM POTENTIAL STORM WATER RUNOFF, WITH ULTIMATE DISPOSAL IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REQUIREMENTS.


4. DEWATERING OF CONTAMINATED GROUNDWATER, OR DISCHARGING CONTAMINATED SOILS VIA SURFACE EROSION IS PROHIBITED. DEWATERING OF NON-CONTAMINATED GROUNDWATER REQUIRES AN APPROVAL FROM THE OWNER.




3 **INTERIOR NORTH SECURITY PLAN (WALL B) - EXISTING**
SCALE: 1/16"=1'-0"



2 PARTIAL EXTERIOR WEST SECURITY PLAN (WALL A) - EXISTING
SCALE: 1/16"=1'-0"



1 PARTIAL EXTERIOR WEST SECURITY PLAN (WALL A) - EXISTING
SCALE: 1/16"=1'-0"



PROJECT :

BARRY J. NIRDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN UPGRADES
PW15739, PCA: P9700230,
PCS ID:2241

LOCATION :

**16350 FILBERT STREET,
SYLMAR, CA 91342**

ARCHITECT




JTC
architects, inc.

**65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006**
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.00

SEAI :



CONSULTANT :

BID SET

TITLE	
-------	--

**PARTIAL ENLARGED SITE PLANS
- EXISTING FOR REFERENCE**

SCALE:	AS NOTED
--------	----------


DATE: 02-04-25

DRAWN BY: JY

CHECKED BY: JG

SHEET NUMBER:

A-1.02



**BARRY J. NIRDOLF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN UPGRADES
PW15739, PCA: P9700230,
PCS ID:2241**

**16350 FILBERT STREET,
SYLMAR, CA 91342**



JTC
architects, inc.

**65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006**

TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D

SEAL :



TITLE:

**PARTIAL ENLARGED SITE PLANS
- EXISTING FOR REFERENCE**

SCALE: AS NOTED

DATE: 02-04-25

DRAWN BY: JY, EP

CHECKED BY: JQ

SHEET NUMBER:

A-1.03

1. EQUIPMENT AND WORKERS FOR EMERGENCY WORK SHALL BE MADE AVAILABLE AT ALL TIMES DURING THE RAINY SEASON. NECESSARY MATERIALS SHALL BE AVAILABLE ONSITE OR STOCKPILED AT CONVENIENT LOCATIONS TO FACILITATE RAPID CONSTRUCTION OF TEMPORARY DEVICES WHEN RAIN IS IMMINENT.
2. EROSION CONTROL DEVICES SHALL NOT BE MOVED OR MODIFIED WITHOUT THE APPROVAL OF THE OWNER.
3. ALL REMOVABLE EROSION PROTECTIVE DEVICES SHALL BE IN PLACE AT THE END OF EACH WORKING DAY WHEN THE 5-DAY RAIN PROBABILITY FORECAST EXCEEDS 40 PERCENT.
4. AFTER A RAINSTORM, ALL SILT AND DEBRIS SHALL BE REMOVED FROM STREETS, CHECK BERMS, AND BASINS.
5. GRADED AREAS ON THE PERMITTED AREA PERIMETER MUST DRAIN AWAY FROM THE FACE OF SLOPES AT THE CONCLUSION OF EACH WORKING DAY. DRAINAGE TO BE DIRECTED TOWARD DESILTING FACILITIES.
6. THE CONTRACTOR SHALL BE RESPONSIBLE AND TAKE NECESSARY PRECAUTIONS TO PREVENT PUBLIC TRESPASS ONTO AREAS WHERE IMPOUNDED WATER CREATES A HAZARDOUS CONDITION.

- CONTRACTOR SHALL PERFORM GROUND PENETRATING RADAR TEST BEFORE COMMENCING WORK. DOCUMENT ALL UTILITY LINES THROUGH AS-BUILT PROCESS. INFORM THE ARCHITECT OF FINDINGS.
2. PROTECT AT ALL COST EXISTING STRUCTURES, SURFACES, ON-SITE EQUIPMENTS, ETC DURING CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES INCURRED DUE TO NEGLIGENCE AND OR AS RESULT OF NOT FURTHER INVESTIGATING OR FAMILIARIZING HIMSELF WITH ALL AREAS INVOLVED (NOT ONLY LIMITED TO WORK AREAS)
3. DO NOT BLOCK ANY INGRESS OR EGRESS PATHWAY OF STRUCTURE. PROVIDE A CLEAR AND UNOBSTRUCTED PATH OF TRAVEL DEEMED SAFE AS AN ALTERNATIVE WAY TO AND FROM BUILDING ENTRANCES, IF NECESSARY
4. SUBMIT CONSTRUCTION SAFETY PLAN TO OWNER FOR REVIEW AND APPROVAL
5. VERIFY LOCATION FOR APPROVAL WITH OWNER FOR STAGING AREA AS REQUIRED FOR TEMPORARY STORAGE OF DEBRIS REMOVED AND STORAGE FOR SUPPLY OF MATERIALS. CONTRACTOR TO PATCH & REPAIR ANY DAMAGED PORTION OF AFFECTED AREA AS A RESULT OF TEMPORARY STAGING AREA
6. ALL CONCRETE CURB AND GUTTER FLOWLINES WITH LESS THAN ONE PERCENT SHALL BE WATER TESTED PRIOR TO FINAL FINISHING TO ENSURE PROPER DRAINAGE W/O UNACCEPTABLE HIGH OR LOW SPOTS.

COORDINATE WITH THE OWNER TO ACQUIRE AN ENCROACHMENT PERMIT (IF APPLICABLE) TO PERFORM WORK WITHIN THE STREET/COMMON PARKING RIGHT-OF-WAY

8. ALL UTILITY TRENCH BACKFILL AND COMPACTION INSPECTION BE PERFORMED IN ACCORDANCE WITH STATE AND FEDERAL REGULATIONS.
9. ALL DAMAGED CONCRETE SIDEWALKS OR CURBS SHALL BE SAW CUT TO THE NEAREST TRANSVERSE SCORE MARK, OR ADJUSTABLE CONTROL JOINT, OR WEAKENED PLANE JOINT AND REPLACED IN CONFORMANCE WITH THE LATEST STANDARDS.
10. CONTRACTOR SHALL MAINTAIN ADJACENT STREETS IN A NEAT, CLEAN, DUST-FREE, AND SANITARY CONDITION AT ALL TIMES AND TO THE SATISFACTION OF THE OWNER. THE ADJACENT AREAS SHALL BE KEPT CLEAN OF DEBRIS, WITH DUST AND OTHER NUISANCE BEING CONTROLLED AT ALL TIMES. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY CLEAN-UP ON ADJACENT STREETS AFFECTED CONSTRUCTION. METHOD OF STREET CLEANING SHALL BE BY DRY SWEEPING OF ALL PAVED AREAS. NO STOCKPILING OF BLDG MATERIALS WILL BE ALLOWED WITHIN THE STREET RIGHT-OF-WAY WITHOUT THE PERMISSION OF THE OWNER.
11. TRAFFIC FLOWS SHALL BE MAINTAINED AT ALL TIMES AND PROTECTED WITH ADEQUATE BARRICADES, LIGHTS, SIGNS, AND WARNING DEVICES IN ACCORDANCE WITH THE CURRENT STATE OF CALIFORNIA, DEPARTMENT OF TRANSPORTATION, TRAFFIC MANUAL AND TO OWNER.
12. IRRIGATION LINES SHALL BE REMOVED, RELOCATED OR RECONSTRUCTED AS NECESSARY, INSTALLED PER LATEST STANDARDS

1. CONTRACTOR SHALL NOTIFY ALL OF HIS SUBCONTRACTORS THAT DUMPING OF CHEMICALS INTO THE STORM DRAIN SYSTEM OR THE WATERSHED IS PROHIBITED.
2. CONTRACTOR SHALL MAINTAIN CONSTRUCTION SITE IN SUCH CONDITION THAT AN ANTICIPATED STORM DOES NOT CARRY WASTES OR POLLUTANTS OFF THE SITE. POTENTIAL POLLUTANTS INCLUDE BUT ARE NOT LIMITED TO: SOLID OR LIQUID CHEMICAL SPILLS; WASTES FROM PAINTS, STAINS, SEALANT, GLUES, LIMES, PESTICIDES, HERBICIDES, WOOD PRESERVATIVES AND SOLVENTS; ASBESTOS FIBERS, PAINTS FLAKES OR STUCCO FRAGMENTS; FUELS OILS, LUBRICANTS, AND HYDRAULIC, RADIATOR, OR BATTERY FLUIDS FERTILIZERS, VEHICLE/EQUIPMENT WASH WATER AND CONCRETE WASH WATER; CONCRETE, DETERGENT OR FLOATABLE WASTES; WASTES FROM ANY ENGINE/EQUIPMENT STEAM CLEANING OR CHEMICAL DEGREASING; AND SUPERCHLORINATED POTABLE WATER LINE FLUSHINGS.
3. DURING CONSTRUCTION, CONTRACTOR SHALL DISPOSE OF SUCH MATERIALS IN A SPECIFIED AND CONTROLLED TEMPORARY AREA ON-SITE, PHYSICALLY SEPARATED FROM POTENTIAL STORM WATER RUNOFF, WITH ULTIMATE DISPOSAL IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REQUIREMENTS.
4. DEWATERING OF CONTAMINATED GROUNDWATER, OR DISCHARGING CONTAMINATED SOILS VIA SURFACE EROSION IS PROHIBITED. DEWATERING OF NON-CONTAMINATED GROUNDWATER REQUIRES AN APPROVAL FROM THE OWNER.

[illegible]

A circle with a shaded sector. The central angle is labeled 'Z'.

A diagram showing a circle with an inscribed triangle. One of the interior angles of the triangle is bisected by a line segment that extends to the circumference of the circle. This construction is used to illustrate the relationship between the angle bisector and the arcs it subtends.



5

REFERENCE NOTES

4

3

1

2

**AD-2.01**





REFERENCE NOTES:

1	(N) NESTING WIRE MESH ON STEEL FRAME SUPPORT SYSTEM (12" MIN ABOVE WALL). SEE STRUCT
2	(E) CONCRETE MASONRY BLOCK WALLS
3	(E) CONCRETE MASONRY BLOCK PILASTERS
4	(E) FINISHED SURFACE
5	REMOVE (E) RAZOR WIRE AND SUPPORT IN THEIR ENTIRETY. CUT AND GRIND SMOOTH ALL CONNECTORS FLUSHED WITH TOP OR SIDE OF WALLS
6	(E) MOTORIZED STEEL GATE
7	(E) OVERHEAD HOUSING WITH STEEL SUPPORTS
8	(E) CHAINLINK FENCE BARRIER
9	(E) TRASH ENCLOSURE
10	(E) CONCRETE APRON BELOW
11	(E) CONCRETE SLAB ON GRADE BELOW
12	(E) CHW LINES ON METAL SUPPORTS TO REMAIN. PROTECT-IN-PLACE DURING CONSTRUCTION. CONTRACTOR TO REPLACE AT NO COST TO OWNER DUE TO NEGLIGENCE
13	(E) UNDERGROUND ELECTRICAL CABLE AREA TO REMAIN
14	(E) UTILITY READOUT/METER. PROTECT-IN-PLACE DURING CONSTRUCTION
15	(E) UNDERGROUND WATER LINE SHOWN DASHED FOR REFERENCE. LOCATE LINES AS REQUIRED FOR REFERENCE

1. CONTRACTOR SHALL PERFORM GROUND PENETRATING RADAR TEST BEFORE COMMENCING WORK. DOCUMENT ALL UTILITY LINES THROUGH AS-BUILT PROCESS. NOTIFY OWNER AND ARCHITECT FOR ANY CONFLICTS DUE TO FINDINGS AGAINST DESIGN INTENT.
2. PROTECT AT ALL COST EXISTING STRUCTURES, SURFACES, ON-SITE EQUIPMENTS, ETC DURING CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES INCURRED DUE TO NEGLIGENCE AND OR AS RESULT OF NOT FURTHER INVESTIGATING OR FAMILIARIZING HIMSELF WITH ALL AREAS INVOLVED (NOT ONLY LIMITED TO WORK AREAS)
3. DO NOT BLOCK ANY INGRESS OR EGRESS PATHWAY OF STRUCTURE. PROVIDE A CLEAR AND UNOBSTRUCTED PATH OF TRAVEL DEEMED SAFE AS AN ALTERNATIVE WAY IN AND FROM BUILDING ENTRANCES, IF NECESSARY
4. SUBMIT CONSTRUCTION SAFETY PLAN TO OWNER FOR REVIEW AND APPROVAL
6. REFER TO CIVIL DRAWINGS FOR ADDITIONAL INFO ON UTILITIES, ITEMS ON WALLS (I.E. LIGHTY, CAMERAS, ETC.).
7. EXTREME CAUTION SHALL BE EXERCISED WHEN WORKING AROUND HIGH/LOW VOLTAGE ELEC CONDUITS ON BLOCK WALLS. REFER TO NOTE 4 ABOVE ON SAFETY PLAN SUBMITTAL REQUIREMENT

1. DURING BID PHASE, SUBMIT THRU RFIs ITEMS WHICH ARE QUESTIONABLE EITHER TO BE REMOVED THEN REINSTALLED OR TO REMAIN IN PLACE. IF NECESSARY, BIDDERS CAN REQUEST FOR A 2ND WALK-THRU TO ELIMINATE CHANGE ORDERS DURING CONSTRUCTION PHASE.
2. CONTRACTOR SHALL COORDINATE WITH OWNER ANY UTILITIES/FIXTURES THAT NEED TO BE REMOVED AND RELOCATED TO ALLOW FOR STEEL FRAME AND COLUMN CONSTRUCTION.
3. EXISTING LIGHT FIXTURES BEHIND PROPOSED NETTING PANELS SHALL BE RELOCATED BELOW HORIZONTAL STEEL FRAMES (REFER TO A-3.02 AND A-3.02A FOR WALL ELEVATIONS), MODIFY EXISTING METAL WALL COVERS FOR CONDUITS AND ALL AFFECTED ACCESSORIES AT THEIR NEW LOCATIONS.



BARRY J. NIRDOLF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN UPGRADES
PW15739, PCA: P9700230,
PCS ID:2241

**16350 FILBERT STREET,
SYLMAR, CA 91342**



JTC
architects, inc.

**65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006**


TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

BID SET


TITLE:

**SECURITY WALL PLANS
(WALLS A AND B) - NEW WORK**


A-3.01



3 EXTERIOR EAST SECURITY PLAN (WALL D) - NEW WORK
SCALE: 1/16"=1'-0"



2 PARTIAL EXTERIOR EAST SECURITY PLAN (WALL C) - NEW WORK
SCALE: 1/16"=1'-0"




1 PARTIAL EXTERIOR EAST SECURITY PLAN (WALL C) - NEW WORK
SCALE: 1/16"=1'-0"

- LEGEND:**
- (E) FIRE HYDRANT W/ BOLLARDS
 - DPB(E) (E) ELECTRICAL PULL BOX
 - LIGHT(E) (E) WALL MOUNTED LIGHT FIXTURE
 - 1.1 (E) SECURITY CAMERA

- REFERENCE NOTES:**
- (N) SECURITY WIRE MESH ON STEEL FRAME SUPPORT SYSTEM (12' MIN ABOVE WALL). SEE STRUCT
 - (E) CONCRETE MASONRY BLOCK WALLS
 - (E) CONCRETE MASONRY BLOCK PILASTERS
 - (E) FINISHED SURFACE
 - (E) RAZOR WIRE TO REMAIN
 - (E) MOTORIZED STEEL GATE
 - (E) OVERHEAD HOUSING, PROTECT-IN-PLACE DURING CONSTRUCTION
 - (E) CHAINLINK FENCE BARRIER
 - (E) TRASH ENCLOSURE
 - (E) CONCRETE APRON BELOW
 - (E) CONCRETE SLAB ON GRADE BELOW
 - (E) CHW LINES ON METAL SUPPORTS TO REMAIN. PROTECT-IN-PLACE DURING CONSTRUCTION. CONTRACTOR TO REPLACE AT NO COST TO OWNER DUE TO NEGLIGENCE.
 - (E) UNDERGROUND ELECTRICAL CABLE AREA TO REMAIN
 - (E) UTILITY READOUT/METER. PROTECT-IN-PLACE DURING CONSTRUCTION
 - (E) UNDERGROUND WATER LINE SHOWN DASHED FOR REFERENCE. LOCATE LINES AS REQUIRED FOR REFERENCE

- GENERAL NOTES:**
- CONTRACTOR SHALL PERFORM GROUND PENETRATING RADAR TEST BEFORE COMMENCING WORK. DOCUMENT ALL UTILITY LINES THROUGH AS-BUILT PROCESS. NOTIFY OWNER AND ARCHITECT FOR ANY CONFLICTS DUE TO FINDINGS AGAINST DESIGN INTENT.
 - PROTECT AT ALL COST EXISTING STRUCTURES, SURFACES, ON-SITE EQUIPMENTS, ETC DURING CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGES INCURRED DUE TO NEGLIGENCE, OR AS RESULT OF NOT FURTHER INVESTIGATING OR FAMILIARIZING HIMSELF WITH ALL AREAS INVOLVED (NOT ONLY LIMITED TO WORK AREAS)
 - DO NOT BLOCK ANY INGRESS OR EGRESS PATHWAY OF STRUCTURE. PROVIDE A CLEAR AND UNOBSTRUCTED PATH OF TRAVEL DEEMED SAFE AS AN ALTERNATIVE WAY TO AND FROM BUILDING ENTRANCES, IF NECESSARY
 - SUBMIT CONSTRUCTION SAFETY PLAN TO OWNER FOR REVIEW AND APPROVAL
 - REFER TO CIVIL DRAWINGS FOR ADDITIONAL INFO ON UTILITIES, ITEMS ON WALLS (I.E. LIGHTS, CAMERAS, ETC.).
 - EXTREME CAUTION SHALL BE EXERCISED WHEN WORKING AROUND HIGH/LOW VOLTAGE ELEC CONDUITS ON BLOCK WALLS. REFER TO NOTE 4 ABOVE ON SAFETY PLAN SUBMITTAL REQUIREMENT

- NOTES OF IMPORTANCE:**
- DURING BID PHASE, SUBMIT THRU RFIs ITEMS WHICH ARE QUESTIONABLE EITHER TO BE REMOVED THEN REINSTALL OR TO REMAIN IN PLACE. IF NECESSARY, BIDDERS CAN REQUEST FOR A 2ND WALK-THRU TO ELIMINATE CHANGE ORDERS DURING CONSTRUCTION PHASE.
 - CONTRACTOR SHALL COORDINATE WITH OWNER ANY UTILITIES/FIXTURES THAT NEED TO BE REMOVED AND RELOCATED TO ALLOW FOR STEEL FRAME AND COLUMN CONSTRUCTION.
 - EXISTING LIGHT FIXTURES BEHIND PROPOSED NETTING PANELS SHALL BE RELOCATED BELOW HORIZONTAL STEEL FRAMES (REFER TO A-3.02 AND A-3.02A FOR WALL ELEVATIONS). MODIFY EXISTING METAL WALL COVERS FOR CONDUITS AND ALL AFFECTED ACCESSORIES AT THEIR NEW LOCATIONS.



NO.	DATE	BY	REMARKS
1	11-11-24	JTC	PLAN CHECK SUBMITTAL-PLANNING
2	02-04-25	JTC	PLAN CHECK RESUBMITTAL-BLDG
3	02-04-25	JTC	BID SET

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.

PUBLIC WORKS

LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :

**BARRY J. NIDDOF
SECURE YOUTH TRACK FACILITY
PW15739, PCA: P9700230,
PCS ID:2241**

LOCATION :

**16350 FILBERT STREET,
SYLMAR, CA 91342**

ARCHITECT :

**JTC
architects, inc.**

**65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006**
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: **37603.0D**

SEAL :

W. HUANG ARCHITECT
33750
REV. 06-30-25
STATE OF CALIFORNIA

CONSULTANT :

BID SET

TITLE:


**SECURITY WALL PLANS
(WALLS C AND D) - NEW WORK**


SCALE: AS NOTED
DATE: 02-04-25
DRAWN BY: JT, EP
CHECKED BY: JQ
SHEET NUMBER:

A-3.01A




- ## KEY PLAN






3 EXTERIOR EAST SECURITY ELEVATION (WALL D) - NEW WORK
SCALE: 1/16"=1'-0"




2 PARTIAL EXTERIOR EAST SECURITY ELEVATION (WALL C) - NEW WORK
SCALE: 1/16"=1'-0"



1 PARTIAL EXTERIOR EAST SECURITY ELEVATION (WALL C) - NEW WORK
SCALE: 1/16"=1'-0"

REFERENCE NOTES:

- 1 (N) SECURITY NYLON MESH ON STEEL FRAME SUPPORT SYSTEM (12' MIN ABOVE WALL). SEE STRUCT
- 2 (E) CONCRETE MASONRY BLOCK WALLS
- 3 (E) CONCRETE MASONRY BLOCK PILASTERS
- 4 (E) FINISHED SURFACE
- 5 (E) RAZOR WIRE TO REMAIN
- 6 (E) MOTORIZED STEEL GATE
- 7 (E) OVERHEAD HOUSING. PROTECT-IN-PLACE DURING CONSTRUCTION
- 8 (E) CHAINLINK FENCE BARRIER
- 9 (E) CONCRETE MASONRY BLOCK PILASTERS (ON OTHER SIDE SHOWN DASHED WHERE APPLIES FOR REFERENCE)
- 10 (N) AIRCRAFT CABLE DIAGONALLY PLACED AND SUPPORTED THRU EYE BOLTS. SEE 5 A3.03
- 11 (E) WALL MOUNTED LIGHT FIXTURE RELOCATE AS NEEDED PER ELEVATIONS
- 12 (E) FIRE HYDRANT WITH STEEL BOLLARDS. PROTECT-IN-PLACE DURING CONSTRUCTION
- 13 (E) SECURITY CAMERA. PROTECT-IN-PLACE DURING CONSTRUCTION
- 14 (E) WALL ACCESSORIES (I.E. SENSORS, COMMUNICATION BOXES, ETC.) TO BE RELOCATED BELOW STEEL FRAME PANELS. COORDINATE WITH OWNER FOR EXTENT OF RELOCATION
- 15 (E) CONDUITS AND PULL BOXES. PROTECT-IN-PLACE DURING CONSTRUCTION
- 16 (E) CONCRETE CURB
- 17 (E) ALUMINUM COVER FOR CONDUITS. CUT AS NECESSARY FOR RELOCATION OF AFFECTED (E) LIGHT FIXTURES



KEY PLAN

DATE:	NO.	REVISIONS:	BY:
5-10-24	1		
6-14-24	2		
DATE:	NO.	REVISIONS:	BY:
11-11-24	1		JTC
02-04-25	2		JTC
DATE:	NO.	REVISIONS:	BY:
02-04-25	1		JTC
DATE:	NO.	REVISIONS:	BY:
02-04-25	1		JTC

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.

PUBLIC WORKS

LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :

BARRY J. NRDOP
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN UPGRADES
PW15739, PCA: P9700230,
PCS ID:2241

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT :

JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: **37603.0D**

SEAL :

LIANG HUANG ARCHITECT
33750
REV. 06-30-25
STATE OF CALIFORNIA

CONSULTANT :


BID SET

TITLE:

SECURITY WALL ELEVATIONS
(WALLS C AND D) - NEW WORK

SCALE: AS NOTED
DATE: 02-04-25
DRAWN BY: JT, EP
CHECKED BY: JQ
SHEET NUMBER:

A-3.02A




- 1 (N) SECURITY FIRE RETARDANT NYLON MESH ON STEEL FRAME SUPPORT SYSTEM (14'-6" TO 15'-0" MAX HIGH). SEE STRUCT. (NOTE: SECURE NYLON MESH TO AIRCRAFT CABLE WITH SECURED-TAMPER PROOF CONNECTOR AS RECOMMENDED BY NYLON MESH MANUFACTURER)
- 2 (E) CONCRETE MASONRY BLOCK WALLS
- 3 (E) FINISHED SURFACE
- 4 (E) TOP OF MASONRY WALL
- 5 (N) STEEL COLUMNS AND STEEL SUPPORTS SEE STRUCT
- 6 (N) STEEL SUPPORTS. SEE STRUCT
- 7 (E) CHW LINES ON METAL SUPPORTS. PROTECT-IN-PLACE DURING CONST.
- 8 (N) $\frac{3}{8}$ " DIA GALVANIZED AIRCRAFT CABLE WIRES ATTACHED TO WELDED EYEBOLTS TO STEEL MEMBERS WITH SECURED-TAMPER PROOF CONNECTORS












1. STRETCH AIRCRAFT CABLE WIRES DIAGONAL, VERTICAL AND HORIZONTAL FOR TENSION WITH TURNBUCKLES, ETC. BEFORE SECURING TO WELDED EYEBOLTS. SECURE NYLON MESH AFTERWARDS WITH SECURED-TAMPER PROOF CONNECTORS
2. ALL STRUCTURAL STEEL ELEMENTS AND COMPONENTS OF THE STEEL FRAMING SHALL BE HOT-DIP GALVANIZED. ANY SCRATCHES DURING STEEL ERECTION SHALL BE HOT-DIP GALVANIZED.
3. SAFETY NET SHALL BE EQUIPPED WITH EDGE ROPE AND ROPES THAT ARE ADDED AND INTEGRATED TO THE NET ALIGNED WITH THE STEEL FRAMING MEMBERS TO REINFORCE THE TIES OF NET TO THE PRESET AIRCRAFT CABLES. QUICK LINKS OF APPROPRIATE SIZE WITH ARCHITECT/ENGINEERS PRIOR APPROVAL SHALL BE USED TO TIE THE NET ROPES, NO MORE THAN 4' ON CENTER.
4. RUN $\frac{5}{16}$ " ϕ 7x19 AIRCRAFT CABLE FOR SAFETY NET, ALONG STEEL FRAMING MEMBER THROUGH CABLE HOLDERS (EYEBOLTS)
5. STRETCH AND TENSION AIRCRAFT CABLES THAT ALIGN WITH STEEL FRAMING MEMBERS IN BOTH LONGITUDINAL AND TRANSVERSE DIRECTIONS UP TO NO MORE THAN 500 POUNDS. PREVENT CABLE FROM SLIDING BY APPLYING CABLE CLAMPS TO MACHINE EYEBOLTS
6. SECURE SAFETY NET TO $\frac{5}{16}$ " ϕ AIRCRAFT CABLE USING TAMPER PROOF CONNECTOR PROVIDED BY NET VENDOR.
7. ALL AIRCRAFT CABLE AND CONNECTIONS SHALL BE HOT DIPPED GALVANIZED.
8. REGULAR EYEBOLT FOR AIRCRAFT CABLE AND SUPPORT OF SAFETY NET ALONG PERIMETER SHALL BE INSTALLED IN CONCRETE NO MORE THAN 4'-0" ON CENTER, AND AT ALL WALL CORNERS AND TURNS
9. CONTRACTOR TO PROVIDE WITH SHACKLES, THIMBLES AND CLIPS PER VENDOR'S RECOMMENDATION FOR CABLE INSTALLATION AND TURNBUCKLE FOR STRETCHING.
10. ALL FITTINGS AND HARDWARE USED FOR CABLE ASSEMBLY SHALL MEET CAPACITY REQUIREMENT EQUAL OR SUPERIOR TO THE AIRCRAFT CABLE CAPACITY.

REMARKS:						REMARKS:					
DATE:	NO.		BY:	DATE:	NO.	DATE:	NO.		BY:	DATE:	NO.
5-10-24	A	PLAN CHECK SUBMITTAL-BUDG & PLANNING	JTC	11-11-24	A		A				A
6-14-24	B	PLAN CHECK RESUBMITTAL-BUDG	JTC	02-04-25	A		B				A



A-3.03

H:\2023\210203 Drawings\2023-02-21 10:00 S-0.01 STRUCTURAL NOTES AND ABBREVIATIONS.dwg PLOTTED BY: Sami Alota ON: September 26, 2024

PLAN SYMBOLS		
SYMBOL	DESCRIPTION	
	APPROXIMATE LOCATION OF SLEEVE FOR PIPES/ CONDUIT ACROSS FOOTING PER PLUMBING, ELECTRICAL OR MECHANICAL.	
	BOTTOM OF FOOTING ELEVATION AT NOTED LOCATION	
	STEP IN FOOTING	
	FOOTING PER FOOTING SCHEDULE	
	STEEL COLUMN STARTING AT THIS LEVEL PER COLUMN SCHEDULE, WHERE NO COLUMN TYPE IS INDICATED, COLUMN CONTINUES FROM LEVEL BELOW.	
	STEEL COLUMN STARTING AT THIS LEVEL WHERE NO COLUMN TYPE IS INDICATED, COLUMN CONTINUES FROM LEVEL BELOW.	
	BEAM SIZE AND SPAN	
	OPENINGS IN FLOOR OR ROOF PER ARCHITECTURAL OR MECHANICAL DRAWINGS	
	MECHANICAL UNIT ABOVE FRAMING (SOLID) OR BELOW FRAMING (DASHED) PER MECHANICAL DRAWINGS	

ABBREVIATIONS:

CODES/INSTITUTIONS/ASSOCIATIONS

ACI	AMERICAN CONCRETE INSTITUTE
AFAPA	(NDS) AMERICAN FOREST & PAPER ASSOCIATION (NDS)
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION
ASIS	AMERICAN IRON AND STEEL INSTITUTE
APA-EWA	APA-ENGINEERED WOOD ASSOCIATION
ASCE	AMERICAN SOCIETY OF CIVIL ENGINEERS
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS
AWC	AMERICAN WELDING SOCIETY
CBS	CALIFORNIA BUILDING CODE
CRSI	CONCRETE REINFORCING STEEL INSTITUTE
DCA	DIVISION OF THE STATE ARCHITECT
HSA	DEPARTMENT OF HEALTH CARE ACCESS AND INFORMATION
IDA	INTERNATIONAL BUILDING CODE
NDS	NATIONAL DESIGN SPECIFICATIONS
ISI	STEEL DECK INSTITUTE
ISI	STEEL JOIST INSTITUTE
SISMA	STEEL STUD MANUFACTURERS ASSOCIATION

SYMBOLS		POUNDS	LBS
#	POUND, NUMBER, QUANTITY		
@	AT		
<	LESS THAN	LL	
>	GREATER THAN	LLH	
±	PLUS OR MINUS	LLV	
°	DEGREE	LOCOS	
Ø	DIAMETER	LONG	

ABBREVIATIONS		POUNDS	LBS
AB	ANCHOR BOLT	LTWT	
ABV	ABOVE	LWT	
ADJ	ADJACENT	MANUF	
ALT	ALTERNATE	MAX	
ANCH	ANCHOR, ANCHORAGE	MECHANICAL	
APPROX	APPROXIMATE, APPROXIMATELY	MHP	
ARCH	ARCHITECT, ARCHITECTURAL	MID	
		MIN	

BEL	BELOW	N	NEW
BLDG	BUILDING	NTS	NOT APPLICABLE
BLOCK	BLOCKING, BLOCK	NVA	NOT TO SCALE
BLDG	BLOCKING, BLOCK	NVA	NOT TO SCALE
BSM	BEAM	NWT	NORMAL-WEIGHT
BOT	BOTTOM		
BOT	BOTTOM OF		
BTWN	BETWEEN	OF	OUTSIDE FACE
		OC	ON CENTER
		OP	OPPOSITE HAND
		OP	OPPOSITE

CALCS	CALCULATIONS	OPNG	OPENING
CFRP	CARBON FIBER REINFORCED POLYMER	OPNG	OPENING
CG	CENTER OF GRAVITY	OPNG	OPENING
CENTERLINE	CENTERLINE	OPNG	OPENING
CLR	CLEAR, CLEARANCE	OPNG	OPENING
CMU	CONCRETE MASONRY UNIT	OPNG	OPENING
CML	COLUMN	OPNG	OPENING
CONC	CONCRETE	OPNG	OPENING
CONN	CONNECT, CONNECTION	OPNG	OPENING
CONT	CONTINUOUS	OPNG	OPENING
COORD	COORDINATE	OPNG	OPENING
CTR	CENTER	OPNG	OPENING

db	BAR DIAMETER (REBAR)	QTY	QUANTITY
DBL	DOUBLE		
DET	DETAIL		
DIAM	DIAMETER		
DIAG	DIAGONAL		
DIM	DIMENSION		
DIST	DISTANCE		
DRAWING	DRAWING		

(E)	EXISTING	SCHED	SCHEDULE
EA	EACH	SEOR	STRUCTURAL ENGINEER OF RECORD
EAC	EACH FACE	SHGT	SHEATHING
ELEC	ELECTRICAL	SH	SIMILAR
EMBED	EMBED, EMBEDDED, EMBEDMENT	SMS	SHEET METAL SCREW
ENG	ENGINEER OF RECORD	SG	SLAB-ON-GRADE
EOR	EQUAL, EQUALLY	SPA	SPACED, SPACING
EQUIP	EQUIPMENT	SPCS	SPACES
EW	EACH WAY	SO	SQUARE
EXP	EXPANSION	SS	STAINLESS STEEL
EXT	EXTERIOR	STAGG	STAGGER
		STD	STANDARD
		STIFF	STIFFEN, STIFFENER
		STRIP	STRIP
		STL	STEEL
		STRUC	STRUCTURAL
		SYN	SYMMETRICAL

GA	GAUGE	T&B	TOP & BOTTOM
GALV	GALVANIZE	TK	THICK, THICKNESS
GC	GENERAL CONTRACTOR	THRU	THROUGH
		TIO	TOP OF
		TRANS	TRANSVERSE
		TYP	TYPICAL

HEX	HEXAGONAL	UNO	UNLESS NOTED OTHERWISE
HGR	HANGER		
HT	HEIGHT		
HORIZ	HORIZONTAL	VERT	VERTICAL
		VERIFY	VERIFY IN FIELD

IF	INSIDE FACE		
ID	INSIDE DIAMETER	W/	WITH
INFO	INFORMATION	WO	WITHOUT
IOR	INSPECTOR OF RECORD	WP	WORK POINT
		WT	WEIGHT

K	KIPS (1000#)	STRUCTURAL	STEEL SHAPES
K&B-TZ	H.L.T. KWIK BOLT T2Z (ANCHOR)	HSS	HOLLOW STANDARD CHANNEL
KSF	KIPS PER SQUARE FOOT	HSS	HOLLOW STRUCTURAL SECTIONS
KSI	KIPS PER SQUARE INCH	ANGLE	ANGLE
		M	MISCELLANEOUS CHANNEL
		Mx	M SHAPES
		STD PIPE	STANDARD PIPE
		Sx	S SHAPES
		STL	STRUCTURAL TEES
		Wx	W SHAPES
		X-STRG	EXTRA STRONG PIPE
		XX-STRG	DBL EXTRA STRONG PIPE

GENERAL STRUCTURAL NOTES:

DESIGN CRITERIA:
CODE OF RECORD: 2022 EDITION, CALIFORNIA BUILDING CODE

DESIGN LOADS:
BASIC WIND SPEED: 101 MPH (3-SECOND GUST)
WIND EXPOSURE CATEGORY: C
ANALYSIS PROCEDURE: SEISMIC DESIGN REQUIREMENTS FOR NONBUILDING STRUCTURES (ASCE 7-16, CHAPTER 15)
RISK CATEGORY: 1
SEISMIC SITE CLASS: D
SEISMIC DESIGN CATEGORY: D
SPECTRAL RESPONSE ACCELERATIONS: $S_s = 2.73g$, $S_{D1} = 1.82g$
SEISMIC IMPORTANCE FACTOR: $I_p = 1.25$

1. GOVERNING CODE AUTHORITY FOR THIS PROJECT: LOS ANGELES COUNTY AND IS REFERRED TO AS "THE GOVERNING AGENCY" IN THESE AND OTHER STRUCTURAL NOTES SECTIONS.

2. GENERAL NOTES AND TYPICAL DETAILS SHALL APPLY TO ALL PARTS OF THE JOB, EXCEPT WHERE THEY MAY DIFFER WITH DETAILS AND NOTES ON OTHER SHEETS. IN WHICH CASE THE DETAILS AND NOTES ON OTHER SHEETS SHALL GOVERN. DETAIL MARKS WITH "SM" NOTED INDICATE THAT DETAIL CONTAINS MODIFIED INFORMATION APPLICABLE TO THE CONDITION REFERENCED.

3. SEE MECHANICAL, ELECTRICAL OR PLUMBING (MEP) DRAWINGS FOR SIZE AND LOCATION OF ALL OPENINGS (EXCEPT AS NOTED), INSERTS, FINISHES, ETC. FOR DETAILS (EXCEPT AS SHOWN), AND FOR DIMENSIONS NOT SHOWN ON STRUCTURAL DRAWINGS. WHERE DIMENSIONS DIFFER BETWEEN PLANS, NOTIFY SEOR AND AWARD DIRECTION PRIOR TO PROCEEDING WITH WORK.

4. DO NOT INSERT MECHANICAL, ELECTRICAL OR PLUMBING (MEP) SLEEVES, PIPES OR CONDUIT IN CONCRETE WITHOUT PRIOR APPROVAL OF THE SEOR, TYPICAL UNLESS NOTED OTHERWISE ON PLAN.

5. OMISSIONS OR CONFLICTS BETWEEN THE VARIOUS ELEMENTS OF THE WORKING DRAWINGS AND/OR SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE SEOR PRIOR TO PROCEEDING WITH ANY WORK INVOLVED.

6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE WORK OF ALL TRADES AND SHALL CHECK ALL DIMENSIONS. ALL DISCREPANCIES SHALL BE CALLED TO THE ATTENTION OF THE ARCHITECT AND THE SEOR AND SHALL BE RESOLVED PRIOR TO PROCEEDING WITH THE WORK.

7. ALL INFORMATION SHOWN ON THE DRAWINGS RELATIVE TO EXISTING CONDITIONS IS GIVEN AS THE BEST CURRENT KNOWLEDGE, BUT WITHOUT GUARANTEE OF ACCURACY. WHERE ACTUAL CONDITIONS CONFLICT WITH THE DRAWINGS, THEY SHALL BE REPORTED TO THE SEOR SO THAT THE PROPER REVISION MAY BE MADE. MODIFICATIONS OF CONSTRUCTION DETAILS SHALL NOT BE MADE WITHOUT WRITTEN APPROVAL OF THE SEOR.

8. THE CONTRACT DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE AND DO NOT INDICATE THE METHOD OR SEQUENCE OF CONSTRUCTION, UNLESS NOTED OTHERWISE. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES AND PROCEDURES, INCLUDING BUT NOT LIMITED TO BRACING, SHORING AND LAYDOWN OF CONSTRUCTION MATERIALS.

9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR TEMPORARY CONSTRUCTION LOADING, INCLUDING LOADING FROM EQUIPMENT SUCH AS SKP LOADERS, SCISSOR LIFTS, ETC., ON ALL PORTIONS OF THE STRUCTURE, WHETHER ELEVATED OR ON-GRADE. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR THE PATH-OF-TRAVEL, FOR MOVING PERMANENT EQUIPMENT TO ITS FINAL LOCATION, INCLUDING THE EFFECTS OF TEMPORARY LOADING AS THE EQUIPMENT IS INSTALLED. THE CONTRACTOR MAY USE THE "DESIGN LOADS" INFORMATION PROVIDED ABOVE WHEN CONSIDERING TEMPORARY CONSTRUCTION LOADING CONDITIONS.

10. OBSERVATION VISITS TO THE SITE BY FIELD REPRESENTATIVES OF THE ARCHITECT/SEOR SHALL NOT INCLUDE INSPECTIONS OF THE PROTECTIVE COVERINGS, AND/OR SUPPORT SERVICES PERFORMED BY THE ARCHITECT/SEOR DURING THE CONSTRUCTION SHALL BE DISTINGUISHED FROM CONTINUOUS AND DETAILED SPECIAL INSPECTION SERVICES WHICH ARE FURNISHED BY OTHERS. THESE SUPPORT SERVICES PERFORMED BY THE ARCHITECT/SEOR, WHETHER OF MATERIAL OR WORK, AND WHETHER PERFORMED PRIOR TO, DURING OR AFTER COMPLETION OF CONSTRUCTION, ARE PERFORMED SOLELY FOR THE PURPOSE OF ASSISTING IN QUALITY CONTROL, AND IN ACHIEVING CONFORMANCE WITH CONTRACT DOCUMENTS, BUT DO NOT GUARANTEE CONTRACTORS PERFORMANCE, AND SHALL NOT BE CONSTRUED AS SUPERVISION OF CONSTRUCTION.

11. ASTM DESIGNATIONS AND ALL STANDARDS REFER TO THE LATEST AMENDMENTS.

12. WHEN THE ALLOWANCE FOR SUBSTITUTION OF A SPECIFIED MATERIAL OR PRODUCT DESIGNATION IS IMPLIED ON THE DESIGN DRAWINGS BY THE USE OF THE WORDS "OR APPROVED/EQUAL", APPROVAL SHALL BE OBTAINED FROM THE SEOR AND THE GOVERNING AGENCY PRIOR TO FABRICATION OR INSTALLATION OF THE SUBSTITUTED MATERIAL OR PRODUCT.

13. DIMENSIONS SHALL GOVERN OVER SCALES SHOWN ON DRAWINGS.

14. THE OWNER SHALL EMPLOY ONE OR MORE SPECIAL INSPECTORS WHO SHALL PROVIDE SPECIAL INSPECTIONS DURING CONSTRUCTION WHEN SO SPECIFIED ON THE CONTRACT DRAWINGS AND SPECIFICATIONS FOR CERTAIN TYPES OF WORK. THE SPECIAL INSPECTOR SHALL BE A QUALIFIED PERSON WHO SHALL DEMONSTRATE HIS COMPETENCE, TO THE SATISFACTION OF THE GOVERNING AGENCY, FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION. THE SPECIAL INSPECTOR SHALL OBSERVE THE WORK ASSIGNED FOR CONFORMANCE WITH THE DESIGN DRAWINGS AND SPECIFICATIONS. THE SPECIAL INSPECTOR SHALL FURNISH INSPECTION REPORTS TO THE SEOR AND TO THE GOVERNING AGENCY. ALL DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION, THEN, IF UNCORRECTED, TO THE SEOR AND TO THE GOVERNING AGENCY. THE SPECIAL INSPECTOR SHALL SUBMIT A FINAL, SIGNED REPORT STATING WHETHER THE WORK REQUIRES SPECIAL INSPECTION WAS, TO THE BEST OF HIS KNOWLEDGE, IN CONFORMANCE WITH THE DESIGN DRAWINGS AND SPECIFICATIONS AND THE APPLICABLE WORKMANSHIP PROVISION OF THE CODE AND OTHER APPLICABLE REGULATIONS IDENTIFIED ON THE PLANS OR IN THE PROJECT SPECIFICATIONS.

15. UNLESS SPECIFICALLY SHOWN ON THESE PLANS, NO STRUCTURAL MEMBER (BEAM, COLUMN, SHEARWALL, GRADE BEAM, ETC.) SHALL BE CUT, DRILLED OR NOTCHED WITHOUT PRIOR AUTHORIZATION FROM THE SEOR AND THE GOVERNING AGENCY.

16. DIMENSIONS OF EQUIPMENT ANCHOR/ MOUNTING LOCATIONS SHOWN ON PLANS AND/OR DETAILS ARE TO BE COORDINATED WITH ACTUAL EQUIPMENT TO BE INSTALLED. CONTRACTOR TO VERIFY THE EXACT SIZE AND LOCATION OF ALL EQUIPMENT ANCHOR/ MOUNTING HOLES PRIOR TO INSTALLATION, WHERE ACTUAL EQUIPMENT DIMENSIONS DO NOT FALL WITHIN THE MINIMUM OR MAXIMUM DIMENSIONS PROVIDED ON PLANS AND/OR DETAILS, NOTIFY SEOR AND AWARD DIRECTION PRIOR TO PROCEEDING WITH WORK.

SHOP DRAWINGS:

A. SHOP DRAWINGS, INCLUDING CONCRETE MIX DESIGNS, SHALL BE SUBMITTED TO THE SEOR FOR REVIEW PRIOR TO FABRICATION OR USE. A SCHEDULE FOR THE RELEASE OF SHOP DRAWING SUBMITTALS SHALL BE PREPARED BY THE CONTRACTOR AND REVIEWED BY THE ARCHITECT/SEOR PRIOR TO THE START OF FABRICATION OR CONSTRUCTION. THIS SUBMITTAL SCHEDULE SHALL PROPORTION THE NUMBER OF SHOP DRAWINGS TO BE REVIEWED IN EACH SUBMITTAL TO ALLOW SUFFICIENT TIME AS DEEMED REASONABLE IN THE PROFESSIONAL JUDGMENT OF THE ARCHITECT/SEOR TO PERMIT ADEQUATE REVIEW. SHOP DRAWINGS SHALL REFERENCE THE LATEST REVISION OF EACH STRUCTURAL DESIGN DRAWING USED TO DETAIL FROM. SUBMITTALS THAT DO NOT IDENTIFY THE LATEST REVISION OF STRUCTURAL PLANS SHALL BE RETURNED WITHOUT REVIEW. FOR THE DETAILER TO UPDATE AND RESUBMIT. THE DETAILING ON EACH SHOP DRAWING SHALL BE COMPLETE BEFORE RELEASING FOR REVIEW THE SUBMITTAL CONTAINING THAT SHOP DRAWING. IF THE SUBMITTAL MUST BE REVISED, IT SHALL IDENTIFY EACH REVISION AND/OR ADDITION TO EACH SHOP DRAWING BY CLOUDING OR OTHER MEANS, TO ENSURE THEIR IDENTIFICATION FOR REVIEW.

B. SHOP DRAWINGS AND CONCRETE MIX DESIGNS WILL NOT BE ACCEPTED BY THE SEOR DIRECTLY FROM THE PROJECT SUB-CONTRACTORS. SHOP DRAWINGS AND CONCRETE DESIGN MIXES WILL BE ACCEPTED FROM THE GENERAL CONTRACTOR ONLY, AFTER THEY HAVE BEEN REVIEWED AND SIGNED BY THE GENERAL CONTRACTOR, INDICATING COMPLIANCE WITH HIS REQUIREMENTS AND THE REQUIREMENTS OF THE CONSTRUCTION DOCUMENTS. SHOP DRAWINGS NOT COMPLYING WITH THE INSTRUCTIONS IN BOTH NOTES A AND B WILL BE RETURNED BY THE SEOR WITHOUT REVIEW.

FOUNDATIONS:

1. RECOMMENDATIONS CONTAINED IN THE PROJECT GEOTECHNICAL/SOILS REPORT AS LISTED BELOW WERE USED FOR THE STRUCTURAL DESIGN OF FOUNDATIONS AND EARTH RETAINING ELEMENTS CONTAINED HEREIN. IF IT IS DETERMINED THAT ANY OF THE RECOMMENDATIONS IN THE PROJECT REPORT AFFECTING CONSTRUCTION WILL NOT BE FOLLOWED, A FORMAL CHANGE ORDER SHALL BE PREPARED WITH ADEQUATE TIME FOR PROCESSING APPROVAL BY THE STRUCTURAL ENGINEER OF RECORD, THE GEOTECHNICAL ENGINEER AND THE GOVERNING AGENCY. MHP ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THE RECOMMENDATIONS CONTAINED WITHIN THE PROJECT REPORT.

A. REPORT OR TITLE: REPORT OF GEOTECHNICAL INVESTIGATION PROPOSED PROBATION CAMP SECURITY UPGRADES
B. REPORT OR PROJECT NUMBER: 1185.1
C. PREPARED BY: GEOTECHNICAL PROFESSIONAL, INC.
D. DATED: APRIL 27, 2023 (REVISED MARCH 22, 2024)

2. THE FOLLOWING DESIGN PARAMETERS WERE USED AS THE BASIS FOR ALLOWABLE FOUNDATION LOADS AND SOIL PRESSURES:
A. ALLOWABLE SOIL BEARING PRESSURES:
• SPREAD/SLAB FOOTINGS: 2,500 PSF
• CONTINUOUS FOOTINGS: 2,500 PSF

B. ALLOWABLE INCREASES FOR SOIL PRESSURE:
• FOR LOAD COMBINATIONS INCLUDING WIND OR SEISMIC, A ONE-THIRD (1/3) INCREASE IS ALLOWED.

C. RESISTANCE TO SLIDING:
• FRICTION COEFFICIENT: 0.40 x DEAD LOAD
• PASSIVE PRESSURE: 500 PCF (500 PSF MAXIMUM)

D. ALLOWABLE SKIN FRICTION VALUES:
• 0 - 3 FEET BELOW GRADE: 40 PSF
• 3 - 7 FEET BELOW GRADE: 100 PSF
• 7 - 10 FEET BELOW GRADE: 150 PSF
• 10 - 15 FEET BELOW GRADE: 200 PSF

3. REMEDIAL EXCAVATIONS ARE NOT REQUIRED AT FENCE STRUCTURES, FOR MINOR STRUCTURES WHICH ARE NOT IN SCOPE OF PROJECT. REMOVAL/REPLACEMENT OF ON-SITE SOILS SHOULD EXTEND TO A DEPTH OF 4 FEET BELOW EXISTING GRADES OR 2 FEET BELOW FOOTINGS, WHICHEVER IS DEEPER. WHERE DEEPER FILLS ARE PRESENT, REMOVALS SHOULD EXTEND DEEP ENOUGH TO REMOVE THE UNDESIRABLE FILL AND REPLACE IT WITH PROPERLY COMPACTED FILL.

4. ALL SITE FILL, INCLUDING BACKFILL FOLLOWING OVER-EXCAVATION, IF REQUIRED, SHALL BE COMPACTED TO THE FOLLOWING MINIMUM RELATIVE COMPACTION CRITERIA AS PER ASTM TEST METHOD D-1557. FLOODING IS NOT PERMITTED AND SHALL NOT BE USED FOR COMPACTION PURPOSES.
A. 90 PERCENT OF MAXIMUM DRY DENSITY WITHIN 40 FEET BELOW FINISH GRADE.
B. 93 PERCENT OF MAXIMUM DRY DENSITY DEEPER THAN 40 FEET BELOW FINISH GRADE.
C. 95 PERCENT OF MAXIMUM DRY DENSITY IS REQUIRED FOR ALL FIRE LANES UNLESS OTHERWISE APPROVED BY THE FIRE DEPARTMENT.

5. ALL FILL AND BACKFILL EXTENTS AND MATERIAL SHALL BE APPROVED BY THE PROJECT GEOTECHNICAL ENGINEER.
• FILL MATERIAL SHALL NOT INCLUDE ORGANIC, FROZEN, OR OTHER DELETERIOUS MATERIALS. ROCK OR SIMILAR REDUCIBLE MATERIAL, GREATER THAN 12 INCHES (305 MM) IN ANY DIMENSION SHALL NOT BE INCLUDED IN FILLS. (SECTION 1107.5 OF THE COUNTY OF LOS ANGELES BUILDING CODE.)

6. ALL FOUNDATION EXCAVATIONS SHALL BE APPROVED BY THE PROJECT GEOTECHNICAL ENGINEER PRIOR TO INSTALLATION OF REINFORCING OR OTHER ELEMENTS WHICH MAKE THE EXCAVATIONS INACCESSIBLE FOR ANY CORRECTIVE WORK DEEMED NECESSARY FOR APPROVAL.

7. FIELD DENSITY SHALL BE DETERMINED BY A METHOD ACCEPTABLE TO THE BUILDING OFFICIAL. (SECTION 1107.5 OF THE COUNTY OF LOS ANGELES BUILDING CODE.) HOWEVER, NOT LESS THAN 10% OF THE REQUIRED DENSITY TEST, UNIFORMLY DISTRIBUTED, AND SHALL BE OBTAINED BY THE SAND CONE METHOD.

8. SUFFICIENT TESTS OF THE FILL SOILS SHALL BE MADE TO DETERMINE THE RELATIVE COMPACTION OF THE FILL IN ACCORDANCE WITH THE FOLLOWING MINIMUM GUIDELINES:
A. ONE TEST FOR EACH 2000 CUBIC FEET VERTICAL LIFT.
B. ONE TEST FOR EACH 1,000 CUBIC YARDS OF MATERIAL PLACED.
C. ONE TEST AT THE LOCATION OF THE FINAL FILL SLOPE FOR EACH BUILDING SITE (LOT) IN EACH FOUR-FOOT VERTICAL LIFT OR PORTION THEREOF.
D. ONE TEST IN THE VICINITY OF EACH

9. SUFFICIENT TESTS OF FILL SOILS SHALL BE MADE TO VERIFY THAT THE SOIL PROPERTIES COMPLY WITH THE DESIGN REQUIREMENTS, AS DETERMINED BY THE PROJECT GEOTECHNICAL ENGINEER INCLUDING SOIL TYPES, SHEAR STRENGTHS PARAMETERS AND CORRESPONDING UNIT WEIGHTS IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
A. PRIOR AND SUBSEQUENT TO PLACEMENT OF THE FILL, SHEAR TESTS SHALL BE TAKEN ON EACH TYPE OF SOIL OR SOIL MIXTURE TO BE USED FOR ALL FILL SLOPES STEEPER THAN THREES (3) HORIZONTAL TO ONE VERTICAL.
B. SHEAR TEST RESULTS FOR THE PROPOSED FILL MATERIAL MUST MEET OR EXCEED THE DESIGN VALUES USED IN THE GEOTECHNICAL REPORT TO DETERMINE SOIL STABILITY REQUIREMENTS. OTHERWISE, THE SLOPE MUST BE REEVALUATED USING THE ACTUAL SHEAR TEST VALUE OF THE FILL MATERIAL, THAT IS IN PLACE.
C. FILL SOILS SHALL BE FREE OF DELETERIOUS MATERIALS.

10. FILL SHALL NOT BE PLACED UNTIL STRIPPING OF VEGETATION, REMOVAL OF UNSUITABLE SOILS, AND INSTALLATION OF SUBDRAIN (IF ANY) HAVE BEEN INSPECTED AND APPROVED BY THE SOIL ENGINEER. THE BUILDING OFFICIAL MAY REQUIRE A "STANDARD TEST METHOD FOR MOISTURE, ASH, ORGANIC MATTER, PEAT OR OTHER ORGANIC SOILS" ASTM D-2947-07 ON ANY SUSPECT MATERIAL. DETRIMENTAL AMOUNTS OF ORGANIC MATERIAL SHALL NOT BE PERMITTED IN FILLS. SOIL CONTAINING SMALL AMOUNTS OF ROOTS MAY BE ALLOWED PROVIDED THAT THE ROOTS ARE IN A QUANTITY AND DISTRIBUTED IN A MANNER THAT WILL NOT BE DETRIMENTAL TO THE FUTURE USE OF THE SITE AND THE SOILS ENGINEER APPROVES THE USE OF SUCH MATERIAL.

11. WATER SHALL BE REMOVED FROM FOUNDATION EXCAVATION PRIOR TO PLACING OF CONCRETE. CARE SHALL BE TAKEN TO AVOID DRYING OUT UNDERLYING NATURAL SOILS.

12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SEQUENCING AND SHORING, ETC., NECESSARY TO SUPPORT CUT AND/OR FILL BANKS DURING EXCAVATION AND FORMING AND PLACEMENT OF CONCRETE. CARE SHALL BE TAKEN TO AVOID DISTURBING SOILS AROUND AND/OR SUPPORTING EXISTING FOUNDATIONS AND UTILITIES.

13. FILL SLOPES IN EXCESS OF 2:1 STEEPNESS RATIO ARE TO BE CONSTRUCTED BY THE PLACEMENT OF SOIL AT SUFFICIENT DISTANCE BEYOND THE PROPOSED FINISH SLOPE TO ALLOW COMPACTION EQUIPMENT TO BE OPERATED AT THE OUTER LIMITS OF THE FINAL SLOPE SURFACE. THE EXCESS FILL IS TO BE REMOVED PRIOR TO COMPLETION OF ROUGH GRADING. OTHER CONSTRUCTION PROCEDURES MAY BE USED WHEN IT IS DEMONSTRATED TO THE SATISFACTION OF THE BUILDING OFFICIAL THAT THE ANGLE OF SLOPE, CONSTRUCTION METHOD AND OTHER FACTORS WILL HAVE EQUIVALENT EFFECT. (SECTION 1107.5 OF THE COUNTY OF LOS ANGELES BUILDING CODE.)

14. SEE SPECIAL INSPECTION GENERAL NOTES FOR INSPECTION REQUIREMENTS.

REINFORCING STEEL:

1. DETAILING, FABRICATION AND PLACING OF REINFORCING STEEL SHALL CONFORM TO STANDARDS AND RECOMMENDATIONS CONTAINED WITHIN THE CRSI "MANUAL OF STANDARD PRACTICE". DETAILING FABRICATION AND PLACING OF WELDED WIRE REINFORCING SHALL CONFORM TO THE STANDARDS AND RECOMMENDATIONS CONTAINED WITHIN THE WRI "MANUAL OF STANDARD PRACTICE". STRUCTURAL WELDED WIRE REINFORCEMENT:

2. REINFORCING BARS (REBAR), STEEL WELDED WIRE REINFORCING (WWR), AND TIE WIRE USED TO SECURE REBAR AND WWR SHALL CONFORM TO THE FOLLOWING ASTM SPECIFICATIONS, UNO:
A. REINFORCING, [ALL BAR SIZES, UNO]: ASTM A-615, GR 60
B. REINFORCING BARS TO BE WELDED [ALL BAR SIZES UNO]: ASTM A-706, GR 60
C. WELD WIRE REINFORCING: ASTM A-1064
D. TIE WIRE: ASTM A-62

3. ALL REINFORCING STEEL SHALL BE BENT COLD. GRADE 60 BARS MAY ONLY BE BENT ONCE, STRAIGHTENING AND/OR RE-BENDING IS NOT ALLOWED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO SEQUENCE PLACEMENT OF REINFORCING SUCH THAT INCIDENTAL BENDING DOES NOT OCCUR.

4. PRIOR TO PLACING CONCRETE, REINFORCING STEEL, INCLUDING WWR, AND OTHER EMBEDDED ITEMS SHALL BE WELL-SECURED IN POSITION AND SHALL BE CLEAN OF RUST, GREASE OR OTHER MATERIAL LIKELY TO IMPAIR BOND. WHERE TWO LAYERS OF REINFORCING STEEL ARE REQUIRED (I.E. FOOTING PADS OR SLABS) PROVIDE APPROPRIATE CHAIRS TIED TO AND SUPPORTED BY LOWER MAT OF REINFORCING TO SUPPORT THE UPPER MAT OF REINFORCING. "HOOK AND PUD" METHODS SHALL NOT BE ALLOWED.

5. CONCRETE PROTECTION FOR REINFORCING BARS SHALL BE AT LEAST EQUAL TO THE DIAMETER OF THE BAR, MINIMUM COVER FOR CAST IN PLACE CONCRETE SHALL BE AS FOLLOWS:
• ALL MEMBERS, ALL REINFORCEMENT: 3"
A. CAST AGAINST AND PERMANENTLY IN CONTACT WITH GROUND:
• ALL MEMBERS, ALL REINFORCEMENT: 3"
B. EXPOSED TO WEATHER OR IN CONTACT WITH GROUND:
• ALL MEMBERS, #6 THROUGH #18 BARS: 1 1/2"
• ALL MEMBERS, #5, WED COTIN WIRE AND SMALLER: 1 1/2"
C. NOT EXPOSED TO WEATHER OR IN CONTACT WITH GROUND:
• SLABS, JOISTS, WALLS, #14 AND #18 BARS: 3/4"
• SLABS, JOISTS, WALLS, #11 BARS AND SMALLER: 1 1/2"
• BEAMS, COLUMNS:
• PRIMARY REINF, STIRRUPS, TIES, SPIRALS AND HOOPS: 1 1/2"

6. MINIMUM CLEAR SPACING BETWEEN PARALLEL BARS IN A SINGLE LAYER SHALL NOT BE LESS THAN 1 1/2" 4/3 TIMES LARGEST AGGREGATE. 1 1/2 TIMES DIAMETER OF THE LARGER BAR, WHICHEVER IS GREATER, WHERE PARALLEL REINFORCING IS PLACED IN TWO OR MORE LAYERS. BARS IN THE UPPER LAYERS SHALL BE PLACED DIRECTLY ABOVE THE BARS IN LOWER LAYERS WITH NOT LESS THAN 1" CLEAR SPACE BETWEEN LAYERS.

7. DEVELOPMENT AND LAP SPICE LENGTHS FOR REINFORCING STEEL AND WELDED WIRE REINFORCING SHALL BE AS NOTED ON PLANS AND DETAILS CONTAINED THEREIN, WHERE SPICE LOCATIONS ARE NOT SPECIFICALLY INDICATED. SPICES SHALL BE STAGGERED A MINIMUM OF ONE (1) LAP LENGTH, WHERE SPECIFIC LAP LENGTH REQUIREMENTS ARE NOT SPECIFICALLY SHOWN ON PLANS, THE FOLLOWING MINIMUM LENGTHS SHALL BE USED:
A. REBAR IN CONCRETE: SEE TYPICAL DETAILS
B. REBAR IN MASONRY: SEE TYPICAL DETAILS
C. WWR IN CONCRETE: 1 1/2 x WIRE GRID SPACES (9" MIN)

8. COMPLETE REINFORCING PLACEMENT DRAWINGS (SHOP DRAWINGS) SHALL BE PREPARED IN ACCORDANCE WITH ACI 315 AND SHALL BE SUBMITTED TO THE SEOR FOR REVIEW PRIOR TO FABRICATION. APPROVED SHOP DRAWINGS SHALL BE MADE AVAILABLE ON THE JOB SITE PRIOR TO PLACING OF CONCRETE. SEE SUBMITTALS SECTION OF THE STRUCTURAL NOTES FOR ADDITIONAL INFORMATION AND REQUIREMENTS.

9. CONTRACTOR SHALL SCHEDULE SPECIAL INSPECTIONS SO THAT BAR SIZE, SPACING, LAP SPICE AND EMBEDMENT LENGTH OF REINFORCING BARS, AND THE LOCATION OF CONDUIT, SLEEVES AND EMBEDDED ITEMS, MAY BE CORRECTED, IF NECESSARY, PRIOR TO PLACEMENT OF OVERLYING GRIDS OF REINFORCING STEEL AND/OR PLACEMENT OF CONCRETE.

10. WHEN CALLED FOR ON PLANS, WELDING OF REINFORCING STEEL, INCLUDING DETAILS, PROCEDURES, AND WORKMANSHIP, SHALL BE COMPLETED IN ACCORDANCE WITH THE REQUIREMENTS OF ANSII/AWS D14 - "STRUCTURAL WELDING CODE - REINFORCING STEEL" AS PUBLISHED BY THE AMERICAN WELDING SOCIETY. THE FOLLOWING ADDITIONAL CRITERIA SHALL BE MET:
A. DEFORMED STEEL BARS CONFORMING TO ASTM A-706, GRADE 60 MAY BE WELDED WITHOUT QUALIFICATION.
B. REINFORCING STEEL CONFORMING TO ASTM A-615, GRADE 60, WITH A CARBON EQUIVALENT OF 0.65% OR LESS, AS ESTABLISHED BY THE MANUFACTURER'S CHEMICAL ANALYSIS, MAY BE WELDED WITHOUT PRIOR QUALIFICATIONS TESTS.
C. REINFORCING STEEL WITH A CARBON EQUIVALENT GREATER THAN 0.65% AND LESS THAN OR EQUAL TO 0.75%, AS ESTABLISHED BY THE MANUFACTURER'S CHEMICAL ANALYSIS, SHALL NOT BE WELDED UNLESS PRIOR QUALIFICATION TESTS VERIFY ACCEPTABLE WELDABILITY.
D. REINFORCING STEEL WHOSE CHEMISTRY FOR CARBON EQUIVALENT WHICH CANNOT BE IDENTIFIED AND/OR IS UNKNOWN, AND REINFORCING STEEL WHOSE CARBON EQUIVALENT EXCEEDS 0.75%, SHALL NOT BE WELDED UNDER ANY CIRCUMSTANCES.
E. REBAR SHALL BE WELDED USING E60XX ELECTRODES.

11. IF FUSION WELDED HOLDING WIRES ARE USED FOR FABRICATION OF REBAR CAGES OR MATS, THE FOLLOWING REQUIREMENTS AND LIMITATIONS SHALL APPLY:
A. FUSION WELDING OF HOLDING WIRES IS ALLOWED FOR TIES, STIRRUPS, HOOPS IN BEAMS, COLUMNS, AND GRADE BEAMS TO PREASSEMBLE REINFORCING STEEL CAGES. FUSION WELDING IS NOT ALLOWED FOR LONGITUDINAL REINFORCING STEEL IN ANY BEAM, COLUMN, OR GRADE BEAM. THE HOLDING WIRE AREA SHALL NOT EXCEED 5% OF THE BEAM, COLUMN, OR GRADE BEAM CROSS SECTIONAL LONGITUDINAL STEEL AREA.
B. FUSION WELDING OF HOLDING WIRES IS ALLOWED AT THE ENDS OF THE REINFORCING STEEL PLACED IN MATS (SPREAD FOOTINGS, SLAB REINFORCEMENT, ETC.) PROVIDED THAT THE FUSION WELD OCCURS WITHIN 8 BAR DIAMETERS OF THE FREE END OF THE BAR (E.G. NOT ALLOWED AT END OF COUPLED, T-HEADED, OR WELD SPICED BARS).
C. FUSION WELDING OF HOLDING WIRES SHALL NOT OCCUR ON A BENT PORTION OF A REINFORCING BAR. AFTER HOLDING WIRE HAS BEEN FUSION WELDED TO A REINFORCING BAR, THAT BAR MAY NOT BE BENT WHERE THE FUSION WELD OCCURS.
D. THE HOLDING WIRES SHALL CONFORM TO ASTM A1064.
E. ALL REINFORCING STEEL TO BE WELDED SHALL COMPLY WITH ASTM A706.
F. SHOP DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW INDICATING WHICH MEMBERS WILL USE FUSION WELDING PROCESS FOR PREASSEMBLY AND SHALL BE IN ACCORDANCE WITH THE GENERAL STRUCTURAL NOTES. PROVIDE COMPLETE STRUCTURAL DETAILS INDICATING THE SIZE OF STIRRUPS AND HOLDING WIRES AND WELDING REQUIREMENTS.
G. WELDING SHALL BE DONE IN THE SHOP BY MACHINES USING ELECTRIC RESISTANCE WELDS AND UNDER A CONTINUOUS CONTROLLED PROCESS. SUBMIT A COMPLETE SHOP WELDING PROGRAM OUTLINING THE FOLLOWING:
• TYPE OF THE SPECIFIC FUSION WELDING MACHINE (I.E. SCHNELL IDEA 1225)
• PERIODIC INSPECTION OF THE IN-PLANT WELDING.
H. FUSION WELDED

STRUCTURAL AND MISCELLANEOUS STEEL:

1. ALL STRUCTURAL AND MISCELLANEOUS STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH AISC SPECIFICATIONS FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS (AISC 360), LATEST EDITION, AND SEISMIC PROVISIONS FOR STRUCTURAL STEEL BUILDINGS (AISC 341) LATEST EDITION.

2. ALL WELDING SHALL COMPLY WITH AISC SPECIFICATION D1.101.1M. WELDING ON PARTS OF THE SEISMIC FORCE RESISTING SYSTEM (SFRS) SHALL ALSO CONFORM TO AISC D1.801.8M. WELDING SHALL BE PERFORMED BY WELDERS CERTIFIED FOR THE TYPE OF WELDING TO BE PERFORMED.

3. WELDING PROCEDURE SPECIFICATIONS (WPS) SHALL BE SUBMITTED FOR REVIEW FOR EACH WELD TYPE, WELDING PROCESS, WELDING ELECTRODE CLASSIFICATION AND/OR BASE MATERIAL (WHERE ASTM GRADE OR ALLOY VARIES) SHOWN ON THE DRAWINGS IN CONFORMANCE WITH AISC D1.101.1M, D1.4D1.4M AND D1.8D1.8M AS APPLICABLE. EACH WPS SHALL BE RECORDED ON FORMS RECOMMENDED BY THE APPLICABLE AISC STANDARD AND SHALL BE REVIEWED BY AN AISC SOW CERTIFIED INSPECTOR AND SUBMITTED TO THE SEOR AND, IF THE PROJECT IS GOVERNED BY OSA OR CSHP, THE INSPECTOR OF RECORD (IOR) FOR REVIEW. IF A WELD ASSEMBLY NOTED ON PLANS DOES NOT FALL WITHIN THE PREQUALIFIED CRITERIA, CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A WELDING PROCEDURE QUALIFICATION RECORD FOR THE SPECIFIED WELD AS PART OF THE WPS SUBMITAL.

4. ALL STRUCTURAL AND MISCELLANEOUS STEEL SHALL CONFORM TO THE FOLLOWING SPECIFICATION (UNLESS NOTED OTHERWISE):

A. WIDE FLANGE SECTIONS (I/W/F)

ASTM A-992

FY=50KSI

B. CHANNELS AND MISC SHAPES (C/MC/S/M)

ASTM A-36

FY=50KSI

C. ANGLES AND PLATES

ASTM A-36

FY=50KSI

D. PIPE (STD X STRG X ASTM)

ASTM A-53 TYPE E, GR B

FY=50KSI

E. HSS TUBE (SQ RECTANG)

ASTM A-500, GR C

FY=50KSI

F. SULFUR CONTENT SHALL BE LESS THAN OR EQUAL TO 0.05%

G. HSS TUBE (ROUND)

ASTM A-500, GR C

FY=48KSI

5. STRUCTURAL STEEL SHOP DRAWINGS SHALL BE SUBMITTED TO THE ARCHITECT AND SEOR FOR REVIEW PRIOR TO FABRICATION AND ERECTION, IN ACCORDANCE WITH NOTE 12 OF GENERAL STRUCTURAL NOTES.

6. WHEN FABRICATING BEAMS PLACE NATURAL CAMBER UP. A TOLERANCE OF + 0, -1/4 INCH MAY BE APPLIED TO ALL SPECIFIED CAMBERS.

7. AFTER FABRICATION, ALL STEEL SHALL BE CLEANED FREE OF RUST, LOOSE MILL SCALE, AND OIL.

8. ALL STEEL EXPOSED TO MOISTURE OR WEATHER SHALL BE HOT-DIPPED GALVANIZED, UNLESS NOTED OTHERWISE. GALVANIZING SHALL BE IN CONFORMANCE WITH ASTM A123 AND A153. REPAIR GALVANIZING AFTER WELDING SHALL BE IN ACCORDANCE WITH ASTM A780.

9. HOT-DIP GALVANIZE OR PROVIDE THREE-INCH (3") MINIMUM CONCRETE COVER AROUND ALL STRUCTURAL STEEL BELOW GRADE.

10. SEE ARCHITECTURAL DRAWINGS FOR PAINTING OF STRUCTURAL STEEL. STRUCTURAL STEEL EMBEDDED IN CONCRETE OR MASONRY SHALL BE UNPAINTED.

11. WHERE CARBON STEEL IS IN CONTACT WITH STAINLESS STEEL OR WHERE EITHER CARBON OR STAINLESS STEEL IS IN CONTACT WITH ALUMINUM, PHENOLIC SHIM OR BREAK SHALL BE INSTALLED TO SEPARATE DISSIMILAR METALS.

12. BOLTS, THREADED RODS, AND WASHERS SHALL CONFORM TO THE FOLLOWING, UNO:

A. MACHINE BOLTS

ASTM A-307

B. HIGH STRENGTH BOLTS

ASTM A-325-A OR A-490

C. THREADED RODS, UNO

ASTM F1554 GR36

D. WELDED HEADED STUDS

ASTM A-108, GRADE 1010-1020

E. WASHERS

ASTM F-436

F. WASHERS AT NON-SEISMIC WIND-RESISTING-FRAME COLUMNS WHERE HOLES AT COLUMN BASE PLATE ARE OVER-SIZED, ONLY WHEN REQUESTED BY CONTRACTOR AND APPROVED BY SEOR.

ASTM F-436 5/8" THICK

G. ANCHOR BOLTS IN CONCRETE OR MASONRY

ASTM F-1554, GR 36

H. HIGH STRENGTH ANCHOR BOLTS IN CONCRETE

ASTM F-1554, GR 105

13. ANCHOR BOLTS SHALL BE HEADED. J-BOLTS SHALL NOT BE USED.

14. BOLTED CONNECTIONS SHALL HAVE A MINIMUM OF TWO 3/4" DIAMETER BOLTS UNLESS SHOWN OTHERWISE.

15. UNLESS NOTED OTHERWISE, BOLTS SHALL BE INSTALLED "SNUG TIGHT". THE SNUG TIGHT CONDITION IS DEFINED AS THE TIGHTNESS THAT EXISTS WHEN ALL PILES OF THE JOINT ARE IN FIRM CONTACT. BOLTS OF SLOTTED CONNECTIONS SHALL BE INSTALLED "HAND TIGHT" ONLY, WITH THREADS SPOILED. THE HAND TIGHT CONDITION IS DEFINED AS THE TIGHTNESS THAT EXISTS WHEN THE WASHER AND BOLT HEAD ARE BROUGHT INTO FULL CONTACT WITH WEB OR SHEAR TAB WITH A SPUD WRENCH AND THE NUT IS THEN BACKED OFF ONE QUARTER OF A TURN. WHERE SLOTTED CONNECTIONS ARE INDICATED, THE WASHER SHALL BE PLACED OVER THE SLOTTED HOLE. BOLTS INDICATED AS SLIP-CRITICAL SHALL BE PRE-TENSIONED PER SECTION 8.2 OF SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS.

16. HOLES FOR BOLTED CONNECTIONS AND ANCHOR BOLTS SHALL BE ALSO "STANDARD" HOLES LIMITED TO 1/16-INCH LARGER IN DIAMETER THAN NOMINAL BOLT DIAMETER FOR 7/8-INCH DIAMETER BOLTS AND SMALLER, AND 1/8-INCH LARGER IN DIAMETER THAN NOMINAL BOLT DIAMETER FOR 1-INCH AND LARGER BOLTS, UNLESS NOTED OTHERWISE. OVERSIZED AND SLOTTED HOLES REQUIRE THE APPROVAL OF THE SEOR, UNLESS SPECIFICALLY DETAILED ON THE APPROVED DRAWINGS.

17. PROVIDE BEVELED WASHERS WHERE JOINT FACE SLOPE IS GREATER THAN 1:20.

18. SEE CONCRETE GENERAL NOTES FOR NON-SHRINK GROUT SPECIFICATIONS.

19. FLANGE STIFFENER PLATES SHALL BE ORIENTED SO THAT ROLLING DIRECTION OF PLATE IS PARALLEL WITH DIRECTION OF PRINCIPLE STRESS.

20. ALL STRUCTURAL STEEL WELDING SHALL BE PERFORMED WITH E70XX ELECTRODES.

21. WHERE FILLET WELD SYMBOL IS SHOWN WITHOUT INDICATION OF THROAT SIZE, USE MINIMUM SIZE WELDS AS SPECIFIED BELOW.

TABLE J2.4

MINIMUM SIZE OF FILLET WELDS

MATERIAL THICKNESS OF THINNER PART JOINED

MINIMUM SIZE OF FILLET WELD

TO 1/4" (6MM) INCLUSIVE

1/8" (3MM)

OVER 1/4" (6MM) TO 1/2" (13MM)

3/16" (5MM)

OVER 1/2" (13MM) TO 3/4" (19MM)

1/4" (6MM)

OVER 3/4" (19MM)

5/16" (8MM)

22. WHERE LENGTH OF WELD IS NOT INDICATED, WELD SHALL BE FULL LENGTH OF JOINT.

23. ALL COMPLETE- AND PARTIAL-JOINT-PENETRATION GROOVE WELDS SHALL BE PERFORMED USING "INNERSHIELD" AND "MIG-2" SEMI-AUTOMATIC EQUIPMENT.

24. SEE SPECIAL INSPECTION AND TESTING NOTES FOR INSPECTION AND TESTING REQUIREMENTS.

POST-INSTALLED ANCHORS:

1. POST INSTALLED ANCHOR NOTES IN THIS SECTION SHALL APPLY TO ALL ANCHORS (INCLUDING THREADED ROD OR REINFORCING BARS) INSTALLED INTO HARDENED CONCRETE OR MASONRY EXCEPT FOR POWDER DRIVEN FASTENERS, AS APPLICABLE. SEE POWDER DRIVEN FASTENER GENERAL NOTES FOR MORE INFORMATION.

2. INSTALLATION SHALL CONFORM TO THE MANUFACTURER'S INSTRUCTIONS AND THE APPLICABLE EVALUATION REPORT AND SHALL BE INSTALLED BY PERSONNEL TRAINED TO INSTALL THE TYPE OF POST-INSTALLED ANCHOR BEING INSTALLED.

3. LOCATE EXISTING REINFORCING BY NON-DESTRUCTIVE METHODS PRIOR TO DRILLING. EXISTING REINFORCING SHALL NOT BE CUT OR DAMAGED.

4. CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF $f_{c'} = 2000$ PSI, BE A MINIMUM OF 21 DAYS OLD AND HAVE A MINIMUM TEMPERATURE OF 40 DEGREES FAHRENHEIT WHEN DRILLING OCCURS.

5. HOLES FOR INSTALLATION OF THE POST-INSTALLED ANCHOR SHALL BE DRILLED USING A DRILL THAT HAS A CARBIDE-TIPPED BIT THAT COMPLIES WITH AWS B212.15. A REBAR CUTTING DRILL BIT IS NOT ALLOWED.

6. CONTRACTOR SHALL USE APPROPRIATE EQUIPMENT AND METHODS AS REQUIRED TO PROVIDE DRILLED HOLES FOR POST-INSTALLED ANCHORS IN ACCORDANCE WITH APPLICABLE STANDARDS, MANUFACTURER'S RECOMMENDATIONS, AND QUALIFYING (IC) TEST REPORTS. CARE SHALL BE TAKEN TO PREVENT OVERSIZING, OVALING, AND/OR BLOW-OUT THROUGH THE BACK FACE OF THE DRILLED MEMBER. IF OVERSIZING, OVALING, AND/OR BLOW-OUT OCCURS, THE EMPLOYED EQUIPMENT AND METHODS SHALL BE DISCONTINUED. ADDITIONAL DRILLING SHALL NOT BE RESUMED UNTIL THE SEOR HAS PROVIDED APPROVED REPAIR PROCEDURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COST OF ALL SUCH REPAIRS. WHEN RESUMING DRILLING, THE CONTRACTOR SHALL MODIFY THE PROCEDURES AS NECESSARY TO PREVENT FURTHER DAMAGE.

7. HOLES SHALL BE CLEANED OF DUST AND DEBRIS, USING A WIRE BRUSH AND COMPRESSED AIR OR MANUFACTURER'S BLOW-OUT BULB (AS PER MANUFACTURER'S RECOMMENDATIONS) AS REQUIRED TO REMOVE PARTICULATE DEBRIS AND TO ACHIEVE A RELATIVELY DUST-FREE SURFACE.

8. OIL, SCALE, AND RUST SHALL BE REMOVED FROM THE POST-INSTALLED ANCHOR AND HOLES SHALL BE DRY, PRIOR TO INSTALLATION.

9. POST-INSTALLED EMBEDMENT DEPTHS NOTED ON THE PLANS OR DETAILS ARE NOMINAL (I.E. MEASURED FROM FACE OF CONCRETE OR MASONRY TO EMBEDDED TIP OF ANCHOR/REBAR). FOR CORRESPONDING HOLE DEPTH, REFER TO APPLICABLE EVALUATION REPORT.

10. APPROVED ADHESIVE ANCHOR SYSTEMS (AND ANCHOR SPECIFICATION) AND EVALUATION REPORTS ARE AS FOLLOWS:

A. CONCRETE

• HILTI HIT-RE 500 V3 (ISO 898 CLASS 5.8)

ESR-3814

• HILTI HIT-HY 200 (ISO 898 CLASS 5.8)

ESR-3187

B. SOLID-GROUTED CONCRETE MASONRY (CMU):

ESR-3200

C. DEWALT AC108-GOLD (A36)

ESR-3200

D. HORIZONTAL SLAB-ON-GRADE DOWELS:

ESR-3029

• HILTI HIT-RE 100

ESR-2508

• SIMPSON TITEN HD

ESR-2508

11. ALL EXPANSION ANCHORS SHALL BE INSTALLED WITH THE REQUIRED TORQUE AS NOTED IN THE APPLICABLE EVALUATION REPORT. APPROVED EXPANSION ANCHORS AND EVALUATION REPORTS ARE AS FOLLOWS:

A. CONCRETE NOT EXPOSED TO WEATHER

• HILTI KWIK BOLT-TZ 2 ANCHORS

ESR-4266

• SIMPSON STRONG-TIE STRONG-BOLT 2 WEDGE ANCHOR

ESR-3037

B. CONCRETE EXPOSED TO WEATHER

• STAINLESS STEEL HILTI KWIK BOLT-TZ 2 ANCHORS

ESR-4266

• STAINLESS STEEL SIMPSON STRONG-TIE STRONG-BOLT 2 WEDGE ANCHOR

ESR-3037

C. SOLID-GROUTED CONCRETE MASONRY (CMU):

ESR-4561

12. WHERE APPLICABLE, EXPANSION ANCHORS SHALL BE INSTALLED WITH THE MINIMUM TORQUE, USING A CALIBRATED TORQUE WRENCH. EXPANSION ANCHORS MUST ATTAIN THE SPECIFIED TORQUE WITHIN ONE HALF TURN OF THE NUT, EXCEPT 3/8" DIAMETER EXPANSION ANCHORS MUST ATTAIN SPECIFIED TORQUE WITHIN ONE QUARTER TURN OF THE NUT.

13. ALL SCREW ANCHORS SHALL BE INSTALLED WITH THE REQUIRED TORQUE AS NOTED IN THE APPLICABLE EVALUATION REPORT. APPROVED SCREW ANCHORS AND EVALUATION REPORTS ARE AS FOLLOWS:

A. CONCRETE

• HILTI HIT-REZ OR KH-EZ P ANCHORS

ESR-3027

• DEWALT SCREW-BOLT+

ESR-3689

• DEWALT TAPPER+

ESR-3268

• SIMPSON TITEN HD

ESR-2713

• ITW RED HEAD TAPCON+

ESR-3699

B. SOLID-GROUTED CONCRETE MASONRY (CMU):

• HILTI HIT-REZ OR KH-EZ P ANCHORS

ESR-3056

• DEWALT SCREW-BOLT+

ESR-4042

• DEWALT ULTRACON+

ESR-3196

• SIMPSON TITEN HD

ESR-1056

14. INSTALLATION TORQUES FOR SCREW ANCHORS SHALL BE AS NOTED BELOW.

15. SEE SPECIAL INSPECTION AND TESTING NOTES FOR INSPECTION REQUIREMENTS.

SPECIAL INSPECTIONS:

1. THE OWNER, OR THE OWNER'S AUTHORIZED AGENT (OTHER THAN THE CONTRACTOR AS APPLICABLE) SHALL EMPLOY ONE OR MORE SPECIAL INSPECTORS, INCLUDING AS APPLICABLE AN INSPECTOR OF RECORD (IOR), WHO SHALL PROVIDE SPECIAL INSPECTION DURING CONSTRUCTION FOR CERTAIN TYPES OF WORK WHEN SO SPECIFIED IN THE CONTRACT DOCUMENTS AND PROJECT SPECIFICATIONS. WHERE AN IOR IS REQUIRED BY THE GOVERNING AGENCY, THE IOR MAY PERFORM SPECIAL INSPECTIONS IF THAT PERSON IS QUALIFIED PER THE GOVERNING AGENCY'S STANDARDS FOR THE SPECIAL INSPECTION. WHERE AN IOR IS NOT REQUIRED, THESE SPECIAL INSPECTIONS SHALL BE IN ADDITION TO AND COMPLEMENTARY WITH THE INSPECTIONS PROVIDED BY THE GOVERNING AGENCY.

2. THE SPECIAL INSPECTOR SHALL BE A QUALIFIED PERSON FROM AN APPROVED AGENCY CONFORMING TO ASTM C1077 WHO SHALL DEMONSTRATE COMPETENCE TO THE SATISFACTION OF THE ARCHITECT, STRUCTURAL ENGINEER OF RECORD AND THE GOVERNING AGENCY, FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION.

3. THE SPECIAL INSPECTOR SHALL OBSERVE THE WORK ASSIGNED FOR CONFORMANCE WITH THE DESIGN DRAWINGS, SPECIFICATIONS AND APPLICABLE WORKMANSHIP PROVISIONS OF THE CODE AND OTHER APPLICABLE REGULATIONS IDENTIFIED WITHIN THE CONSTRUCTION DOCUMENTS. ALL DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE GENERAL CONTRACTOR FOR CORRECTION AND THEN, IF UNCORRECTED, TO THE ATTENTION OF THE ARCHITECT, STRUCTURAL ENGINEER OF RECORD AND THE GOVERNING AGENCY. IT SHALL BE THE GENERAL CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE SPECIAL INSPECTOR AND SCHEDULE THE SPECIAL INSPECTIONS WITH ADEQUATE TIME TO ADDRESS ANY AND ALL POTENTIAL DISCREPANCIES PRIOR TO PROCEEDING WITH SUBSEQUENT WORK THAT COVERS OR OTHERWISE MAKES INACCESSIBLE ANY WORK IDENTIFIED AS DEVIATING FROM THE PROJECT REQUIREMENTS.

4. THE SPECIAL INSPECTOR SHALL FURNISH REGULAR INSPECTION REPORTS TO THE ARCHITECT, STRUCTURAL ENGINEER OF RECORD AND THE GOVERNING AGENCY IDENTIFYING THE WORK INSPECTED AND ANY UNCORRECTED DISCREPANCIES FROM THE CONSTRUCTION DOCUMENTS. AT THE CONCLUSION OF THE PROJECT OR THE SPECIAL INSPECTOR'S ASSIGNED SCOPE OF WORK, THE SPECIAL INSPECTOR SHALL SUBMIT A FINAL SIGNED REPORT STATING WHETHER THE WORK REQUIRING SPECIAL INSPECTION WAS, TO THE BEST OF HIS OR HER KNOWLEDGE, COMPLETED IN CONFORMANCE WITH THE CONSTRUCTION DOCUMENTS AND SPECIFICATIONS (INCLUDING APPROVED WFS, ADDENDUMS, ETC.) AND THE APPLICABLE WORKMANSHIP PROVISIONS OF THE CODE AND OTHER APPLICABLE REGULATIONS IDENTIFIED WITHIN THE CONSTRUCTION DOCUMENTS.

5. UNLESS NOTED OTHERWISE, SPECIAL INSPECTIONS INDICATED BELOW SHALL BE PROVIDED IN EITHER A CONTINUOUS OR PERIODIC CAPACITY, AS DEFINED BELOW, AS REQUIRED BY THE INDIVIDUAL CODE OR REFERENCED STANDARD.

6. CONTINUOUS- SPECIAL INSPECTION BY THE SPECIAL INSPECTOR WHO IS PRESENT WHEN AND WHERE THE WORK TO BE INSPECTED IS BEING PERFORMED.

7. PERIODIC- SPECIAL INSPECTION BY THE SPECIAL INSPECTOR WHO IS INTERMITTENTLY PRESENT WHERE THE WORK TO BE INSPECTED HAS BEEN OR IS BEING PERFORMED, FOR STRUCTURAL STEEL. PERIODIC INSPECTION IS FURTHER DEFINED SUCH THAT ITEMS ARE OBSERVED ON A RANDOM BASIS.

8. FOR STRUCTURAL STEEL WELDING AND BOLTING, SPECIAL INSPECTION SHALL BE PROVIDED IN EITHER AN OBSERVE OR PERFORM CAPACITY AS DEFINED BELOW:

• OBSERVE (O)- INSPECTOR SHALL OBSERVE, THESE ITEMS ON A RANDOM BASIS

• PERFORM (P)- INSPECTOR SHALL OBSERVE OR PERFORM SPECIFIED TASK FOR EACH WELDED OR BOLTED JOINT OR MEMBER

9. QUALITY CONTROL (QC) INSPECTION TASKS SHALL BE PERFORMED BY THE FABRICATOR'S OR ERECTOR'S QC INSPECTOR (QC) AS INDICATED. QUALITY ASSURANCE (QA) INSPECTION TASKS SHALL BE PERFORMED BY THE QA INSPECTOR (QA) AS INDICATED. WHEN A TASK IS INDICATED TO BE PERFORMED BY BOTH THE QA AND QC, COORDINATION IS PERMITTED SO THAT THE INSPECTIONS MAY BE PERFORMED BY ONLY ONE PARTY. WHEN THE QA RELIES ON THE QC, THE APPROVAL OF THE SEOR AND AGENCY HAVING JURISDICTION IS REQUIRED.

10. THE FOLLOWING CONSTRUCTION ELEMENTS AND MATERIALS SHALL BE INSPECTED AND EVALUATED BY A SPECIAL INSPECTOR IN ACCORDANCE WITH THE NOTED CBC SECTIONS AND REFERENCED STANDARDS, WHERE ELEMENTS AND MATERIALS ARE PRESENT ON THE PROJECT. SEE GENERAL NOTES FOR EACH MATERIAL FOR ADDITIONAL REQUIREMENTS, IN ADDITION TO TABLES AND NOTES BELOW:

FOUNDATION SPECIAL INSPECTION TABLES:

REQUIRED VERIFICATION AND INSPECTION OF BOLTS PER CBC TABLE 1705.6

VERIFICATION AND INSPECTION	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED
1. VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY	---	X
2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REINFORCED PROPERLY	---	X
3. PERFORMANCE CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS	---	X
4. VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL	X	---
5. VERIFY MATERIALS, DENSITIES AND LIFT THICKNESSES AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY	---	X

REQUIRED VERIFICATION AND INSPECTION OF CAST-IN-PLACE DEEP FOUNDATION ELEMENTS PER CBC TABLE 1705.8

VERIFICATION AND INSPECTION	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED
1. INSPECT DRILLING OPERATIONS AND MAINTAIN COMPLETE AND ACCURATE RECORDS FOR EACH ELEMENT	X	---
2. VERIFY PLACEMENT LOCATIONS AND DIMENSIONS, CONFIRM ELEMENT DIAMETERS, BELL DIAMETERS (IF APPLICABLE), LENGTH, EMBEDMENT INTO BEDROCK (IF APPLICABLE) AND ADEQUATE END BEARING STRAIN CAPACITY. RECORD CONCRETE OR GROUT VOLUMES.	X	---

FOUNDATION SPECIAL INSPECTION NOTES:

1. FOR STEEL, CONCRETE OR CONCRETE-FILLED ELEMENTS PERFORM ADDITIONAL INSPECTIONS INDICATED BELOW AS APPLICABLE.

CONCRETE SPECIAL INSPECTION TABLE:

REQUIRED VERIFICATION AND INSPECTION OF CONCRETE CONSTRUCTION PER CBC TABLE 1705.3

VERIFICATION AND INSPECTION	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	REFERENCE FOR CRITERIA
1. INSPECT REINFORCING INCLUDING PRESTRESSING TENDONS AND VERIFY PLACEMENT	---	X	ASCI 318: CH 20.2, 20.3, 20.4, 20.5, 20.6, 20.7
2. PERFORMANCE CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS	---	X	ASCI 318: CH 20.2, 20.3, 20.4, 20.5, 20.6, 20.7
3. VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL	X	---	ASCI 318: CH 20.2, 20.3, 20.4, 20.5, 20.6, 20.7
4. VERIFY MATERIALS, DENSITIES AND LIFT THICKNESSES AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY	---	X	ASCI 318: CH 20.2, 20.3, 20.4, 20.5, 20.6, 20.7
5. INSPECT ALL OTHER WELDS	---	X	ASCI 318: CH 17.8.2
6. INSPECTION OF ANCHORS INSTALLED IN CONCRETE	---	X	ASCI 318: CH 17.8.2.4
7. INSPECT ANCHORS POST-INSTALLED IN HARDENED CONCRETE. MEMBER SIZE AND ADHESIVE ANCHORS SHALL BE INSTALLED HORIZONTALLY OR ORIENTATIONS TO RESIST TENSILE LOADS. MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED IN A.	X	---	ASCI 318: CH 17.8.2.4
8. VERIFY USE OF REQUIRED DESIGN MIX	---	X	ASCI 318: CH 19.3A.4, 19.3A.5, 19.3A.6
9. PRIOR TO CONCRETE PLACEMENT, FABRICATE SPECIMENS FOR STRENGTH TESTS (SEE NOTE 2 BELOW). CONDUCT TEMPERATURE AND CURING TESTS, AND OBTAIN THE TEMPERATURE OF THE CONCRETE.	X	---	ASTM C 172, 173, 174, 175, 176, 177, 178, 179, 180, 181, 182, 183, 184, 185, 186, 187, 188, 189, 190, 191, 192, 193, 194, 195, 196, 197, 198, 199, 200, 201, 202, 203, 204, 205, 206, 207, 208, 209, 210, 211, 212, 213, 214, 215, 216, 217, 218, 219, 220, 221, 222, 223, 224, 225, 226, 227, 228, 229, 230, 231, 232, 233, 234, 235, 236, 237, 238, 239, 240, 241, 242, 243, 244, 245, 246, 247, 248, 249, 250, 251, 252, 253, 254, 255, 256, 257, 258, 259, 260, 261, 262, 263, 264, 265, 266, 267, 268, 269, 270, 271, 272, 273, 274, 275, 276, 277, 278, 279, 280, 281, 282, 283, 284, 285, 286, 287, 288, 289, 290, 291, 292, 293, 294, 295, 296, 297, 298, 299, 300, 301, 302, 303, 304, 305, 306, 307, 308, 309, 310, 311, 312, 313, 314, 315, 316, 317, 318, 319, 320, 321, 322, 323, 324, 325, 326, 327, 328, 329, 330, 331, 332, 333, 334, 335, 336, 337, 338, 339, 340, 341, 342, 343, 344, 345, 346, 347, 348, 349, 350, 351, 352, 353, 354, 355, 356, 357, 358, 359, 360, 361, 362, 363, 364, 365, 366, 367, 368, 369, 370, 371, 372, 373, 374, 375, 376, 377, 378, 379, 380, 381, 382, 383, 384, 385, 386, 387, 388, 389, 390, 391, 392, 393, 394, 395, 396, 397, 398, 399, 400, 401, 402, 403, 404, 405, 406, 407, 408, 409, 410, 411, 412, 413, 414, 415, 416, 417, 418, 419, 420, 421, 422, 423, 424, 425, 426, 427, 428, 429, 430, 431, 432, 433, 434, 435, 436, 437, 438, 439, 440, 441, 442, 443, 444, 445, 446, 447, 448, 449, 450, 451, 452, 453, 454, 455, 456, 457, 458, 459, 460, 461, 462, 463, 464, 465, 466, 467, 468, 469, 470, 471, 472, 473, 474, 475, 476, 477, 478, 479, 480, 481, 482, 483, 484, 485, 486, 487, 488, 489, 490, 491, 492, 493, 494, 495, 496, 497, 498, 499, 500, 501, 502, 503, 504, 505, 506, 507, 508, 509, 510, 511, 512, 513, 514, 515, 516, 517, 518, 519, 520, 521, 522, 523, 524, 525, 526, 527, 528, 529, 530, 531, 532, 533, 534, 535, 536, 537, 538, 539, 540, 541, 542, 543, 544, 545, 546, 547, 548, 549, 550, 551, 552, 553, 554, 555, 556, 557, 558, 559, 560, 561, 562, 563, 564, 565, 566, 567, 568, 569, 570, 571, 572, 573, 574, 575, 576, 577, 578, 579, 580, 581, 582, 583, 584, 585, 586, 587, 588, 589, 590, 591, 592, 593, 594, 595, 596, 597, 598, 599, 600, 601, 602, 603, 604, 605, 606, 607, 608, 609, 610, 611, 612, 613, 614, 615, 616, 617, 618, 619, 620, 621, 622, 623, 624, 625, 626, 627, 628, 629, 630, 631, 632, 633, 634, 635, 636, 637, 638, 639, 640, 641, 642, 643, 644, 645, 646, 647, 648, 649, 650, 651, 652, 653, 654, 655, 656, 657, 658, 659, 660, 661, 662, 663, 664, 665, 666, 667, 668, 669, 670, 671, 672, 673, 674, 675, 676, 677, 678, 679, 680, 681, 682, 683, 684, 685, 686, 687, 688, 689, 690, 691, 692, 693, 694, 695, 696, 697, 698, 699, 700, 701, 702, 703, 704, 705, 706, 707, 708, 709, 710, 711, 712, 713, 714, 715, 716, 717, 718, 719, 720, 721, 722, 723, 724, 725, 726, 727, 728, 729, 730, 731, 732, 733, 734, 735, 736, 737, 738, 739, 740, 741, 742, 743, 744, 745, 746, 747, 748, 749, 750, 751, 752, 753, 754, 755, 756, 757, 758, 759, 760, 761, 762, 763, 764, 765, 766, 767, 768, 769, 770, 771, 772, 773, 774, 775, 776, 777, 778, 779, 780, 781, 782, 783, 784, 785, 786, 787, 788, 789, 790, 791, 792, 793, 794, 795, 796, 797, 798, 799, 800, 801, 802, 803, 804, 805, 806, 807, 808, 809, 810, 811, 812, 813, 814, 815, 816, 817, 818, 819, 820, 821, 822, 823, 824, 825, 826, 827, 828, 829, 830, 831, 832, 833, 834, 835, 836, 837, 838, 839, 840, 841, 842, 843, 844, 845, 846, 847, 848, 849, 850, 851, 852, 853, 854, 855, 856, 857, 858, 859, 860, 861, 862, 863, 864, 865, 866, 867, 868, 869, 870, 871, 872, 873, 874, 875, 876, 877, 878, 879, 880, 881, 882, 883, 884, 885, 886, 887, 888, 889, 890, 891, 892, 893, 894, 895, 896, 897, 898, 899, 900, 901, 902, 903, 904, 905, 906, 907, 908, 909, 910, 911, 912, 913, 914, 915, 916, 917, 918, 919, 920, 921, 922, 923, 924, 925, 926, 927, 928, 929, 930, 931, 932, 933, 934, 935, 936, 937, 938, 939, 940, 941, 942, 943, 944, 945, 946, 947, 948, 949, 950, 951, 952, 953, 954, 955, 956, 957, 958, 959, 960, 961, 962, 963, 964, 965, 966, 967, 968, 969, 970, 971, 972, 973, 974, 975, 976, 977, 978, 979, 980, 981, 982, 983, 984, 985, 986, 987, 988, 989, 990, 991, 992, 993, 994, 995, 996, 997, 998, 999, 1000

CONCRETE SPECIAL INSPECTION NOTES:

1. SPECIFIC REQUIREMENTS FOR SPECIAL INSPECTION ARE INCLUDED IN THE RESEARCH REPORT FOR EACH POST-INSTALLED ANCHOR ISSUED BY AN APPROVED SOURCE. THESE SPECIAL INSPECTION REQUIREMENTS SHOULD BE FOLLOWED, WHERE SPECIFIC REQUIREMENTS ARE NOT PROVIDED, CONTACT STRUCTURAL ENGINEER FOR SPECIAL INSPECTION REQUIREMENTS PRIOR TO PROCEEDING WITH THE WORK. PROJECT SPECIFIC SPECIAL INSPECTION MEASURES SHALL BE APPROVED BY THE GOVERNING AGENCY PRIOR TO THE COMMENCEMENT OF THE WORK.

2. A STRENGTH TEST SHALL BE THE AVERAGE OF, AT A MINIMUM, TWO 6x12 CYLINDERS OR THREE 4x8 CYLINDERS MADE FROM THE SAME SAMPLE OF CONCRETE. A TESTING LABORATORY SHALL MAKE AND TEST ONE SAMPLE SET FOR EACH 150 CUBIC YARDS OF CONCRETE BUT NOT LESS THAN ONE SAMPLE SET FOR EACH 5,000 SQ FT OF SURFACE AREA FOR SLABS OR WALLS. IF TOTAL VOLUME OF CONCRETE IS SUCH THAT FREQUENCY OF TESTING WOULD PRODUCE FEWER THAN A GIVEN CONCRETE MIXTURE, THEN STRENGTH TEST SPECIMENS SHALL BE MADE FROM AT LEAST 5 RANDOMLY SELECTED BATCHES OR FROM EACH BATCH IF FEWER THAN 5 BATCHES ARE USED.

STEEL SPECIAL INSPECTION TABLES:

INSPECTION TASKS PRIOR TO WELDING PER AISC 360 TABLE B6.4.1

INSPECTION TASKS PRIOR TO WELDING	QC	QA
1. WELDING QUALIFICATION RECORDS AND CERTIFICATION RECORDS	P	O
2. WELDING PROCEDURE SPECIFICATIONS (WPS) AVAILABLE	P	P
3. MANUFACTURER CERTIFICATIONS FOR WELDING CONSUMABLES AVAILABLE	P	P
4. MATERIAL IDENTIFICATION (TAGGING)	O	O
5. WELDER IDENTIFICATION SYSTEM	O	O
6. IF USE OF GROOVE WELDS (INCLUDING JOINT GEOMETRY) HAVE A MINIMUM TEMPERATURE OF 40 DEGREES FAHRENHEIT WHEN DRILLING OCCURS: <div><div><div>• DIMENSIONS ALIGNMENT: ROOT OPENING, ROOT FACE BEVEL</div><div>O</div><div>O</div></div><div><div>• CLEANLINESS (CONDITION OF STEEL SURFACES)</div><div>P</div><div>O</div></div><div><div>• TACKING (TACK WELD QUALITY AND LOCATION)</div><div>P</div><div>O</div></div></div>		


| 7. IF USE OF CP GROOVE WELDS OF F80-T-1Y AND K-ANTS WITHOUT BACKING: • JOINT PREPARATIONS P O • DIMENSIONS ALIGNMENT: ROOT OPENING, ROOT FACE BEVEL P O • CLEANLINESS (CONDITION OF STEEL SURFACES) P O • TACKING (TACK WELD QUALITY AND LOCATION) P O |

| 8. CONFIGURATION AND FINISH OF ACCESS HOLES | O | O |
| 9. IF USE OF FILLET WELDS: • DIMENSIONS ALIGNMENT: GAPS AT ROOT O O • CLEANLINESS (CONDITION OF STEEL SURFACES) O O • TACKING (TACK WELD QUALITY AND LOCATION) O O |

| 10. CHECK WELDING EQUIPMENT | O | --- |
| 11. THE FABRICATOR OR ERECTOR, AS APPLICABLE, SHALL MAINTAIN A SYSTEM BY WHICH A WELDER WHO HAS WELDED A JOINT OR MEMBER CAN BE IDENTIFIED. STAMPS, IF USED, SHALL BE THE LOW-STRESS TYPE. | P | P |

INSPECTION TASKS DURING WELDING PER AISC 360 TABLE B6.4.2

INSPECTION TASKS DURING WELDING	QC	QA



SCALE: 1" = 50'

14-H-202312301203 DrawingsIDwgs-00123-0120-00 S-1.01 SITE PLAN.dwg PLOTTED BY: Shawn Alvira ON: September 26, 2024

PLAN NOTES	
1.	SEE GENERAL NOTES SHEET(S) FOR APPLICABLE NOTES, ABBREVIATIONS AND PLAN SYMBOLS/LEGEND.
2.	EXISTING CONSTRUCTION IS SHOWN FADDED AND IS LABELED AS EXISTING OR (E). NEW CONSTRUCTION IS SHOWN DARK AND IS SPECIFICALLY REFERENCED BY DETAILS AND NOTES.
3.	EXISTING CONDITIONS ARE SHOWN TO THE BEST OF OUR KNOWLEDGE. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ACTUAL CONDITIONS. DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THOSE SHOWN ON THESE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO PROCEEDING.
4.	FOUNDATION EXCAVATIONS MUST BE INSPECTED AND APPROVED BY THE GEOTECHNICAL CONSULTANT PRIOR TO THE PLACING OF STEEL OR CONCRETE.

THESE DRAWINGS ARE THE PROPERTY AND
COPYRIGHT OF JTC ARCHITECTS, INC.
REUSE, REPRODUCTION OR PUBLICATION
BY ANY METHOD IN WHOLE OR IN PART
THEREOF WITHOUT THE EXPRESS WRITTEN
CONSENT OF JTC ARCHITECTS, INC. IS NOT
PERMITTED.



LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :

BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT



JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D

SEAL :



CONSULTANT :

MHP
STRUCTURAL ENGINEERS
LONG BEACH • SAN DIEGO
LONG BEACH OFFICE
3900 Cover Street, Long Beach
CA 90808 • 562.985.3200
Project: 23-0120-00

TITLE:

SITE PLAN

SCALE: AS NOTED

DATE: 02-04-25




DRAWN BY: GL

CHECKED BY: GM, SH

SHEET NUMBER:

S-1.01

H:\2023\201703 Drawings\2023\10\03 S-2.00 PARTIAL SECURITY WALL FOUNDATION PLANS.dwg PLOTTED BY: Sham Avara ON: September 26, 2024





- PLAN NOTES**
- SEE GENERAL NOTES SHEET(S) FOR APPLICABLE NOTES, ABBREVIATIONS AND PLAN SYMBOLS LEGEND.
 - EXISTING CONSTRUCTION IS SHOWN FADED AND IS LABELED AS EXISTING OR (E). NEW CONSTRUCTION IS SHOWN DARK AND IS SPECIFICALLY REFERENCED BY DETAILS AND NOTES.
 - EXISTING CONDITIONS ARE SHOWN TO THE BEST OF OUR KNOWLEDGE. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ACTUAL CONDITIONS. DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THOSE SHOWN ON THESE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO PROCEEDING.
 - DIMENSIONS OF EQUIPMENT ANCHOR MOUNTING LOCATIONS SHOWN ON PLANS AND/OR DETAILS ARE TO BE COORDINATED WITH ACTUAL EQUIPMENT TO BE INSTALLED.
 - CONTRACTOR TO VERIFY THE EXACT SIZE AND LOCATION OF ALL EQUIPMENT ANCHOR MOUNTING HOLES PRIOR TO INSTALLATION. WHERE ACTUAL EQUIPMENT DIMENSIONS DO NOT FALL WITHIN THE MINIMUM OR MAXIMUM DIMENSIONS PROVIDED ON PLANS AND/OR DETAILS, NOTIFY SEOR AND AWAIT DIRECTION PRIOR TO PROCEEDING WITH WORK.
 - DO NOT CUT ANY NEW OPENINGS OR ENLARGE ANY EXISTING OPENINGS IN THE ROOF (FOR DUCTS, PIPES, ETC.) UNLESS SPECIFICALLY SHOWN ON THESE STRUCTURAL DRAWINGS.
 - ALL EXTERIOR STEEL MEMBERS TO BE HOT DIP GALVANIZED.
 - FOUNDATION EXCAVATIONS MUST BE INSPECTED AND APPROVED BY THE GEOTECHNICAL CONSULTANT(S) PRIOR TO THE PLACING OF STEEL OR CONCRETE.

COLUMN SCHEDULE		
COLUMN MARK	COLUMN SIZE	REFERENCE DETAIL
C1	HSS10x6x1/2	1/S-3.01
C2	HSS10x6x5/8	1/S-3.01
C3	HSS10x8x5/8	1/S-3.01

FENCE FOOTING SCHEDULE			
FOOTING MARK	D FOOTING DIAMETER	E FOOTING EMBEDMENT	VERTICAL BARS
F1	2'-0"	11'-0"	(6) #8
F2	2'-0"	MINIMUM	(7) #8
F3	2'-0"	SEE NOTE 2	(7) #8

NOTES:

- REFERENCE DETAIL C7/S-3.00 FOR SECTION AT FOOTING
- FOOTING EMBEDMENT SHALL BE EMBEDDED AT LEAST 12 INCHES INTO UNDISTURBED ALLUVIAL SOILS FOUND AT OR BELOW A DEPTH OF 11 FEET.



THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.



LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :

BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT :

JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D
SEAL :

CONSULTANT :


MH
STRUCTURAL ENGINEERS
LONG BEACH • SAN DIEGO
LONG BEACH OFFICE
3900 Cover Street, Long Beach
CA 90809 • 562.985.3200
Project: 23-0120-00

TITLE:

**PARTIAL SECURITY WALL
FOUNDATION PLANS**


SCALE: AS NOTED
DATE: 02-04-25
DRAWN BY: GL
CHECKED BY: GM, SH
SHEET NUMBER:

S-2.00




PARTIAL EXTERIOR EAST SECURITY FOUNDATION PLAN (WALL C)

SCALE: 1/16" = 1'-0"



PARTIAL EXTERIOR EAST SECURITY FOUNDATION PLAN (WALL C)

SCALE: 1/16" = 1'-0"



PARTIAL EXTERIOR EAST SECURITY FOUNDATION PLAN (WALL D)

SCALE: 1/16" = 1'-0"


- PLAN NOTES**
- SEE GENERAL NOTES SHEET(S) FOR APPLICABLE NOTES, ABBREVIATIONS AND PLAN SYMBOLS LEGEND.
 - EXISTING CONSTRUCTION IS SHOWN FADED AND IS LABELED AS EXISTING OR (E). NEW CONSTRUCTION IS SHOWN DARK AND IS SPECIFICALLY REFERENCED BY DETAILS AND NOTES.
 - EXISTING CONDITIONS ARE SHOWN TO THE BEST OF OUR KNOWLEDGE. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ACTUAL CONDITIONS. DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THOSE SHOWN ON THESE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO PROCEEDING.
 - DIMENSIONS OF EQUIPMENT ANCHOR MOUNTING LOCATIONS SHOWN ON PLANS AND/OR DETAILS ARE TO BE COORDINATED WITH ACTUAL EQUIPMENT TO BE INSTALLED.
 - CONTRACTOR TO VERIFY THE EXACT SIZE AND LOCATION OF ALL EQUIPMENT ANCHOR MOUNTING HOLES PRIOR TO INSTALLATION. WHERE ACTUAL EQUIPMENT DIMENSIONS DO NOT FALL WITHIN THE MINIMUM OR MAXIMUM DIMENSIONS PROVIDED ON PLANS AND/OR DETAILS, NOTIFY SEOR AND AWAIT DIRECTION PRIOR TO PROCEEDING WITH WORK.
 - DO NOT CUT ANY NEW OPENINGS OR ENLARGE ANY EXISTING OPENINGS IN THE ROOF (FOR DUCTS, PIPES, ETC.) UNLESS SPECIFICALLY SHOWN ON THESE STRUCTURAL DRAWINGS.
 - ALL EXTERIOR STEEL MEMBERS TO BE HOT DIP GALVANIZED.
 - FOUNDATION EXCAVATIONS MUST BE INSPECTED AND APPROVED BY THE GEOTECHNICAL CONSULTANT(S) PRIOR TO THE PLACING OF STEEL OR CONCRETE.

COLUMN SCHEDULE		
COLUMN MARK	COLUMN SIZE	REFERENCE DETAIL
C1	HSS10x6x1/2	1/S-3.01
C2	HSS10x6x5/8	1/S-3.01
C3	HSS10x8x5/8	1/S-3.01

FENCE FOOTING SCHEDULE			
FOOTING MARK	D FOOTING DIAMETER	E FOOTING EMBEDMENT	VERTICAL BARS
F1	2'-0"	11'-0"	(6) #8
F2	2'-0"	MINIMUM	(7) #8
F3	2'-0"	SEE NOTE 2	(7) #8

NOTES:

- REFERENCE DETAIL C7/S3.00 FOR SECTION AT FOOTING.
- FOOTING EMBEDMENT SHALL BE EMBEDDED AT LEAST 12 INCHES INTO UNDISTURBED ALLUVIAL SOILS FOUND AT OR BELOW A DEPTH OF 11 FEET.



KEY PLAN

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.



LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :

BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT :

JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D

SEAL :

REGISTERED PROFESSIONAL ENGINEER
No. 3503
JAMES E. HARRIS
STATE OF CALIFORNIA

CONSULTANT :

MH
STRUCTURAL ENGINEERS
LONG BEACH • SAN DIEGO
LONG BEACH OFFICE
3900 Cover Street, Long Beach
CA 90809 • 562-985-3200
Project: 23-0120-00

TITLE:

**PARTIAL SECURITY WALL
FOUNDATION PLANS**

SCALE: AS NOTED
DATE: 02-04-25
DRAWN BY: GL
CHECKED BY: GM, SH
SHEET NUMBER:

S-2.01

H:\2023\201703 Drawings\Drawings\02-04-25 S-2.02 PARTIAL ROOF FRAMING PLAN.dwg PLOTTED BY: Shivan Arora ON: September 26, 2024

- FRAMING PLAN NOTES
1.

SEE GENERAL NOTES SHEET(S) FOR APPLICABLE NOTES, ABBREVIATIONS AND PLAN SYMBOLS LEGEND.
2.



EXISTING CONSTRUCTION IS SHOWN FADED AND IS LABELED AS EXISTING OR (E). NEW CONSTRUCTION IS SHOWN DARK AND IS SPECIFICALLY REFERENCED BY DETAILS AND NOTES.
3.

EXISTING CONDITIONS ARE SHOWN TO THE BEST OF OUR KNOWLEDGE. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ACTUAL CONDITIONS. DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THOSE SHOWN ON THESE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO PROCEEDING.
4.

DIMENSIONS OF EQUIPMENT ANCHOR MOUNTING LOCATIONS SHOWN ON PLANS AND/OR DETAILS ARE TO BE COORDINATED WITH ACTUAL EQUIPMENT TO BE INSTALLED.
5.

CONTRACTOR TO VERIFY THE EXACT SIZE AND LOCATION OF ALL EQUIPMENT ANCHOR MOUNTING HOLES PRIOR TO INSTALLATION. WHERE ACTUAL EQUIPMENT DIMENSIONS DO NOT FALL WITHIN THE MINIMUM OR MAXIMUM DIMENSIONS PROVIDED ON PLANS AND/OR DETAILS, NOTIFY SEOR AND AWAIT DIRECTION PRIOR TO PROCEEDING WITH WORK.
6.

DO NOT CUT ANY NEW OPENINGS OR ENLARGE ANY EXISTING OPENINGS IN THE ROOF (FOR DUCTS, PIPES, ETC.) UNLESS SPECIFICALLY SHOWN ON THESE STRUCTURAL DRAWINGS.



PARTIAL ROOF FRAMING PLAN
SCALE: 1/4" = 1'-0"

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.



LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :

BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT :

JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D

SEAL :



CONSULTANT :

MH
STRUCTURAL ENGINEERS
LONG BEACH • SAN DIEGO
LONG BEACH OFFICE
3900 Cover Street, Long Beach
CA 90808 • 562-985-3200
Project: 23-0120-00

TITLE:

PARTIAL ROOF FRAMING PLAN

SCALE: AS NOTED

DATE: 02-04-25






DRAWN BY: GL

CHECKED BY: GM, SH

SHEET NUMBER:

S-2.02

H:\2023\201703 Drawings\Drawings\02-24\100-00 S-3.01 SECTIONS AND DETAILS.dwg PLOTTED BY: Shaw Alvia ON: September 26, 2024



NO.	DATE	BY	REVISIONS
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.

PUBLIC WORKS

LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :
**BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241**

LOCATION :
**16350 FILBERT STREET,
SYLMAR, CA 91342**

ARCHITECT :
**JTC
architects, inc.**
65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D

SEAL :
**James E. Harris
Professional Engineer
No. 35033
State of California**


CONSULTANT :
**MH
STRUCTURAL ENGINEERS
LONG BEACH • SAN DIEGO
LONG BEACH OFFICE
3900 Cover Street, Long Beach
CA 90808 • 562-585-3200
Project: 23-0120-00**

TITLE:
SECTIONS AND DETAILS

SCALE: AS NOTED
DATE: 02-04-25
DRAWN BY: GL
CHECKED BY: GM, SH
SHEET NUMBER:
S-3.01

<

THESE DRAWINGS ARE THE PROPERTY AND
COPYRIGHT OF JTC ARCHITECTS, INC.
REUSE, REPRODUCTION OR PUBLICATION
BY ANY METHOD IN WHOLE OR IN PART
THEREOF WITHOUT THE EXPRESS WRITTEN
CONSENT OF JTC ARCHITECTS, INC. IS NOT
PERMITTED.



PROJECT :

BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
 PW15739, PCA: P9700230,
 PCS ID: 2241

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT



JTC
architects, inc

**65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006**


TEL : 626-254-8884 FAX : 626-574-7775

ITC PROJECT NO: 27022-25

SEAL :



CONSULTANT

23990  dHA + CALPEC
150 S. ARROYO PARKWAY
SUITE NO. 100
PASADENA, CA. 91105
TEL: (626) 445-8580
FAX: (626) 445-8987

TITLE:

MECHANICAL LEGEND

NOTES AND ABBREVIATIONS

SCALE:	
DATE:	02-04-25
DRAWN BY:	dHA + CALPEC
CHECKED BY:	KC/AI
SHEET NUMBER:	

M-0.01

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 1 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 1 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

A. GENERAL INFORMATION			
01 Project Location (city)	Sylmar	04 Total Conditioned Floor Area	200
02 Climate Zone	9	05 Total Unconditioned Floor Area	0
03 Occupancy Types Within Project:		06 # of Stories (Habitable Above Grade)	0
• All Other Occupancies			

B. PROJECT SCOPE
This table is used to demonstrate compliance for mechanical systems or components that are within the scope of the permit application and are demonstrating compliance using the prescriptive path outlined in 140.4, 170.2(b) or 141.0(b)(2) and 180.2(b)(2) for alterations.

01	02	03
Air System(s)	Wet System Components	Dry System Components
<input type="checkbox"/> Heating Air System	<input type="checkbox"/> Water Economizer	<input type="checkbox"/> Air Economizer
<input checked="" type="checkbox"/> Cooling Air System	<input type="checkbox"/> Pumps	<input type="checkbox"/> Electric Resistance Heat
<input type="checkbox"/> Mechanical Controls	<input type="checkbox"/> System Piping	<input checked="" type="checkbox"/> Fan Systems
<input checked="" type="checkbox"/> Mechanical Controls (existing to remain, altered or new)	<input type="checkbox"/> Cooling Towers	<input type="checkbox"/> Ductwork (existing to remain, altered or new)
	<input type="checkbox"/> Chillers	<input checked="" type="checkbox"/> Ventilation
	<input type="checkbox"/> Boilers	<input type="checkbox"/> Zonal Systems/ Terminal Boxes

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 4 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 4 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

G. PUMPS
This section does not apply to this project.

H. FAN SYSTEMS & AIR ECONOMIZERS
This table is used to demonstrate compliance with prescriptive requirements found in 140.4(c), 140.4(e), 140.4(m), 170.2(c)(3), and 170.2(c)(4A) for fan systems. Fan systems serving only process loads are exempt from these requirements and do not need to be included in Table H.

System Name	FC-1, 2	Quantit y	2	Fan System Status	New	System Zoning	all other systems	Serving Dwelling Units	06	Not Serving Dwelling Units	07	Fan System Airflow (cfm)	381	Site Elevation	1,270	Economizer	NA: <=33 kbtu/h cooling
01	02	03	04	05	06	07	08	09	10	11							
Fan Name or Item Tag	Fan Type	Qty	Component	Airflow through Component (%)	Water Gauge (wg)	Componen t Allowance	Fan Allowance (watt/cfm)	Design Electrical Input Power Method	Motor Nameplate Horsepower	Design Electrical Input Power (kW)							
FC-1, FC-2	Supply	2	Hydronic/DX cooling coil or heat pump coil	100		0.13	0.139	Manufacturer provided		0.01							
Supply Fan Base Allowance (kW)			Exhaust/Return/Relief/Transfer Fan Base Allowance (kW)			Fan System Allowance (kW) ¹		Fan System Electrical Output (kW)		0.04							

¹ FOOTNOTES: Fans serving spaces with design background noise goals below NC35
² Low-turn-down single-zone VAV fan system must be capable of and configured to reduce airflow to 50 percent of design airflow and use no more than 30 percent of the design wattage at that airflow. No more than 10 percent of the design load served by the equipment shall have fixed loads.
³ Fan system allowance includes fan system base allowance.
⁴ Filter pressure loss can only be counted once per fan system.
⁵ Complex Fan System means a fan system that combines a single cabinet fan system with other supply fans, exhaust fans, or both.
⁶ Computer room economizers must meet requirements of 140.9(a) and will be documented on the NRCC-PRC-E document.

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 7 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 7 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

J. VENTILATION AND INDOOR AIR QUALITY
³ For lecture halls with fixed seating, the expected number of occupants shall be determined in accordance with the California Building Code.
⁴ 120.2(e)(3) requires systems serving rooms that are required by 130.1(c) to have lighting occupancy sensing controls to also have occupancy sensing zone controls for ventilation. Examples of spaces which require lighting occupancy sensors include offices 250ft² or smaller, multipurpose rooms less than 1,000 ft², classrooms, conference rooms, restrooms, aisles and open areas in warehouses, library book stack aisles, corridors, stairwells, parking garages, and loading and unloading zones, unless excepted by 130.1(c).

K. TERMINAL BOX CONTROLS
This section does not apply to this project.

L. DISTRIBUTION (DUCTWORK AND PIPING)
This section does not apply to this project.

M. COOLING TOWERS
This section does not apply to this project.

N. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION
Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/programs-and-topics/programs/building-energy-efficiency-standards/2022-building-energy-efficiency-4

Form/Title	
NRCI-MCH-01-E - Must be submitted for all buildings	

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 2 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 2 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

C. COMPLIANCE RESULTS																
Table C will indicate if the project data input into the compliance document is compliant with mechanical requirements. This table is not editable by the user. If this table says "DOES NOT COMPLY" or "COMPLIES with Exceptional Conditions" refer to Table D, or the table indicated as not compliant for guidance.																
01	02		03		04		05		06		07		08		09	
System Summary 110.1, 110.2, 140.4, 170.2(c)	AND	Pumps 140.4(k), 170.2(c)(4)	AND	Fans/Economizers 140.4(c), 140.4(e), 170.2(c)	AND	System Controls 110.2, 120.2, 140.4(f), 170.2(c)	AND	Ventilation 120.1, 160.2	AND	Terminal Box Controls 140.4(d), 170.2(c)(4B)	AND	Distribution 120.3, 140.4(i), 160.2, 160.3	AND	Cooling Towers 110.2(e)(2)	Compliance Results	
(See Table F)	(See Table G)		(See Table H)		(See Table I)		(See Table J)		(See Table K)		(See Table L)		(See Table M)			
Yes	AND		AND	Yes	AND	Yes	AND	Yes	AND		AND		AND		AND	COMPLIES with Exceptional Conditions
Mandatory Measures Compliance (See Table Q for Details)											COMPLIES					

D. EXCEPTIONAL CONDITIONS
This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.

The permit applicant has indicated on Table J that natural ventilation is being utilized to meet ventilation requirements. Additional documentation may be requested by the Authority Having Jurisdiction demonstrating compliance for natural ventilation design.
Transfer air is being used in at least one zone to meet minimum ventilation requirements. See Table J for details. Transfer air must be designed per §120.1(g) for air classification and recirculation limitations and be documented within construction documents.

E. ADDITIONAL REMARKS
This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 5 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 5 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

H. EXHAUST AIR HEAT RECOVERY 140.4(q), 170.2(c)(4D)

01	02	03	04	05	06	07	08	09	10	11
Fan System Name	Qty	Hours of Operation per Year	Design Supply Airflow Rate	Outdoor Airflow	% Outdoor Air at Full Design Airflow	Exemptions to Exhaust Air Heat Recovery Requirement per 140.4(q) and 170.2(c)(4D)	Exhaust Air Heat Recovery 140.4(q) and 170.2(c)(4D)	Type Of Heat Recovery Rating	Required Recovery Ratio	Energy Recovery Bypass
FC-1, 2			381	15	0.04	NA: Serving space not cooled and heated to <60 F				

Fan Energy Index (FEI)

01	02	03
Name or Item Tag	FEI Exception	FEI
FC-1, 2	Embedded Fan <5HP or <4.1kW	

I. SYSTEM CONTROLS
This table is used to demonstrate compliance with mandatory controls in 110.2 and 120.2 and prescriptive controls in 140.4(f) and (i), 170.2(c)(4D) 170.2(c)(4L) or requirements in 141.0(b)(2)E and 180.2(b)(2) for altered space conditioning systems.

01	02	03	04	05	06	07	08	09	10
System Name	System Zoning	Conditione d Floor Area Being Served (ft²)	Thermostats 110.2(b) & (c) ¹ , 120.2(a) 160.3(a)(2A) or 141.0(b)(2)E & 180.2(b)(2)	Shut-Off Controls 120.2(e) & 160.3(a)(2D)	Isolation Zone Controls 120.2(g) & 160.3(a)(2F)	Demand Response 110.12 120.2(b) & 140.4(f) & 160.3(a)(2B)	Supply Air Temp. Reset. 140.4(f) & 170.2(c)(4D)	Window Interlocks per 140.4(n) & 170.2(c)(4D)	Direct Digital Control (DDC) per 120.2
FC-1, 2	Single zone	<= 25,000 ft²	EMCS	NA: Altered per 141.0(b)(2)E	NA: Serves < 25k ft²	EMCS	NA: Alteration	NA: Alteration Project	NA: Single Zone

¹ FOOTNOTES: Gravity gas wall heaters, gravity floor heaters, gravity room heaters, non-central electric heaters, fireplaces or decorative gas appliances, wood stoves are not required to have setback thermostats.

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 6 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 6 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

O. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE
Selections have been made based on information provided in previous tables of this document. If any selection needs to be changed, please explain why in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online at https://www.energy.ca.gov/programs-and-topics/programs/building-energy-efficiency-standards/2022-building-energy-efficiency-4

Form/Title	Systems/Spaces To Be Field Verified
NRCA-MCH-02-A - Outdoor Air must be submitted for all newly installed HVAC units. Note: MCH-02-A can be performed in conjunction with MCH-07-A Supply Fan VFD Acceptance (if applicable) since testing activities overlap.	FC-1, 2
NRCA-MCH-18-A Energy Management Control Systems	FC-1, 2

P. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION
There are no NRCV forms required for this project.

Q. MANDATORY MEASURES DOCUMENTATION LOCATION	
This table is used to indicate where mandatory measures are documented in the plan set or construction documentation.	
01	02
Compliance with Mandatory Measures documented through MCH	No
Mandatory Measures Note Block	Plan sheet or construction document location
03	04
Mandatory Measure	Plan sheet or construction document location
Heating Equipment Efficiency per 110.1	N/A
Cooling Equipment Efficiency per 110.1	N/A
Furnace Standby Loss Control per 110.2(f)	N/A
Heat Pump with Supplemental electric Resistance Heater Controls per 110.2(b)	N/A
Kitchen range hoods shall be rated for sound in accordance with Section 7.2 of ASHRAE 62.2	N/A

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 3 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 3 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

F. HVAC SYSTEM SUMMARY (DRY & WET SYSTEMS)
Space Conditioning System Information

01	02	03	04	05	06
System Name	Quantity	System Serving	System Status	Space Type	Utilizing Recovered Heat
CU-1	1	Single zone	New/ Addition	All Other Occupancies	<input type="checkbox"/>

Dry System Equipment Sizing (Includes air conditioners, condensers, heat pumps, VRF, furnaces and unit heaters and DOAS systems)

01	02	03	04	05	06	07	08	09	10	11
Name or Item Tag	Equipment Category per Tables 110.2, 140.4(a)(2) and 170.2(c)(3a)i	Equipment Type per Tables 110.2 and Title 20	Smallest Size Available ¹ 140.4(a) and 170.2(c)(1	Heating Output ^{2,3} Per Design (kbtu/h)	Rated (kbtu/h)	Supp. Heating Output (kbtu/h)	Sensible Per Design (kbtu/h)	Rated (kbtu/h)	Total Heating Load (kbtu/h)	Total Sensible Cooling Load (kbtu/h)
CU-1	Unitary Heat Pumps (no elec. resistance)	Air-cooled, pkg (1phase)	Yes	0	17	0	17,000	17.5	1	17

¹ FOOTNOTES: Equipment shall be the smallest size, within the available options of the desired equipment line, necessary to meet the design heating and cooling loads of the building per 140.4(a) and 170.2(c)(1). Healthcare facilities are excepted.
² It is common practice to show rated output capacity on the equipment schedule. Sensible cooling output comes from specification sheet tables.
³ If equipment is heating only, leave cooling output and load blank. If equipment is cooling only, leave heating output and load blank.
⁴ Authority Having Jurisdiction may ask for load calculations used for compliance per 140.4(b) and 170.2(c).

Dry System Equipment Efficiency (Other than Package Terminal Air Conditioners (PTAC) and Package Terminal Heat Pumps (PTHP), DX-DOAS and Dual Fuel Heat Pumps)

01	02	03	04	05	06	07	08	09
Name or Item Tag	Size Category (Btu/h)	Rating Condition ("F)	Efficiency Unit	Minimum Efficiency Required per Tables 110.2 / Title 20	Design Efficiency	Efficiency Unit	Minimum Efficiency Required per Tables 110.2 / Title 20	Design Efficiency
CU-1	<65,000					SEER2	13.4	17

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 6 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Report Page: (Page 6 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

I. VENTILATION AND INDOOR AIR QUALITY
This table is used to demonstrate compliance with mandatory ventilation requirements in 120.1 120.2(c)(3B 140.4(p) and 140.4(q) for all nonresidential and hotel/motel and d(24)refolink(160.2, 160.3(a)(3D, 170.2(a)(4N, 170.2(a)(4D for high-rise residential occupancies. For alterations, only ventilation systems being altered within the scope of the permit application need to be documented in this table. In lieu of this table, the required outdoor ventilation rates and airflow may be shown on the plans or the calculations can be presented in a spreadsheet.

01	<input type="checkbox"/>	Check the box if the project is showing ventilation calculations on the plans, or attaching the calculations instead of completing this table.
02	<input type="checkbox"/>	Check this box if the project included Nonresidential, Hotel/Motel Spaces or Multifamily Common Use Spaces
03	<input type="checkbox"/>	Check the box if the project is using natural ventilation in any nonresidential or hotel/motel spaces to meet required ventilation rates per 120.1(c)(2).

Nonresidential and Hotel/ Motel Multifamily Common Use Ventilation Systems

04	05	06	07
System Name	FC-1, 2	System Design OA CFM Airflow ¹	0
		System Design Transfer Air CFM	30
08	09	10	11
		12	13
		14	15
		16	17
Space Name or Item Tag	Mechanical Ventilation Required per 120.1(c)(3) ³ & 160.2(c)(3	# of Shower heads/ toilets	# of people ⁵
Occupancy Type ⁴	Conditioned Floor Area (ft²)	Required Min CFM	Provided per Design CFM
Dry Food Storage Room	Occupiable storage rooms for dry materials	200	30
17	Total System Required Min OA CFM	30	18
		Ventilation for this System Complies?	Yes

¹ FOOTNOTES: System CFM should include both mechanical and natural ventilation for the zone/system
² Air filtration requirements apply to the following three system types per 120.1(c)(1A): space conditioning systems utilizing ducts to supply air to occupiable space; supply-only ventilation systems providing outside air to occupiable space; supply side of balanced ventilation systems including heat recovery and energy recovery ventilation systems providing outside air to occupiable space.
³ Uniform Mechanical Code may have more stringent ventilation requirements; the most stringent code requirement takes precedence.
⁴ See Standards Tables 120.1-A and 120.1-B.

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 16350 Filbert Street Sylmar, CA 91342
Report Page: (Page 9 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

STATE OF CALIFORNIA
Mechanical Systems
CERTIFICATE OF COMPLIANCE
Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade
Project Address: 16350 Filbert Street Sylmar, CA 91342
Report Page: (Page 9 of 9)
Date Prepared: 2024-05-30T14:58:58-04:00

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT
I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Christopher Chen
Signature Date: 05/30/24
Address: 150 S Arroyo Parkway, Suite No. 100
City/State/Zip: Pasadena/CA/91105
Phone: 626-445-4580

RESPONSIBLE PERSON'S DECLARATION STATEMENT
I certify the following under penalty of perjury, under the laws of the State of California:
1. The information provided on this Certificate of Compliance is true and correct.
2. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer).
3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
4. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.
5. I will ensure that a completed signed copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections. I understand that a completed signed copy of this Certificate of Compliance is required to be included with the documentation the builder provides to the building owner at occupancy.

Responsible Designer Name: Kevin Chen
Company: dHA + CALPEC
Address: 150 S Arroyo Parkway, Suite No. 100
City/State/Zip: Pasadena/CA/91105
Date Signed: 05-30-2024
License: M-31154
Phone: 626-445-4580

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Schema Version: rev 20220101 Compliance ID: 202367-0524-0002 Report Generated: 2024-05-30 11:59:04

REVISIONS

NO.	DATE	BY	REVISIONS
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			

CERTIFICATE OF COMPLIANCE

NRCC-ENV-4

This document is used to demonstrate compliance with mandatory requirements in 110.8(g) and 120.7(b)/ 160.1 for newly constructed nonresidential, hotel/ motel, multifamily and mixed-use buildings, and 141.0(b)(1)/ 180.2 for alterations, related to roof, wall and floor assemblies. It is also used to demonstrate compliance with prescriptive requirements in 140.3/ 170.2 for newly constructed buildings, and 141.0/ 180.1/ 180.2 for additions and alterations, related to roof, wall, floor, door, fenestration and daylighting requirements.

Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade - Envelope

Report Page: (Page 1 of 6)

Project Address: 23990 LACDPW Barry J Nidorf Camp Security Upgrade - Envelope

Date Prepared: 2024-06-03T18:55:14-04:00

A. GENERAL INFORMATION

01	Project Location (city)	Sylmar	05	# of Stories (Habitable Above Grade)	0
02	Zipcode	91342	06	Total Conditioned Floor Area (ft²)	200
03	Climate Zone	9	07	Total Unconditioned Floor Area (ft²)	0
04	Occupancy Types Within Project: (select all that apply): If one occupancy constitutes >= 80% of the conditioned floor area, the entire building envelope may be designed to comply with the provisions of that occupancy (per 100.0(f)).		08	Project includes unconditioned enclosed space(s) > 5,000 ft² under a roof with a ceiling height of at least 15 ft.¹	<input type="checkbox"/>

• All Other Occupancies

¹ FOOTNOTE: Enclosed spaces > 5,000 ft² directly under roof with ceiling height > 15 ft in climate zones 2 through 15 are required to meet the minimum daylighting requirements defined in 140.3(c)/ 170.2(b). Compliance with 140.3(c)/ 170.2(b) is documented in Table L. This is the only prescriptive requirement which applies to unconditioned spaces.

B. PROJECT SCOPE

This table specifies project envelope components within the permit application demonstrating compliance using the prescriptive paths outlined in 140.3/ 170.2 and 141.0(a)(1)/ 180.1 and 141.0(b)(1) and 2/ 180.2 for additions and alterations.

My project consists of (check all that apply)		Component Types	
<input checked="" type="checkbox"/>	New Construction or Newly Conditioned Space	<input checked="" type="checkbox"/>	Roof
<input type="checkbox"/>	One or more enclosed spaces > 5,000 ft² directly under roof with ceiling height > 15ft	<input type="checkbox"/>	Walls
<input type="checkbox"/>	Addition of conditioned space	<input type="checkbox"/>	Floors
<input type="checkbox"/>	One or more enclosed spaces > 5,000 ft² directly under roof with ceiling height > 15ft	<input type="checkbox"/>	Walls
<input type="checkbox"/>	Addition is <= 700 ft²	<input type="checkbox"/>	Floors
<input type="checkbox"/>	Addition is > 700 ft²	<input type="checkbox"/>	Fenestration/ Glazed Doors¹
<input type="checkbox"/>	Alteration of conditioned space	<input type="checkbox"/>	Roof Assembly
<input type="checkbox"/>	One or more enclosed spaces > 5,000 ft² directly under roof with ceiling height > 15ft and lighting system installed for the first time	<input type="checkbox"/>	Walls
<input type="checkbox"/>		<input type="checkbox"/>	Floors
<input type="checkbox"/>		<input type="checkbox"/>	Fenestration

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 202523-0624-0003 Schema Version: rev 20220101 Report Generated: 2024-06-03 15:55:16

CERTIFICATE OF COMPLIANCE

NRCC-ENV-4

Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade - Envelope

Report Page: (Page 4 of 6)

Date Prepared: 2024-06-03T18:55:14-04:00

H. WALL ASSEMBLY SCHEDULE

This table demonstrates compliance with prescriptive wall assembly requirements in 140.3(a)/ 170.2(a) for new constructions, 141.0(a)/ 180.1 for additions and 141.0(b)(1)/ 180.2 for alterations.

01	Indicate wall types included in the project:¹	<input type="checkbox"/> Framed	<input checked="" type="checkbox"/> Mass (new only)	<input type="checkbox"/> Concrete Sandwich Panel (new only)	<input type="checkbox"/> SIPs	<input type="checkbox"/> ICF (new only)
		<input type="checkbox"/> Metal Panels	<input type="checkbox"/> Metal Building	<input type="checkbox"/> Spandrel/ Curtain Wall	<input type="checkbox"/> Straw Bale	<input type="checkbox"/> Log Home (new only)

¹ FOOTNOTES: Wall types indicated above as "new only" do not have Title 24, Part 6 requirements for alterations. New construction and additions do have requirements and should be clicked above and compliance demonstrated within this table.

Mass Walls (new walls only)

01	<input type="checkbox"/>	Calculate Area-Weighted Average U-factor for Mass Walls¹									
02	03	04	05	06	07	08	09	10	11	12	
Tag/Plan Detail ID	Occupancy Type	How Design U-factor was determined	Mass Information		Additional Insulation Information		Cavity Insulation per Design	Maximum U-factor Allowed²	U-factor per Design	Net Area³ ft²	
			Mass Material	Fill Options	Thickness (in)	Frame Material & Thickness					
General Notes #1	Nonresidential/ Relocatable 1 CZ	JAA Tables	CMU medium weight	Solid Grout	8 in			0.69	per JAA 4 per Software/ Other	0.65	

¹ FOOTNOTES: If any individual assembly is non-compliant, assemblies may show compliance using an area-weighted calculation. Mass walls are combined with concrete sandwich panel, log and ICF wall types. Mass walls must meet mandatory requirements in 120.7(b), but may area-weight to comply with prescriptive requirements in Table 140.3 for new construction.

² Mass walls are defined as "light" or "heavy" depending on their Heat Capacity. Heat Capacity is determined in Tables 4.3.5 and 4.3.6 in Joint Appendix 4. Walls with Heat Capacity of 15 or greater are "heavy" while walls with Heat Capacity from 7 to less than 15 are "light". Walls with heat capacity less than 7 would be categorized as "Wood framed and Other" for compliance purposes.

³ Wall area minus any fenestration area

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 202523-0624-0003 Schema Version: rev 20220101 Report Generated: 2024-06-03 15:55:16

CERTIFICATE OF COMPLIANCE

NRCC-ENV-4

Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade - Envelope

Report Page: (Page 2 of 6)

Date Prepared: 2024-06-03T18:55:14-04:00

B. PROJECT SCOPE

¹ FOOTNOTE: Doors that are more than 25% glass in area are considered Glazed Doors and should be documented on table K with fenestration.

² Roof recovers and replacements must also check "Roof Assembly" box and document compliance with insulation requirements in Table F. Roof recasts may document compliance with roof material only in Table G.

C. COMPLIANCE RESULTS

Results in this table are automatically calculated from data input and calculations in Tables F through L. Note: If any cell on this table says "COMPLIES with Exceptional Conditions" refer to Table D. Exceptional Conditions for guidance or see the applicable table referenced below.

Opaque Envelope Components					Fenestration	Daylighting Spaces > 5,000ft²	Compliance Results
Roof Assembly	Roofing Materials	Walls	Floors	Doors			
01	02	03	04	05	06	07	08
(See Table F)	(See Table G)	(See Table H)	(See Table I)	(See Table J)	(See Table K)	(See Table L)	
Yes	Yes	Yes					COMPLIES

D. EXCEPTIONAL CONDITIONS

This table is auto-filled with uneditable comments because of selections made or data entered in tables throughout the form.

E. ADDITIONAL REMARKS

01

This table includes remarks made by the permit applicant to the Authority Having Jurisdiction.

F. ROOF ASSEMBLY SCHEDULE

This table demonstrates compliance for prescriptive roof assembly requirements in 140.3(a)(1)/ 170.2(a)(1) for new construction, 141.0(a)/ 180.1 for additions, or 141.0(b)(2)/ 180.2 for alterations.

01	Indicate roof types included in the project: <input type="checkbox"/> Framed <input type="checkbox"/> Framed-Multifamily <input type="checkbox"/> SIPs <input checked="" type="checkbox"/> Span Deck & Concrete <input type="checkbox"/> Metal Panels <input type="checkbox"/> Metal Building
----	---

Span Deck And Concrete Roof Assemblies

01	<input type="checkbox"/>	Include Span Deck and Concrete Roof Assemblies in Area-Weighted Average U-factor Calculation¹
----	--------------------------	---

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 202523-0624-0003 Schema Version: rev 20220101 Report Generated: 2024-06-03 15:55:16

CERTIFICATE OF COMPLIANCE

NRCC-ENV-4

Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade - Envelope

Report Page: (Page 5 of 6)

Date Prepared: 2024-06-03T18:55:14-04:00

I. FLOOR ASSEMBLY SCHEDULE

This section does not apply to this project.

J. EXTERIOR DOOR SCHEDULE

This section does not apply to this project.

K. FENESTRATION AND GLAZED DOOR SCHEDULE

This section does not apply to this project.

L. DAYLIGHT IN LARGE ENCLOSED SPACES

This section does not apply to this project.

M. DECLARATION OF REQUIRED CERTIFICATES OF INSTALLATION

Selections have been made based on information provided in this document. If any selection have been changed by the permit applicant, an explanation should be included in Table E Additional Remarks. These documents must be provided to the building inspector during construction and can be found online

Form/Title

NRCC-ENV-01-E - Must be submitted for all buildings

N. DECLARATION OF REQUIRED CERTIFICATES OF ACCEPTANCE

There are no NRCA forms required for this project.

O. DECLARATION OF REQUIRED CERTIFICATES OF VERIFICATION

There are no forms required for this project.

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 202523-0624-0003 Schema Version: rev 20220101 Report Generated: 2024-06-03 15:55:16

CERTIFICATE OF COMPLIANCE

NRCC-ENV-4

Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade - Envelope

Report Page: (Page 3 of 6)

Date Prepared: 2024-06-03T18:55:14-04:00

F. ROOF ASSEMBLY SCHEDULE

Span Deck And Concrete Roof Assemblies

02	03	04	05			06
Tag/Plan Detail ID	Name/Description	Status	Exception to Roof Insulation Requirements in 141.0(b)(2)iii (Alts. Only)			Occupancy Type
General Notes #1	M-1.01	Altered	The area of the roof recast is not required to be insulated.			Nonresidential/ Relocatable 1 CZ

07	08	09	10	11	12	13	14	15
Tag/Plan Detail ID	How Design U-factor was determined	Fireproofing	Concrete Topping Thickness (in.)	Continuous Insulation per Design²	Thermal Performance Unit	Required Thermal Performance³	U-factor per Design	Net Area⁴ ft²
General Notes #1							per JAA 4 per Software/ Other	

¹ FOOTNOTES: If any individual assembly is non-compliant, assemblies may show compliance using an area-weighted calculation. Metal building roofs may not be combined with other roof types. The area-weighted compliance option is not available for alterations demonstrating compliance with R-values in Table 141.0-C.

² For alterations using U-factor as the Thermal Performance Unit, at least R-10 insulation must be above deck.

³ If "R-value" is shown in cell 13 as the Thermal Performance Unit, the R-value shown here is for continuous insulation per Table 141.0-C.

⁴ Roof area minus any fenestration/ skylight area

G. RATED ROOFING MATERIAL (COOL ROOF)

This table demonstrates compliance with prescriptive roof material requirements in 140.3(a)(1)/ 170.2(a)(1) for new construction, 141.0(a)/ 180.1 for additions, and 141.0(b)(2)/ 180.2 for alterations. Roof recovers and replacements must also document compliance with insulation requirements in Table F. Roof recasts may document compliance with roof material only in Table G.

01	02	03	04	05	06	07	08	09	10
Tag/Plan Detail ID	Name/ Description/ Location	Status	Occupancy Type	Roof Slope	Roof Material	Compliance Method	Required Minimum Material Performance	Designed Material Performance	U-factor / R-value of Assembly

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 202523-0624-0003 Schema Version: rev 20220101 Report Generated: 2024-06-03 15:55:16

CERTIFICATE OF COMPLIANCE

NRCC-ENV-4

Project Name: 23990 LACDPW Barry J Nidorf Camp Security Upgrade - Envelope

Report Page: (Page 6 of 6)

Date Prepared: 2024-06-03T18:55:14-04:00

DOCUMENTATION AUTHOR'S DECLARATION STATEMENT

I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Christopher Chen

Documentation Author Signature: C Chen

Company: dHA + CALPEC

Signature Date: 05/30/24

Address: 150 S Arroyo Parkway, Suite No. 100

City/State/Zip: Pasadena/CA/91105

Phone: 626-445-4580

RESPONSIBLE PERSON'S DECLARATION STATEMENT

I certify the following under penalty of perjury, under the laws of the State of California:

1. The information provided on this Certificate of Compliance is true and correct.

2. I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer).

3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.

4. The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with this building permit application.

5. I will ensure that a completed signed copy of this Certificate of Compliance shall be made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections. I understand that a completed signed copy of this Certificate of Compliance is required to be included with the documentation the builder provides to the building owner at occupancy.

Responsible Designer Name: Kevin Chen

Responsible Designer Signature: Kevin Chen

Company: dHA + CALPEC

Date Signed: 05-30-2024

Address: 150 S Arroyo Parkway, Suite No. 100

City/State/Zip: Pasadena/CA/91105

License: M-31154

Phone: 626-445-4580

Generated Date/Time: Documentation Software: Energy Code Ace

CA Building Energy Efficiency Standards - 2022 Nonresidential Compliance Report Version: 2022.0.000 Compliance ID: 202523-0624-0003 Schema Version: rev 20220101 Report Generated: 2024-06-03 15:55:16

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.



PROJECT :

BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT :

JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D



CONSULTANT :

23990
dHA + CALPEC
150 S. ARROYO PARKWAY
SUITE NO. 100
PASADENA, CA 91105
TEL: (626) 445-8580
FAX: (626) 445-8081

TITLE:

MECHANICAL TITLE
24

SCALE:

DATE: 02-04-25

DRAWN BY: dHA + CALPEC

CHECKED BY: KC/AI

SHEET NUMBER:

M-0.04




GENERAL NOTES

1. DRY FOOD STORAGE ROOM - NEW CONDITIONED SPACE WITHIN EXISTING CONCRETE BLOCK WALLS AND EXISTING CONCRETE ROOF DECK.

REFERENCE NOTES

- 1 REMOVE (E) DUCTWORK ACCESSORIES AND PATCH PENETRATIONS TO MATCH (E)WALLS AND ROOF

EXACT LOCATION, ELEVATION & SIZE OF EXISTING SHALL BE FIELD VERIFIED



PARTIAL ROOF PLAN - DEMO WORK

SCALE: 1/4"=1'-0"



1

GENERAL NOTES

1. DRY FOOD STORAGE ROOM - NEW CONDITIONED SPACE WITHIN EXISTING CONCRETE BLOCK WALLS AND EXISTING CONCRETE ROOF DECK.

REFERENCE NOTES

- 1 3/4" CD (TYP.)
2 3/4" CD DOWN & CONNECT TO THE TAIL PIECE OF THE LAVATORY.
3 REFRIGERANT PIPING UP TO CU-1 ON THE ROOF.
4 REFRIGERANT PIPING FROM FC-1.
5 REFRIGERANT PIPING FROM FC-2.
6 4" OSA DUCT UP TO THE ROOF WITH MANUAL DAMPER TO SET TO 30 CFM, TERMINATE 3' ABOVE THE ROOF WITH GOOSENECK AND 1/4" MESH SCREEN.



PARTIAL FLOOR AND ROOF PLAN - NEW WORK

SCALE: 1/4"=1'-0"

2

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.



LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
600 SOUTH FERNWOOD AVE. 2ND FLOOR
ALHAMBRA, CA 91803

PROJECT :

BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT :

JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D

SEAL :



CONSULTANT :

23990 dHA + CALPEC
150 S. ARROYO PARKWAY
SUITE NO. 100
PASADENA, CA. 91105
TEL: (626) 445-8580
FAX: (626) 445-8081

TITLE:

MECHANICAL FLOOR AND
ROOF PLAN

SCALE:



DATE: 02-04-25

DRAWN BY: dHA + CALPEC

CHECKED BY: KC/AI



SHEET NUMBER:

M-1.01



NOTES:

1. P=MAX LOAD ON ONE FRAME @ PIPES 300 lbs MAX
2. PAINT ALL EXPOSED STEEL



NOTES:

1. REFRIGERANT PIPING DIAGRAM SHOWN IS SCHEMATIC. PROVIDE AND INSTALL REFRIGERANT PIPING IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. SUBMIT MANUFACTURER'S WRITTEN APPROVAL OF REFRIGERANT PIPING DIAGRAM. SEE EQUIPMENT SCHEDULES FOR REFRIGERANT PIPING SIZES.



PROJECT :

**BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241**

LOCATION :

**16350 FILBERT STREET,
SYLMAR, CA 91342**

ARCHITECT :

 **JTC**
architects, inc

**65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006**

TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: **37603.0D**



CONSULTANT :

23990


 JHA + CALPEC

150 S. ARROYO PARKWAY
SUITE NO. 100
PASADENA, CA. 91105
TEL: (626) 445-8580
FAX: (626) 445-8081

TITLE:

MECHANICAL DETAILS

SCALE:	
DATE:	02-04-25
DRAWN BY:	dHA + CALPEC
CHECKED BY:	KC/AI
SHEET NUMBER:	



1. SCREENED ITEMS DENOTES EXISTING (E) EQUIPMENT TO REMAIN IN PLACE U.O.N.
2. BOUNDARY IN DASH-DOT-DOT-DASH LINES DENOTES THE SCOPE OF WORK ITEMS UNLESS NOTED OTHERWISE
3. ALL EXISTING DEVICE/BREAKERS/FEEDERS INFORMATION DATA REQUIRED SHALL BE VERIFIED BY CONTRACTOR PRIOR TO SUBMITTALS.
4. SWITCHGEAR PRODUCTS, INCLUDING LOW-VOLTAGE DISTRIBUTION TRANSFORMER ARE BASED ON THE SCHNEIDER ELECTRIC-SQUARE D PRODUCTS, UNLESS NOTED OTHERWISE.

1. SUBMITTALS SHALL INCLUDE ARC-FLASH WARNING LABEL, PERTAINING INDENTED ENERGY LEVEL AND PUE REQUIREMENTS FOR NEW PANELS.
2. ALL CIRCUIT BREAKERS SHALL BE 3 POLES - MCCB TYPE CIRCUIT BREAKER, UNLESS OTHERWISE NOTED.
3. MINIMUM CIRCUIT BREAKER AMPERE INTERRUPTING CAPACITY SHALL BE 10,000 AMPS FOR 208V/120V 3PH-4W BRANCH CIRCUIT PANEL BOARD, AND 14,000 AMPS FOR 480V/277V 3PH-4W LIGHTING PANELBOARD IF NONE IS SHOWN.
4. PROVIDE MAIN BRANCH CIRCUIT NUMBER FOR EACH PANELBOARD, GLUE ON STOKER NUMBER IS NOT ACCEPTABLE.
5. PROVIDE EQUIPMENT NAME PLATE FOR EACH EQUIPMENT; NAME PLATE SHALL BE SECURED WITH METAL SHEET SCREWS, GLUE ON ATTACHMENT NOT ACCEPTABLE.
6. FEEDER LEADS ARE SHOWN FOR CALCULATION PURPOSES ONLY AND SHALL NOT BE USED FOR BIDDING/MATERIAL TAKE-OFF.
7. PROVIDE FULLY RATED OVERLOAD PROTECTION DEVICE/CIRCUIT BREAKER SYSTEM. SERIES RATED CIRCUIT BREAKERS WILL NOT BE PERMITTED.
8. FUSES FOR MOTOR SERVICE DISCONNECT SWITCH SHALL BE TIME DELAY AND DUAL ELEMENT TYPE.
9. NEW PANEL SHALL HAVE ALL COPPER BUSBING.

1 PROVIDE MOUNTING HARDWARE AS REQUIRED AND NEW PERMANENT LABEL FOR NEW CIRCUIT BREAKER. FIELD VERIFY EXISTING BOARD FOR REQUIRED EQUIPMENT NEEDED.

PROJECT :

BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241

16350 FILBERT STREET,
SYLMAR, CA 91342



JTC
architects, inc.

TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

SEAL :



00 dHA + CALPEC

TITLE:





SCALE:

DATE:	02-04-25
-------	----------


DRAWN BY:	dHA+CALPEC
DATE: 07/11/2014	15:40

CHECKED BY:	KC/AI
SHEET NUMBER:	

E-0.02

<div><p>PLAN VIEW</p><p>ELEVATION VIEW</p><p>NOTES:</p><ol style="list-style-type: none">LOCATE EXIST REINFORCING STEEL IN CONCRETE PRIOR TO DRILLING. DO NOT CUT OR DAMAGE (E)REINFORCING STEEL.REFER TO STRUCTURAL ENGINEER FOR ACTUAL EMBEDMENT AND CONNECTIONS TO STRUCTURE.</div>			<div><p>NOTES:</p><ol style="list-style-type: none">REFER TO STRUCTURAL ENGINEER FOR ACTUAL EMBEDMENT AND CONNECTIONS TO STRUCTURE.</div>			<div><p>NOTES:</p><ol style="list-style-type: none">REFER TO ARCHITECTURAL DRAWINGS FOR FURTHER PENETRATION DETAILS.</div>		
TYPICAL CONDUIT SUPPORT DETAIL			TYPICAL PANELBOARD - CONCRETE / CMU WALL DETAIL			TYPICAL CONDUIT THROUGH ROOF DETAIL		
			<div><p>SYSTEM NO. W-L-1001</p><p>NOTES:</p><ol style="list-style-type: none">THE CAULK IS TO BE FORCED INTO THE ANNULAR SPACE TO THE MAXIMUM EXTENT POSSIBLE FLUSH WITH THE EXTERIOR OF THE PENETRATION SURFACE.FINISH CAULKING WITH A 1/4" (6mm) MINIMUM BEAD OF CP 25N/S CAULK APPLIED TO THE PERIMETER OF THE CONDUIT/PIPE AT IT EGRESS FROM THE WALL.THE MAXIMUM ANNULAR SPACE IS NOT TO EXCEED 3/16" (5mm). INSTALL 3M FIRESTOP ON BOTH SIDES OF WALL.THESE RECOMMENDATIONS ARE BASED ON PRODUCT PERFORMANCE PER ASTM E-814 (UL 1479) FIRE TEST AND UL THROUGH-PENETRATION FIRESTOP SYSTEM #147.<p>(FOR METAL CONDUIT)</p></div>					
NOT USED			THRU GYP. WALL BOARD PENETRATION FIRESTOP			NOT USED		
NOT USED			NOT USED			NOT USED		

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.



LOS ANGELES COUNTY
DEPARTMENT OF PUBLIC WORKS
900 SOUTH FREMONT AVE. 8TH FLOOR
ALHAMBRA, CA 91803

PROJECT :
**BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES
PW15739, PCA: P9700230,
PCS ID: 2241**

LOCATION :

16350 FILBERT STREET,
SYLMAR, CA 91342

ARCHITECT :

JTC
architects, inc.

65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: 37603.0D

SEAL :



CONSULTANT :

dHA + CALPEC
23990
150 S. ARROYO PARKWAY
SUITE NO. 100
PASADENA, CA 91106
TEL: (626) 446-8680
FAX: (626) 446-8081

TITLE:

ELECTRICAL DETAILS

SCALE:


DATE: 02-04-25

DRAWN BY: dHA+CALPEC


CHECKED BY: KC/AI

SHEET NUMBER:


E-0.03



2 PARTIAL MEZZANINE FLOOR PLAN - NEW WORK
SCALE: 1/4"=1'-0"



3 PARTIAL ROOF PLAN - NEW WORK
SCALE: 1/4"=1'-0"




1 FLOOR PLAN-NEW WORK
SCALE: 1/8"=1'-0"

- ### GENERAL NOTES
1. ALL EXTERIOR ELECTRICAL ENCLOSURES TO BE NEMA-3R RATED AND IN WEATHER-PROOF INSTALLATION RACEWAYS AND FITTINGS.
 2. PROVIDE UL-FIRE RATED AND WP-SEAL AT ALL ROOF PENETRATIONS.
 3. ALL EXTERIOR SERVICE DISCONNECTS TO BE HEAVY DUTY NEMA-3R RATED AND TO BE MOUNTED ON SEPARATE STRUCTURE, NOT ON HVAC EQUIPMENT. UON. SERVICE DISCONNECT SWITCH SHALL HAVE PERMANENT NAMEPLATES WITH EQUIPMENT IDENTIFICATION AND SERVING PANEL-CIRCUIT NUMBER.
 4. ALL EXTERIOR RECEPTACLES TO BE 20A-125VAC TAMPER RESISTANT, WEATHER RESISTANT TYPE, GFCI PROTECTED, AND IN EXTRA DUTY DIE-CAST METAL WEATHERPROOF OUTLET BOX WOODS (WHILE-IN-USE LOCKABLE ENCLOSURE). HVAC EQUIPMENT SERVICE RECEPTACLE AND TO BE LOCATED WITHIN 25' OF EQUIPMENT FOR SERVICE PURPOSES.
 5. PROVIDE LABEL (SERVING PANEL-CIRCUIT NUMBER) FOR NEW RECEPTACLE TO BE INSTALLED.
 6. ALL OUTDOOR/EXPOSED CONDUIT TO BE RIGID STEEL CONDUIT. PROVIDE INSULATED THROAT METALLIC BUSHINGS.
 4. MECHANICAL CONTROL CONTRACTOR TO PROVIDE ALL LOW VOLTAGE CONTROL CONNECTION (CONDUIT AND WIRES).
 5. FINAL CONNECTION TO HVAC EQUIPMENT SHALL BE IN MAX 5' FLEXIBLE METAL CONDUIT (INTERIOR) / FLEXIBLE LIQUID-TITE CONDUIT (EXTERIOR).
 6. FUSES FOR MOTOR SERVICE DISCONNECT SWITCH SHALL BE TIME DELAY AND DUAL ELEMENT TYPE.

- ### REFERENCE NOTES
1. PROVIDE MANUAL MOTOR STARTER WITH PILOT LIGHT AND HP-RATED THERMAL UNIT, EQUAL TO SQUARE D, CLASS 2510, TYPE FQ3P (2 POLE, 230VAC RATED, NEMA 1 ENCLOSURE). FIELD COORDINATE WITH MECHANICAL.
 2. PROVIDE 3/4\"/>
 3. FINISH AND INSTALL 600VAC, 30A/15A/5P FUSED DISCONNECT SWITCH IN NEMA-3R ENCLOSURE AND PROVIDE CONNECTION TO CU UNIT. DISCONNECT SWITCH SHALL BE MOUNTED ON UNISTRUT SUPPORT STRUCTURE ADJACENT TO ASSOCIATE UNIT SERVED. FIELD COORDINATE FOR EXACT LOCATION.
 4. NEMA 5-20R GFCI TAMPER RESISTANT, WEATHER RESISTANT TYPE SERVICE RECEPTACLE IN EXTRA DUTY WP-ENCLOSURE. PROVIDE 4\"/>

THESE DRAWINGS ARE THE PROPERTY AND COPYRIGHT OF JTC ARCHITECTS, INC. REUSE, REPRODUCTION OR PUBLICATION BY ANY METHOD IN WHOLE OR IN PART THEREOF WITHOUT THE EXPRESS WRITTEN CONSENT OF JTC ARCHITECTS, INC. IS NOT PERMITTED.



PROJECT :
**BARRY J. NIDORF
SECURE YOUTH TRACK FACILITY
SECURITY AND KITCHEN
UPGRADES**
PW15739, PCA: P9700230,
PCS ID: 2241


LOCATION :

**16350 FILBERT STREET,
SYLMAR, CA 91342**

ARCHITECT :

**JTC
architects, inc.**
**65 NORTH FIRST AVE., SUITE 201
ARCADIA, CA 91006**
TEL : 626-254-8884 FAX : 626-574-7775
E-MAIL : jtcarch@pacbell.net

JTC PROJECT NO: **37603.0D**



CONSULTANT :

dHA + CALPEC
23990
**150 S. ARROYO PARKWAY
SUITE NO. 100
PASADENA, CA 91106**
TEL: (626) 446-8880
FAX: (626) 446-8881

TITLE:

FLOOR PLAN-NEW WORK

SCALE:
DATE: **02-04-25**
DRAWN BY: **dHA+CALPEC**
CHECKED BY: **KC/AI**
SHEET NUMBER:

E-2.01