

Marina Del Rey 18-inch Waterline Replacement, Phase IIIA

The Los Angeles County Department of Public Works, on behalf of the Marina del Rey Water System, is proposing to install approximately 957 linear feet of new 18-inch diameter steel pipeline to replace the existing aged and undersized 12-inch- diameter water mains that currently form a loop around Marina del Rey. The purpose of the project is to improve the Marina del Rey Water System to meet domestic and fire protection water demands. Water main will be installed along Via Marina between Panay Way and Marquesas Way. Several fire hydrants, water system laterals, and appurtenances will be improved as well.

This project is the first part of the third and final phase scheduled to replace the existing Marina del Rey Water System. Construction of the project was completed in June 2013.

